



WASHINGTON STATE DEPARTMENT OF
Natural Resources
Peter Goldmark - Commissioner of Public Lands

Olympic Region

INVITATION TO BID

Contract Number # 1304

Contract Digest: TREE PLANTING
(Professional tree planting contract that ensures maximum seedling survival and stocking requirements are met.)

Notice to Bidders
Definitions

SECTION I

A. Instructions to Bidders and Contract Award

SECTION II

A. General Provisions
B. Specifications for the Activity
C. Compliance Inspection and Payments

SECTION III

A. Unit Description Summaries
B. Unit Maps
C. Vicinity Maps

SECTION IV

A. Bid Form Requirements and Bid Form

SECTION V

A. Offer and Contract Award

NOTICE TO BIDDERS

You are invited to bid on this contract and are advised to examine the planting units prior to bidding.

Sealed bids will be accepted at the Department's Olympic Region office until 2:00 p.m. on Thursday, January 6th, 2011 at which time and place all bids will be opened and read aloud. Individuals who wish to request special accommodations for the bid opening (e.g., sign language, interpreters, Braille, etc.) should contact the Department ten (10) Working days prior to the scheduled bid opening.

The sealed bid envelope should be prepared in the following manner:

Addressed to: Susan K. Trettevik, Region Manager
Washington State Department of Natural Resources
Olympic Region
411 Tillicum Lane
Forks, WA 98331

Upper left corner: Bidder's Address

Lower left corner: Tree Planting – “Sealed Bid”
Invitation to Bid/Contract Number: 1304

Tree Planting Contract #1304 (1,722 acres) is divided into two items. Item A (875 acres) includes planting units in west Clallam and west Jefferson Counties with a contract period from January 19th, 2011 through March 31st, 2011. Item B (847 acres) includes planting units in east Clallam and east Jefferson Counties with a contract period from February 1st, 2011 through March 31st, 2011. Minimum crew size is 10 planters.

Questions pertaining to this Invitation to Bid and can be answered by contacting John Keller by phone at 360-640-1730 or by e-mail at john.keller@dnr.wa.gov. Oral explanations, interpretation, or instructions given before the award will not be binding.

Bidders may temporarily obtain DNR gate keys for planting unit inspection prior to bidding through the Olympic Region Office. Call first at 360-374-2800 to make arrangements.

The Department reserves the right to amend this Invitation to Bid/Contract by giving written notification to all known bidders at least seven (7) days prior to bid opening.

DEFINITIONS

- A. 'Compliance Forester' means the Department staff who perform the compliance inspections, approves Work, recommends payment to the Contract Manager, manages the Work Schedule, and assists with seedling distribution.
- B. 'Contract' means this Invitation to Bid/Contract the Pre-Work Conference packet and all required documents provided by the contractor.
- C. 'Contract Manager' means the Department staff that processes this Contract, makes payments, provides and facilitates dispute resolution, provides technical advice to the Compliance Forester, and is the first point of contact for questions relating to this Contract or interpretation of Work. The Contract Manager may perform the duties of the Compliance Forester.
- D. 'Contractor' means the bidder who was awarded this Contract.
- E. 'Department' means the Department of Natural Resources of the State of Washington, acting through an authorized employee.
- F. 'Designated Contract Representative(s): Those individuals designated by the Contractor on the Pre Work form during the Pre Work Conference (2-11, 2-12)
- G. 'Force Majeure' means those acts that are unforeseeable and beyond the control of either party to the Contract. Acts of Force Majeure include, but are not limited to: acts of God, the public enemy, fire, or other casualty. Force Majeure may result in an equitable adjustment in the time period to complete the Contract.
- H. 'Item' means the smallest category of area that can be awarded to one contractor. This contract can be a roll-up of a large geographic area and Items are used for award purposes to identify to the contractor what portions of this contract their specific award is for.
- I. 'Planting Stock', 'Trees', 'Seedlings', 'Trees Planted', are interchangeable terms in this contract meant to identify Tree Seedlings to be planted under the terms of this contract. Multiple forms of reference exist in this contract in order to conform with standard industry terminology.
- J. 'Pre-Work Conference' is the meeting between the department and the contractor after award of the contract is made but prior to commencement of work. Items agreed upon in this meeting are signed off by both the department and the contractor and become part of the contract.
- K. 'Region Manager' means the designated Department staff responsible for managing the affairs of the Department in designated large geographic areas. The Region Manager may perform the duties of the Contract Manager.
- L. 'Unit' is the individual geographical area that the Work is to be done on. Each unit is specifically identified by number on the Bid Form (Section IV), the Unit Description Summary and corresponding Unit Map (Section III).
- M. 'Work Schedule' means the approved timeline for how the requirements of this contract will be fulfilled by the contractor. The work schedule is agreed upon during the Pre-Work Conference by both the department and the contractor.
- N. 'Work' means the services the Contractor is required to satisfactorily complete this Contract found in Section II Specifications for the Activity and Section III Unit Description Summary.
- O. 'Unit Bid Price' is the rate per acre or per 1000 trees written in the Unit Bid Price column of the bid form (Section IV Bid Form).

SECTION I: INSTRUCTIONS TO BIDDERS AND CONTRACT AWARD

Bid Preparation

1-01 Unit Inspection

Bidders are expected to examine this entire Invitation to Bid/Contract and are urged to inspect the Unit(s) prior to submission of their bid. Bidder acknowledges through submission of their bid that it has ascertained the nature and location of the Work and investigated and satisfied itself as to the general and local conditions which can affect the Work or its cost, including but not limited to:

- A. Conditions bearing upon transportation, disposal, handling, and storage of materials;
- B. The availability of labor, water, electric power, and road;
- C. Uncertainties of weather, river stages, tides, or similar physical conditions at the Unit;
- D. The confirmation and conditions of the ground;
- E. Seasonal conditions that may affect the timing and use of materials needed for the Work;
and
- F. The character of equipment and facilities needed to complete the Work.

Bids should include all costs, any failure of the bidder to examine the Invitation to Bid/Contract or the Unit(s) prior to submission of the bid will not relieve the bidder from responsibility for properly estimating the cost of satisfactorily completing this contract.

Bid Submission

1-03 Offer to Contract

Your bid in response to this Invitation to Bid/Contract is an offer to contract with the Department. All offers shall remain firm for a period of 90 calendar days after the bid opening. If there is a problem and the lowest responsible bidder is unable to accept this contract the next lowest responsible bidder will be contacted for possible award. An Invitation to Bid becomes a contract when officially awarded by the Department with the return of a countersigned SECTION V - Offer and Contract Award.

1-05 Bid Contents

The bid shall include the Bid Form (Section IV), the Offer and Contract Award Form (Section V) properly completed and signed, the bid deposit specified in Clause 1-09, Contractor's Declaration of Industrial Insurance Status, and a photocopy of bidder's Washington State Farm Labor Contractors License.

1-07 Withdrawal of Bid

A bid may be withdrawn in person by a bidder's authorized representative before the opening of the bids. Bidder's representative(s) will be required to show ID and sign on the bid summary sheet before it will be released.

1-08 Rejection of Bids

To be considered, bids should conform to the above requirements, except that the Department may waive informalities and minor irregularities in bids received. The Department reserves the right to reject any or all bids received.

Bid and Performance and Damage Deposit

1-09 Bid Deposit

A bid deposit of ONE THOUSAND DOLLARS (\$1,000) is required. This deposit assures the Department that the bidder will accept award of any items on which the bidder is the lowest responsible bidder. In the event the bidder rejects award of **any item**, the bidder will forfeit the bid deposit. The bid deposit must be in the form of certified check made payable to the Washington State Department of Natural Resources and include a reference to the bid/contract number. The bid deposit must be delivered to the Department's Region Office with the delivery of the bid (Clauses 1-04 and 1-05). The bid deposit of a bidder awarded the contract will be released when the performance/damage deposit has been approved, or the bid deposit may be converted to apply to part or all of the required performance/damage deposits after contract award. Once all the bids are evaluated and the contract has been awarded, bid deposits will be returned to all unsuccessful bidders.

1-10 Performance and Damage Deposit

The bidder awarded the Contract (Contractor) agrees to furnish a performance and damage deposit of ten percent (10%) of the Contractor's total award established in the award letter. The deposit shall be in the form of certified check or cashiers check made payable to "Washington State Department of Natural Resources", irrevocable letter of credit, or a savings account assignment. This deposit guarantees performance of this Contract and payment of damages caused by operations during the performance of this Contract or resulting from Contractor's noncompliance with any contract provisions or the law. In the event the Department needs to utilize the deposit, Contractor shall replace the portion(s) by the due date indicated on the written notification from DNR.

Award of Contract

1-11 Lowest Responsible Bidder

Award of this Contract shall be to the lowest responsible bidder as determined by the Department. In determining the lowest responsible bidder, in addition to price, the following may be considered: (a) the ability, capacity, and skill of the bidder to perform the contract; (b) the character, integrity, reputation, judgment, experience, and efficiency of the bidder; (c) whether the bidder can perform the contract within the time specified; (d) the quality of performance of previous contracts; and (e) the previous and existing compliance by the bidder with laws relating to the contract or services. The Department's determination that a bidder is not qualified shall result in rejection of the bid submitted.

1-12 Award Letter

The Department will make every effort to mail an award letter with instructions and a copy of the executed contract to the successful bidder within ten (10) business days of bid opening.

1-13 Conditions on Award

Within ten (10) business days after the bidder receives their award letter, the Department must receive the signed contract, the performance and damage deposit, and insurance certificate at the

Department's Region Office (Page 2 Notice to Bidders). The Department may extend upon written request to the Contract Manager, the time allowed for receipt of the above items. If the bidder fails to submit the above items within the time specified, the Department may consider the contract award rejected and may terminate award of the contract.

1-14 Contract Modification or Cancellation

The Region Manager reserves the right to modify or cancel this Contract in part or whole without cause. The Contractor shall be paid only for Work performed satisfactorily prior to cancellation of the Contract.

SECTION II -A: GENERAL PROVISIONS

Legal Responsibilities

2-01 Compliance with all Laws

The Contractor shall comply with all laws and regulations of the United States, State of Washington, and counties where the Work is located. The Contractor will make any payments, contributions, remittances, and reports or statements required under those laws.

2-02 Licenses and Permits

The Contractor shall, without additional expense to the Department, obtain all required licenses and permits necessary for executing the Contract.

2-03 Indemnification and Hold Harmless

To the fullest extent permitted by law, Contractor shall indemnify, defend, and save harmless the State, agencies of the State, and all officers and employees of the State, from and against any and all claims for injuries or death, including claims by Contractor's employees, or for damages arising out of, resulting from, or incident to Contractor's performance or failure to perform the Contract. Contractor's obligation to indemnify, defend and save harmless shall not be eliminated or reduced by any alleged concurrent negligence of the State or its agencies, employees, and officers. Contractor waives its immunity under Title 51 RCW to the extent required to indemnify, defend, and save harmless the State and its agencies, officers, or employees.

2-04 Insurance

Before commencing Work, the Contractor shall obtain and keep during the term of this Contract the following liability insurance policies, insuring Contractor against liability arising out of its operations, including use of vehicles. Failure to buy and maintain the required insurance may result in termination of the Contract. The limits of insurance, which may be increased by the Department as deemed necessary, shall not be less than as follows:

- A. **Commercial General Liability (CGL) insurance**, with a limit of not less than \$1,000,000 per each occurrence. If such CGL insurance contains aggregate limits, the general aggregate limits shall be at least twice the "each occurrence" limit, and the products-completed operations aggregate limit shall be at least twice the "each occurrence" limit.
- B. **Employer's liability ("Stop Gap") insurance**, and if necessary, commercial umbrella liability insurance with limits not less than \$1,000,000 each accident for bodily injury by accident or \$1,000,000 each employee for bodily injury by disease.
- C. **Business Auto Policy (BAP) insurance**, and if necessary, commercial umbrella liability insurance with a limit of not less than \$1,000,000 per accident, with such insurance covering liability arising out of "Any Auto."

All insurance must be purchased on an occurrence basis and should be issued by companies admitted to do business within the State of Washington and have a rating of A- or better in the most recently published edition of Best's Reports. Any exception shall be reviewed and approved in advance by the Risk Manager for the Department. If an insurer is not admitted, all insurance policies and procedures for issuing the insurance policies must comply with Chapters 48.15 RCW

and 284-15 WAC.

The “State of Washington, Department of Natural Resources, its elected and appointed officials, agents and employees” shall be named as an additional insured on all general liability, excess, and umbrella insurance policies.

Before using any rights granted herein, Contractor shall furnish the Department with a certificate(s) of insurance, executed by a duly authorized representative of each insurer, showing compliance with the insurance requirements specified above. Certificate(s) must reference the Contract Number 1304 in the time required by Clause 1-13.

The Contractor shall provide the Department written notice before cancellation or non-renewal of any insurance referred to herein, as prescribed in statute (RCW Title 48).

All insurance provided in compliance with this Contract shall be primary as to any other insurance or self-insurance programs afforded to or maintained by State. Contractor waives all rights against State for recovery of damages to the extent these damages are covered by general liability or umbrella insurance maintained pursuant to this Contract.

By requiring insurance herein, State does not represent that coverage and limits will be adequate to protect Contractor and such coverage and limits shall not limit Contractor’s liability under the indemnities in this Contract.

2-05 Safety Compliance

Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Work.

- A. During the Contract performance, Contractor shall protect the lives and health of employees performing the Work and other persons who may be affected by the Work and prevent damage to property at the Unit and adjacent property. Contractor shall comply with all applicable laws, ordinances, rules, regulations, and orders of any public body having jurisdiction for the safety of persons or property; shall protect from damage, injury, or loss; and shall erect and maintain all necessary safeguards for such safety and protection.
- B. In an emergency affecting the safety or life of employees or adjoining property, Contractor is permitted to act to prevent threatened loss or injury. Within 24 hours of any emergency, Contractor shall notify the Compliance Forester. If directed by the Compliance Forester, within five (5) business days of any emergency. Contractor shall prepare an incident report and submit it to the Department’s Region manager within five (5) business days following an emergency if directed to do so by the Compliance Forester.

2-06 Venue

Disputes arising under this Contract shall be brought in the State of Washington and the venue shall be Thurston County.

2-07 Dispute Resolution

Before initiating any litigation over the terms of this Contract, the Contractor commits to the following process:

- A. Any concerns or disputes which the Contractor has relating to this Contract shall first be brought to the attention of the Compliance Forester.

- B. If the Compliance Forester is unable to resolve the dispute to the Contractor's satisfaction, the Contractor will notify the Contract Manager in writing, with specificity, of his dispute. The Contract Manager will provide a written response within ten (10) business days.
- C. If the Contractor is not satisfied with the Contract Manager's response, he will notify the Region Manager in writing of his dispute. The Region Manager will review and set a meeting with the Contractor within fifteen (15) business days, unless the Contractor agrees to a longer period. After the meeting, the Region Manager will provide a written response.

Subcontracting

2-08 The Contractor shall not enter into any subcontract or assignment of this Contract.

Nondiscrimination

2-09 During the performance of this Contract, the Contractor shall comply with all federal and State nondiscrimination laws, regulations, and policies.

2-10 In the event of Contractor's noncompliance or refusal to comply with any nondiscrimination law, regulation, or policy this Contract may be rescinded, canceled, or terminated in whole or in part, and the Contractor may be declared ineligible for further contracts with the Department. The Contractor shall be given a reasonable time to cure this noncompliance.

Contract Work Procedure

2-11 Pre-Work Conference

The Contractor shall attend a Pre-Work Conference before beginning Work. The Compliance Forester will notify the Contractor of the time and place of the Pre-Work Conference.

2-12 Purpose of the Pre-Work Conference

The purpose of the Pre-Work Conference is to document the following on the Pre-Work Conference form:

- A. All required documentation as outlined in sections I and II of the contract have been received from the Contractor, such as insurance forms, prior to beginning Work on this Contract.
- B. Name(s) and contact information for the Contractor and Designated Contract Representative(s), including all personnel authorized to sign unit completion forms and payment invoices.
- C. Names(s) and contact information for the Contract Manager and Compliance Forester(s).
- D. The Work plan of operations including the order and time frame in which Work will occur on individual units or groups of units within this Contract.
- E. Time interval(s) at which units will be processed for payment.
- F. Clarification of any unique requirements or conditions of the Work within this Contract prior to commencing Work.

2-13 Work Delay

Contractor shall promptly notify the Compliance Forester of any actual or anticipated event which is delaying or could delay the Work, including the expected duration of the delay, the anticipated effect of the delay on the schedule, and the action being or to be taken to correct the

delay. The notification does not relieve Contractor of the obligation to complete the Work within the time required by this Contract.

2-14 Non-conformances with Work Schedule

If Contractor is not in conformance with the Work schedule for reasons other than acts of Force Majeure, Contractor shall bring its activities into conformance with the schedule or request the Compliance Forester to revise the Work schedule. The Compliance Forester may require a meeting to determine if a revision is necessary. In the event the Contractor stops Work or if the initial start-up is delayed for a period of one (1) week or more, a new Pre-Work Conference may be held.

2-15 Work Days

Work shall only proceed on regular Monday through Friday business days. Work on weekends or designated State holidays requires written permission from the Compliance Forester.

2-16 Breach of Contract

Nonperformance, unsatisfactory performance, or willful violation of Contract requirements by the Contractor shall constitute breach of contract and the Department may collect liquidated damages, terminate the contract with forfeiture of the performance and damage deposit, or declare breach of contract and make a claim for actual damages suffered by the Department. Any delay or failure of performance by the Department or Contractor, other than the payment of money, shall not constitute a breach if the cause was Force Majeure.

Fire Responsibility

2-17 Washington State Forest Fire Protection Requirements

The Contractor and employees shall be familiar with the Washington State Forest Fire Protection Requirements and adhere to them. These requirements are found in:

[Revised Code of Washington Chapter 76.04](#)

2-18 Inspection

The Department may inspect the Units for adherence to regulations and presence of fire tools. Any inspection by the Department shall not limit Contractor's liability for failure to adhere to applicable regulations.

2-19 Spark Arresters

All spark emitting engines will be equipped with approved spark arresters. Spark arresters are approved by contractors demonstration to the Compliance Forester as to functionality and serviceability onsite, prior to use of the device. The lists adopted by the agency are from the National Wildfire Coordinating Group (NWCG).

[NWCG approved spark arrestor lists.](#)

2-20 Open Fires

The Contractor shall not build any open fires on the contract area without first obtaining written permission from the Compliance Forester.

Merchantable Products

2-21 Prohibition from Removal

Contractor is prohibited from removing merchantable or potentially merchantable products from the Units. A separate agreement with the Department is required for removal of Christmas trees, boughs, brush pickings, decorative shrubs or trees, firewood, poles, posts and other merchantable or potentially merchantable material.

Garbage

2-22 Contractor shall dispose of garbage brought onto State lands in garbage disposal areas meeting all State, county, and local requirements. Garbage includes equipment maintenance, abandoned equipment, containers, and other expended materials.

Camping

2-23 Contractor is prohibited from using or authorizing its employees to use non-designated State lands, landings, or roads for camping.

Section II-B: Specifications for the Activity

2-24 Precedence between Sections

Section II-B covers the general standards that apply over the whole contract. If a change is required on a site by site basis those differences will be outlined on the Unit Description Summary (Section III-A). The site specific details found on the Unit Description Summary should take precedence over these general guidelines when they exist.

2-25 Workers, Supervision and Equipment

The Contractor shall provide:

- A. All Workers meeting the minimum crew size identified in Section III- Unit Summary and discussed at the Pre-Work Conference;
- B. Adequate crew supervision, including at least one qualified non-planting, English speaking foreperson per ten (10) person crew, unless otherwise allowed by the Compliance Forester. The foreperson must have one season (at least three (3) months) of tree planting experience. Documentation of a foreperson’s experience shall be provided to the Department upon request; and
- C. Specific tool requirements are detailed in Section III-Unit Summary.
- D. Vehicle where seedlings are transported in a covered, unheated compartment, such as an enclosed truck or pickup with canopy. Tarps are not acceptable covering for transport. Shelving or sufficient floor space shall be available so that seedling containers are not stacked more than five high without intermediate support.

2-26 Seedling Supply

The Department will supply Seedlings. If the Department’s supply of Seedlings is temporarily interrupted, it could cause a delay for the Contractor. If needed, the Contract will be extended to permit completion, pursuant to Clause 2-14.

2-27 Substitution of Type of Seedling Stock Types

If the Department substitutes seedlings, adjustment of the per acre or per thousand unit bid price will be made based on the stock type of the new seedlings pursuant to the following schedule:

Stock Type as Per Bid Invitation	Stock Type To Be Substituted	Percent Adjustment
1+1 or P+1 or P+1/2 Or 2+0 or 1+0 or P+0(> 10in ³)	P+0 (≤ 10in ³)	-10%
P+0 (≤ 10in ³)	1+1 or P+1 or P+1/2 Or 2+0 or 1+0 or P+0 (> 10in ³)	+10%
1+1 or P+1 or P+1/2 Or 2+0 or 1+0 or P+0(> 10in ³)	1+1 or P+1 or P+1/2 Or 2+0 or 1+0 or P+0(> 10in ³)	No adjustment

Table 1: Substitution of Seedling Stock Types

In the event that more than one stock type of seedlings are required for a planting unit, the

adjustment in unit bid price will be prorated based on the acreage planted with each stock type. In such cases, the entire Unit will use the adjusted price.

2-28 Weather Conditions

Planting operations will be halted when the Compliance Forester determines weather conditions are injurious to the seedlings. These determinations will be made on site and communicated verbally. Weather conditions during which the Department may not allow planting include but are not limited to:

- A. Air temperature of less than 32 degrees F (32°F) or greater than 65 degrees F (65°F);
- B. Wind velocity greater than twenty (20) miles per hour;
- C. Soil frozen more than one-half (1/2) inch deep;
- D. Snow cover greater than two (2) inches; or
- E. Less than 50 percent Relative Humidity (RH).

2-30 Seedling Care During Transportation and Handling

The Contractor shall comply with the following specifications for seedling care during transportation and handling:

- A. Seedling containers shall be carefully handled at all times. No throwing, dropping, crushing, etc.
- B. Containers of seedlings shall be shaded from the sun and shielded with a reflective tarp from drying winds.
- C. Containers of seedlings shall be stored in a manner that will provide air circulation around each container. When containers are stored in snow banks, snow shall be placed around each container.
- D. Seedlings will be distributed to the workers so that no more than one container of seedlings will be open at the assembly point at one time.
- E. Opened seedling containers shall be immediately resealed. The Contractor shall supply tape and/or stapler to reseal and have them available on the Work site at all times.
- F. Seedlings carried by a worker shall be in a planting bag and arranged for easy removal of one seedling at a time. Planting bags shall not be overfilled. Seedlings should be placed in planting bags without shaking or removing soil from the roots. Seedlings should be placed in the planting bag by cupping the roots and guiding the roots into the bag. Seedlings should not be grabbed at the root collar and stuffed into the planting bag.
- G. Seedlings shall not be removed from the planting bag before a planting hole has been prepared.
- H. Seedlings shall be planted as received without pruning or culling, unless directed to do so by the Compliance Forester.
- I. If mold, dry roots, freezing, dying, or evidence of other injury is observed, the condition shall be immediately reported to the Compliance Forester.
- J. At the end of the Work day, seedlings which have been distributed but not planted shall be sealed and returned to the cooler.

K. Contractor shall keep seedlings free from damage at all times, including but not limited to: drying, heating, smothering, freezing, drowning, or mechanical injury.

2-31 Line Planting Method

The “line” method of planting will be used by planting crews, unless otherwise permitted by the Compliance Forester. Each planter will only plant one (1) line at a time on each pass. Each line will be at the “Average Spacing” given in Clause 2-32A.

2-32 Spacing and Number of Seedlings

Seedlings shall be planted as follows:

A. Specified Average Spacing

Seedlings shall be planted over the Unit at an average spacing (see table below) which will meet the Unit Description’s specifications for seedlings required per acre after planting.

Table 2: Average Spacing Table

Seedlings Required Per Acre After Planting	Maximum Planting Spots Allowed Per Inspection Plot	Average Spacing (Feet)
100	2	20.9 x 20.9
150	3	17.0 x 17.0
200	4	14.8 x 14.8
250	5	13.2 x 13.2
300	6	12.0 x 12.0
350	7	11.2 x 11.2
400	8	10.4 x 10.4
450	9	9.8 x 9.8
500	10	9.3 x 9.3
550	11	8.9 x 8.9
600	12	8.5 x 8.5
650	13	8.2 x 8.2
700	14	7.9 x 7.9
750	15	7.6 x 7.6

B. Variation to Specified Average Spacing

The spacing of individual seedlings may vary within the limits of the minimum seedling distance where needed to locate a planting spot, so long as average spacing is maintained.

D. Minimum Seedling Distance

Seedlings shall not be planted closer than the minimum seedling distance specified in the Unit Description Summary (Section III) from:

1. Another Contractor planted seedling;
2. An acceptable natural seedling; or
3. An acceptable previously planted seedling.

Acceptable natural or previously planted seedlings are conifer seedlings which are at least six (6) inches tall, well formed, and vigorous.

2-33 Planting Spots

Where available, Seedlings shall be planted near stumps, logs, dead brush, or other dead shade to provide protection from animal damage, drying winds, and solar radiation.

2-34 Plantable Spots

The number of plantable spots available will be calculated for each inspection plot (2-38) as follows: Maximum allowable planting spots (Clause 2-32(A) - Table 2: Average Spacing Table) per inspection plot minus unplantable spots. Unplantable spots are those that do not meet the conditions for clearing in 2-35A or are closer than the minimum distance specified in the Unit Description Summary (Section III).

2-36 Satisfactorily Planted Seedlings

Seedlings must meet the following criteria to be considered satisfactorily planted. Satisfactorily Planted Seedlings are used in the analysis of the compliance inspection 2-37 done by the Compliance Forester and are used to determine payment for Work completed (Clause 2-41).

A. Preparation of Planting Spot

Preparation for planting a seedling shall include the clearing and/or scalping to mineral soil to a minimum diameter of one (1) foot located as near the center of the planting spot as is practicable.

- i. 'Clearing' means the removal of duff up to eight (8) inches deep, loosely compacted slash up to two (2) feet deep, and other accumulations such as rock, rotten wood, snow, and ice which can be removed by kicking, dragging, or the use of a planting tool.
- ii. 'Scalping' means the removal of sod and vegetation less than two (2) feet tall with a base diameter of one-fourth (1/4) inch or less.

B. Planting Hole Location and Preparation

Planting shall be as follows:

- I. The planting hole shall be located in mineral soil and as near the center of the planting spot as is practicable;
- II. The planting hole shall be vertical, broken out on three sides, and shall be wide and deep enough to fully accommodate the roots of the trees being planted; and

C. Seedling Placement in Planting Hole

Tree placement shall be as follows:

- I. All seedlings shall be suspended near the center of the planting hole with the roots in a near natural arrangement;
- II. Seedlings shall be at a depth that after filling, packing and leveling, the soil comes to a point midway between the top lateral roots and the lower needles or branches;
- III. The roots shall not be doubled up, twisted, tangled, or bunched;
- IV. Moist mineral soil shall be filled in and firmly packed around roots. The seedling should not pull loose after a firm tug on the main stem; and
- V. The planted seedling shall have the main stem and roots vertical and free to grow.

SECTION II-C: COMPLIANCE INSPECTION AND PAYMENT

Compliance Inspection

2-37 Field Inspections

The Compliance Forester will conduct periodic inspections. Inspection plot Work may be done concurrently with planting Work but will be completed no later than five (5) business days after Work completion on the Unit.

2-38 Inspection Plots

The Compliance Forester will use inspection plots using the criteria specified in the Unit Description Summary (Section III) and the Specifications (section II) to determine the Contractor's seedling planting performance rating (Clause 2-39). Inspection plots shall be circular and have a one fiftieth (1/50) acre radius. The seedling planting performance rating will be determined from a minimum sample of five (5) plots, or two (2) plots for every five (5) acres of unit, whichever is more. The inspection plots will be well distributed over the Unit. The Compliance Forester will examine each inspection plot and record:

- A. **Plantable Spots.** The number of planting spots available under clause 2-34.
- B. **Trees Planted Per Acre.** If a unit is being paid by number of trees planted, the number of Contractor planted trees within the inspection plot will be:
 - From the inspection plot data, the Department will calculate the average number of trees planted per acre. The average number of trees planted per acre multiplied by the number of acres completed equals the total number of trees planted. Large openings, roads, and buffer zones have been deducted from the gross acreage and are designated on the Unit Map (Section III).
- C. **Satisfactorily Planted Seedlings.** The total number of Contractor planted seedlings that meet all applicable specifications of the Unit Description Summary (Section III) and Clause 2-36.
- D. **Dropped or Wasted Seedlings.** The Compliance Forester will record the number of dropped and wasted seedlings found during the inspection of the Unit.

2-39 Seedling Planting Performance Rating

The rating of seedling planting performance will be expressed as a percent and will be calculated using the sum (or aggregate) of all inspection plots in a Unit. The total of all recorded values for Satisfactorily Planted Seedlings (Clause 2-36) divided by the total of all recorded values for Plantable Spots (Clause 2-34), multiplied by one hundred (100), equals the seedling planting performance rating percent:

$$\frac{\text{Total Satisfactorily Planted Seedlings}}{\text{Total Plantable Spots}} \times 100 = \text{Planting Performance Rating \%}$$

Determination of Payment

2-40 Boundaries

The boundaries depicted on Unit Map (Section III) delineate the planting area. Failure to complete Work to boundaries established by the Department renders Work in that Unit unsatisfactorily completed. The planting boundaries will consist of easily identifiable features (including but not limited to roads, streams, or abrupt changes in forest type or age). Flagging will be used for areas where identifiable features are absent. The Contractor is responsible for understanding the location of all boundaries. No consideration will be given for Work that extends beyond Unit boundaries. If Work extends beyond Unit boundaries, charges may be levied against the Contractor by the Department for damages suffered.

2-41 Determination of Payment

The acceptability and the rate of pay for planting Work performed will be based on the Seedling Planting Performance Rating (Clause 2-39). The Compliance Forester's inspection will determine the rating.

- A. **Satisfactory Planting Performance:** The Work will be satisfactory if the seedling planting performance rating is between 92 percent and 105 percent.
- B. **Rate of Pay:** The rate of pay is the Unit Bid Price (Section IV). The rate of pay will not exceed the per-acre or per-thousand rate of the Unit Bid Price.
- C. **Unsatisfactory Planting Performance:** The Work will be considered unsatisfactory if the seedling planting performance rating is greater than 105 percent or less than 92 percent.
- D. **Reduction in Payment:** The reduction in payment for unsatisfactory Work will be:
 - 1. If the seedling planting performance is rated less than 92 percent but equal to or greater than 80 percent, the rate of pay will be equal to the Unit Bid Price reduced by 3 percent for every 1 percent the seedling planting performance rating is less than 92 percent.
 - 2. If the seedling planting performance is rated at 79 percent or less, there will be no payment.
 - 3. If the seedling planting performance rating is greater than 105 percent, the rate of pay will be equal to the Unit Bid Price reduced by 3 percent for every 1 percent the seedling planting performance rating is above 105 percent.
 - 4. The Contract Manager will deduct from the Contractor's payment three dollars (\$3) per seedling found dropped or otherwise wasted by the Contractor.

2-42 Payment Examples

Example A: The Unit Bid Price is \$40 per acre and the seedling planting performance rating is 90 percent.

The seedling planting performance rating of 90 percent is two percentage points less than the 92 percent performance limit. A 3 percent reduction for each of the percentage points equals a total reduction in the Unit Bid Price of 6 percent. Therefore, 100 percent minus 6 percent equals a 94 percent rate of pay per acre which is: 94 percent X \$40/acre = \$37.60/acre.

Example B: The Unit Bid Price is \$78 per thousand and the seedling planting performance rating is 80 percent.

The seedling planting performance rating of 80 percent is 12 percentage points less than the 92 percent performance limit. A 3 percent reduction for each of the percentage points equals a total reduction in the Unit Bid Price of 36 Percent. Therefore, 100 percent minus 36 percent equals a 64 percent rate of pay per thousand which is: 64 percent X \$78/thousand = \$49.92/thousand.

Example C: The Unit Bid Price is \$40 per acre and seedling planting performance rating is 107 percent.

The seedling planting performance rating of 107 percent is two percentage points more than the 105 percent performance limit. A 3 percent reduction for each of the percentage points equals a total reduction in the Unit Bid Price of 6 percent. Therefore, 100 percent minus 6 percent equals a 94 percent rate of pay per acre which is: 94 percent X \$40/acre = \$37.60/acre.

2-43 Seedling Waste

Dumping, discarding, mishandling or otherwise destroying seedlings shall be considered a willful violation of the Contract and shall be considered a breach of contract (Clause 2-16).

2-44 Re-work of Unsatisfactory Units

The Compliance Forester may require the Contractor to re-work a Unit which is not rated satisfactory (Clause 2-41A). The Compliance Forester may require the rework to be completed prior to starting Work on a new Unit. Re-worked areas will be reexamined for contract compliance, and will replace the previous planting performance rating.

If the Contractor refuses to re-work the Unit, the Department may terminate the contract and retain the damage and performance deposit. If the Contractor re-works the Unit and it is rated unsatisfactory, the Department may terminate the contract and the Contractor will be paid only for satisfactorily completed Work prior to termination.

2-45 Payment Schedule

Details of the payment schedule will be determined in the Pre-Work Conference (Clause 2-11) and will be set forth in the Work schedule. Payment shall be made as follows:

- A. **L&I Insurance Premiums.** Ten percent (10%) of all payments due Contractors who employ Workers shall be retained by the Department as security for Labor & Industries industrial insurance premiums owed for their Workers. Upon determination that the Contractor has met all financial obligations for industrial insurance premiums related to the Item(s) of this Contract, the 10% retainage will be returned to the Contractor.
- B. **Partial Payment.** The Contractor may request partial payment when part of a Unit is completed. The Contractor or Designated Contract Representative (Clause 2-12) shall sign the unit completion form after completion of each partial Unit being submitted for payment. The Compliance Forester will make payment recommendations for the invoice and forward the unit completion form to the Contract Manager for processing.

- C. **Unit Completion Form.** The Contractor or the Designated Contract Representative and the Compliance Forester shall sign a unit completion form at the conclusion of Work and completion of the compliance inspection on each Unit.
- D. **Verification Traverse.** If a Unit's acreage is disputed, the Contractor may request a verification traverse by the Department. The request must be in writing and signed by the Contractor. The Department will base the rate of pay on the acres determined from the verification traverse. If the net acres specified in the Unit Description Summary are correct within plus or minus five percent ($\pm 5\%$) after the verification traverse, the Contractor shall pay for the verification traverse at a rate of ten dollars (\$10.00) per one hundred (100) feet of traversed boundary.

**SECTION III-A:
UNIT DESCRIPTION SUMMARIES**

BID 1304 - ITEM A UNIT DESCRIPTION SUMMARY

ADMIN INFO				SPECIES AND PLANTING REQUIREMENTS				ADDITIONAL INFORMATION				COMMENTS
ITEM #	UNIT #	FMU NAME	ACRES	SPECIES	STOCK TYPE	TPA BY SPECIES	SPACING TPA	TOTAL TREES BY SPECIES	TOTAL TREES BY UNIT	ELEVATION (FT)	GATE KEY	
A	1	Good 2V	40	NF	P+1	NF 400	10.4 X 10.4	NF 16,000	16,000	649 - 933	AA-1	
A	2	Mainsail U1	27	WH/WRC/NF	P+1	WH 250 WRC100 NF 400	11.2 X 11.2 10.4 X 10.4	WH 4,750 WRC 1,900 NF 3,200	9,850	591 - 646	AA-1	Plant NF in SE corner at 10.4 X 10.4 spacing for 9 acres
A	3	Mainsail U2	9	NF	P+1	NF 400	10.4 X 10.4	NF 3,600	3,600	622 - 644	AA-1	
A	4	Mainsail U3	15	NF	P+1	NF 400	10.4 X 10.4	NF 6,000	6,000	640 - 666	AA-1	
A	5	High N Dry U1	40	DF	P+1 / 1+1	DF 350	11.2 X 11.2	DF 14,000	14,000	59 - 88	AA-1	
A	6	High N Dry U2	10	DF	P+1	DF 350	11.2 X 11.2	DF 3,500	3,500	89 - 102	AA-1	
A	7	Scotch U1	23	SS / AYC / WH	P+1	SS 200 AYC 150 WH 50	10.4 X 10.4	SS 4,600 AYC 3,450 WH 1,150	9,200	81 - 253	AA-1	Plant all three species throughout the unit
A	8	Middle Drift U17	22	DF / GF / WRC SS	DF 1+1 GF,WRC,SS P+1	DF 150 WRC 100 SS 100 GF 375	11.2 X 11.2 10.8 X 10.8	DF 2,100 WRC 1,400 SS 1,400 GF 3,000	7,900	321 - 412	None	Plant GF starting in SW corner, south of the type 5 stream at 375 spa
A	9	Middle Drift U17A	23	DF / SS / WRC	DF 1+1 SS,WRC P+1	DF 150 SS 100 WRC 100	11.2 X 11.2	DF 3,450 SS 2,300 WRC 2,300	8,050	434 - 623	None	Plant all three species throughout the unit
A	10	Lightning Fast U1	23	DF / SS	DF 1+1 SS P+1	DF 175 SS 175	11.2 X 11.2	DF 4,025 SS 4,025	8,050	416 - 568	None	Plant both species throughout unit.
A	11	Lightning Fast U2	21	DF / WRC / SS	DF 1+1 WRC, SS P+1	DF 200 WRC 100 SS 100	10.4 X 10.4	DF 4,200 WRC 2,100 SS 2,100	8,400	439 - 521	Rayonier North	Plant all three species throughout the unit
A	12	Lightning Fast U3	50	DF / SS / WH	DF 1+1 SS, WH P+1	DF 350 SS 175 WH 175	11.2 X 11.2	DF 9,800 SS 3,850 WH 3,850	17,500	396 - 598	Rayonier North	Road is blocked at west end of Unit 2. Unit 3 is a walk in. Plant 350 DF/acre to the South and West of spur road. Plant SS/WH to the north.
A	13	Gunderson Lookout	45	DF / WH / WRC	DF, WRC, WH P+1 and WH P+0	DF 150 WRC 100 WH 100	11.2 X 11.2	DF 6,750 WRC 4,500 WH 4,500	15,750	612 - 1187	AA-1	Unit has slopes over 80%
A	14	Horse Feathers	80	DF / WRC	P+1	DF 200 WRC 100	12 X 12	DF 16,000 WRC 8,000	24,000	339 - 410	None	Plant both species throughout unit.
A	15	Raine Drop U1	7	SS / WH / WRC	P+1	SS 100 WH 100 WRC 100	12 X 12	SS 700 WH 700 WRC 700	2,100	565 - 586	None	Powerline road is only access to unit.
A	16	Raine Drop U2	18	SS / WH / WRC	P+1 and 1,500 SS P+0	SS100 WH 100 WRC 100	12 X 12	SS 1,800 WH 1,800 WRC 1,800	5,400	551 - 582	None	Powerline road is only access to unit.
A	17	Raine Drop U3	54	DF / WRC / GF	DF, WRC, GF P+1 and 250 DF 1+1	DF250 WRC 100 GF 375	11.2 X 11.2 10.8 X 10.8	DF 12,500 WRC 5,000 GF 1,500	19,000	735 - 1591	None	Plant GF in SE bottom at 375 / acre. Plant DF/WRC mix in the rest of the unit.

Item A Mandatory Elements:

Item A Contract Period: January 19th, 2011 through March 31st, 2011
 Minimum Crew Size: 10 Planters with one non-planting supervisor.
 Planting Tool Specifications: Planting shovel with minimum 10" blade length
 Tree Cooler Storage Locations: Olympic Region Office, Forks (Section 4 T28N R13W)

Daily Contract Start Time: 7:00 a.m. at Cooler
 Maximum Crew Size per Supervisor: 14 Planters
 Minimum Seedling Distance: 6 feet

BID 1304 - ITEM A UNIT DESCRIPTION SUMMARY

ADMIN INFO				SPECIES AND PLANTING REQUIREMENTS				ADDITIONAL INFORMATION				COMMENTS
ITEM #	UNIT #	FMU NAME	ACRES	SPECIES	STOCK TYPE	TPA BY SPECIES	SPACING TPA	TOTAL TREES BY SPECIES	TOTAL TREES BY UNIT	ELEVATION (FT)	GATE KEY	
A	18	Fiberboard Flats U1	31	DF	P+1	DF 350	11.2 X 11.2	DF 10,850	10,850	942 - 1015	AA-1	
A	19	Duc Valley BD	25	DF / WRC	P+1	DF 250 WRC 100	11.2 X 11.2	DF 6,250 WRC 2,500	8,750	631 - 669	AA-1	Plant both species throughout unit.
A	20	Big Trout U1	94	WH / SS	P+1	WH 100 SS 250	11.2 X 11.2	WH 9,400 SS 23,500	32,900	115 - 330	AA-1	Road is blocked at west end of Unit 2. Unit 1 is a walk in. Plant both species throughout unit.
A	21	Big Trout U2	19	WH / SS	P+1	WH 100 SS 250	11.2 X 11.2	WH 1,900 SS 4,750	6,650	110 - 220	AA-1	Plant both species throughout unit.
A	22	Buck Run U1	26	SS / AYC / WRC	P+1	SS 100 AYC 100 WRC 200	10.4 X 10.4	SS 2,600 AYC 2,600 WRC 5,200	10,400	236 - 434	None	Plant all three species throughout the unit
A	23	Buck Run U2	73	SS / AYC / WRC	P+1	SS 100 AYC 50 WRC 250	10.4 X 10.4	SS 7,300 AYC 3,650 WRC 18,250	29,200	369 - 454	None	Plant all three species throughout the unit
A	24	Carpenter U1	96	DF / WRC / WH SS	DF 1+1 WRC,WH, SS P+1	DF 200 WRC100 WH50 SS 50	10.4 X 10.4	DF 19,200 WRC 9,600 WH 4,800 SS 4,800	38,400	206 - 734	AA-1	Road entering unit from the South is blocked. Unit is a walk in. Plant all four species throughout unit.
A	25	Carpenter U2	4	SS / WRC / WH	P+1	SS 200 WRC 100 WH 50	11.2 X 11.2	SS 800 WRC 400 WH 200	1,400	319 - 341	AA-1	Plant all three species throughout the unit

Item A Mandatory Elements:

Item A Contract Period: January 19th, 2011 through March 31st, 2011
 Minimum Crew Size: 10 Planters with one non-planting supervisor.
 Planting Tool Specifications: Planting shovel with minimum 10" blade length
 Tree Cooler Storage Locations: Olympic Region Office, Forks (Section 4 T28N R13W)

Daily Contract Start Time: 7:00 a.m. at Cooler
 Maximum Crew Size per supervisor: 14 Planters
 Minimum Seedling Distance: 6 feet

Note: Monday, February 21st is a state holiday and is not a guaranteed work day.

Item A Summary: Total Acres: 875 # Units: 25

Item A + B Summary: Grand Total Acres: 1,722 # Units: 45

BID 1304 - ITEM B UNIT DESCRIPTION SUMMARY

ADMIN INFO				SPECIES AND PLANTING REQUIREMENTS				ADDITIONAL INFORMATION				
ITEM #	UNIT #	FMU NAME	ACRES	SPECIES	STOCK TYPE	TPA BY SPECIES	SPACING TPA	TOTAL TREES BY SPECIES	TOTAL TREES BY UNIT	ELEVATION (FT)	GATE KEY	COMMENTS
B	1	Lyre Low U1	48	DF	1+1	300	10.4 x 10.4	14,400	19,200	421-751	AA-1	Mix seedling species
				SS	P+1	50		2,400				
				WRC	P+1	50		2,400				
B	2	Lyre Low U2	76	DF	P+1	350	11.2 x 11.2	17,500	26,600	914-1217	00-1	Plant only DF P+1s to rocky higher elevations and slopes in southern areas (50 acres).
				DF	1+1	300		7,800				
				WRC	P+1	50		1,300				Mix in WRC in other areas (26 acres).
B	3	Lyre Low U2 BD A	12	DF	1+1	200	11.2 x 11.2	2,300	4,025	568-712	00-1	Mix seedling species
				WRC	P+1	100		1,150				
				SS	P+1	50		575				
B	4	Lyre Low U2 BD B	1	DF	1+1	200	11.2 x 11.2	200	350	814-948	00-1	Mix seedling species
				WRC	P+1	150		150				
B	5	Lyre Low U3	32	DF	1+1	350	10.4 x 10.4	10,400	12,800	914-1217	00-1	
				NF	P+1	25		1,200				Concentrate NF to south
				SS	P+1	25		1,200				Concentrate SS to north
B	6	Susie Mix U1	81	NF	P+1	450	9.8 x 9.8	36,450	36,450	623-956	AA-1	
B	7	Susie Mix U2	64	DF	1+1	350	9.8 x 9.8	22,400	31,050	674-914	00-1	Pocket of POC planted in west area of unit
				WRC	P+1	100		6,400				
				SS	P+1	350		1,750				Put SS/WRC mix below PA-S-1000 and adjacent to WMZ on south boundary (5 acres)
				WRC	P+1	100		500				
B	8	Susie Mix U3	13	DF	1+1	100	9.8 x 9.8	1,300	5,850	548-697	00-1	Pocket of POC planted in middle of unit
				WRC	P+1	100		1,300				
				SS	P+1	250		3,250				
B	9	Majestic Power	29	AYC	P+1	200	9.8	2,600	12,600	566-832	00-1	Put AYC and WRC mix on north & east slopes and poorly drained areas (15 acres)
				WRC	P+1	250		3,250				
				NF	P+1	400		6,750				Put NF at top where unit is flatter (13 acres)
B	10	Something Else U1	80	DF	1+1	350	10.4 x 10.4	28,000	32,000	429-564	AA-1	Mix seedling species
				WRC	P+1	50		4,000				
B	11	Something Else U2	4	DF	1+1	350	10.4 x 10.4	1,400	1,600	451-543	AA-1	Mix seedling species
				WRC	P+1	50		200				
B	12	Something Else U3	18	DF	1+1	350	10.4 x 10.4	6,300	7,200	388-742	AA-1	Mix seedling species
				WRC	P+1	50		900				
B	13	Something Else U4	80	DF	1+1	350	10.4 x 10.4	28,000	32,000	442-666	AA-1	Mix seedling species
				WRC	P+1	50		4,000				

Item B Mandatory Elements:

Item B Contract Period:	February 1st, 2011 through March 31st, 2011	Daily Contract Start Time:	7:00 a.m. at Cooler
Minimum Crew Size:	10 Planters with one non-planting supervisor.	Maximum Crew Size per Supervisor:	14 Planters
Planting Tool Specifications:	Planting shovel with minimum 10" blade length	Minimum Seedling Distance:	6 feet
Tree Cooler Storage Locations:	Port Angeles Work Center (Section 7 T30N R5W) and / or Ranger County Pit (Section 3 T30N R7W) or comparable location		

BID 1304 - ITEM B UNIT DESCRIPTION SUMMARY

ADMIN INFO				SPECIES AND PLANTING REQUIREMENTS				ADDITIONAL INFORMATION				
ITEM #	UNIT #	FMU NAME	ACRES	SPECIES	STOCK TYPE	TPA BY SPECIES	SPACING TPA	TOTAL TREES BY SPECIES	TOTAL TREES BY UNIT	ELEVATION (FT)	GATE KEY	COMMENTS
B	14	Piedmont Hill U1	60	DF	P+1	325	11.2 x 11.2	19,500	21,000	1122-1557	AA-1	Concentrate WRC in RMZs
				WRC	P+1	25		1,500				
B	15	River View Too U1	31	DF	1+1	300	11.2 x 11.2	9,300	10,850	481-716		Mix seedling species
				WRC	P+1	50		1,550				
B	16	River View Too U2	64	DF	1+1	300	11.2 x 11.2	19,200	22,400	1432-1808		Mix seedling species
				WRC	P+1	50		3,200				
B	17	River View Too U3	87	DF	1+1	300	11.2 x 11.2	26,100	30,450	1705-2256	AA-1	Mix seedling species
				WRC	P+1	50		4,350				
B	18	Pleasantine U2	32	DF	1+1	300	10.4 x 10.4	9,600	11,200	1196-1642	00-1	Mix seedling species
				WP	P+1	100		1,600				
B	19	Oly Blow	26	DF	1+1	400	10.4 x 10.4	10,400	10,400	1363-1508	AA-1	
B	20	Center Blow FY08 U2	9	DF	1+1	194	11.2 x 11.2	1,750	3,150	387-482	00-1	Concentrate WRC on north end of unit.
				WRC	P+1	117		1,050				
				GF	P+1	39		350				

Item B Mandatory Elements:

Item B Contract Period:	February 1st, 2011 through March 31st, 2011	Daily Contract Start Time:	7:00 a.m. at Cooler
Minimum Crew Size:	10 Planters with one non-planting supervisor.	Maximum Crew Size per supervisor:	14 Planters
Planting Tool Specifications:	Planting shovel with minimum 10" blade length	Minimum Seedling Distance:	6 feet
Tree Cooler Storage Locations:	Port Angeles Work Center (Section 7 T30N R5W) and / or Ranger County Pit (Section 3 T30N R7W) or comparable location		

Note: Monday, February 21st is a state holiday and is not a guaranteed work day.

Item B Summary: Total Acres: 847 # Units: 20


Item A + B Summary: Grand Total Acres: 1,722 # Units: 45

Abbreviations for Species	DF = Douglas-fir	NF = Noble fir	WRC = Western redcedar	WP = Western white pine
	WH = Western Hemlock	GF = Grand fir	AYC = Alaska yellow cedar	
	SS = Sitka Spruce	SF = Silver fir	POC = Port Orford cedar	

**SECTION III-B:
UNIT MAPS**

Section III - Unit Map
Tree Planting
Item A - Unit # 1
Unit Name: Good 2V

Invitation to Bid / Contract # 1304
T27N R13W S26



Legend


-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



Section III - Unit Map
Tree Planting
Item A - Unit # 7
Unit Name: Scotch U1

Invitation to Bid / Contract # 1304
T29N R14W S31



Legend


-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item A - Unit #s 10,11,12
Unit Name: Lightning Fast U1,2,3

T30N R14W S25
T30N R13W S30



Legend


-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



Section III - Unit Map
Tree Planting
Item A - Unit # 19
Unit Name: Duc Valley

Invitation to Bid / Contract # 1304
T30N R12W S36




Legend

-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item A - Unit #s 20 & 21 T31N R15W S36
Unit Name: Big Trout U1, U2



Legend


-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item A - Unit #s 24 & 25
Unit Name: Carpenter U1,2

T32N R13W S18



Legend


-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



**Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting**

**Item B - Unit #s 1, 2, 3, 4, & 5 T30N R09W S04, 08, 09,10
Unit Names: Lyre Low U1, U2, U2 BD A, U2, BD B, U3**



Legend

-  Planting Unit Area
-  Road Blocked
-  Trans
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections

1,000 500 0 1,000 Feet



Section III - Unit Map


Invitation to Bid / Contract # 1304

Tree Planting

Item B - Unit # 6

T31N R09W S30, 31

Unit Name: Susie Mix U1




Legend

-  Planting Unit Area
-  Road Blocked
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit #s 7, 8 T30N R09W S5, 6
Unit Names: Susie Mix U2, U3





1,000 500 0 1,000 Feet

Legend

-  Previously Planted
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 9 T31N R09W S31
Unit Name: Majestic Power




Legend

-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads




Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Units # 10, 11 T30N R07W S19, 20
Unit Names: Something Else U1, U2





Legend

-  Planting Unit Area
-  Road Blocked
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads




Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 12 T30N R07W S21
Unit Name: Something Else U3



Legend


-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 13 T30N R07W S15, 16
Unit Names: Something Else U4




Legend

-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 14 T30N R09W S11
Unit Names: Piedmont Hill U1





Legend

-  Road Blocked
-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet




Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 15 T30N R07W S26
Unit Names: River View Too U1



Legend

-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 16 T30N R06W S31, 32
Unit Names: River View Too U2




Legend

-  Planting Unit Area
-  Road Blocked
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

890 445 0 890 Feet




Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 17 T30N R06W S32, 33
Unit Names: River View Too U3



Legend

-  Planting Unit Area
-  Road Blocked
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads



Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 18 T29N R05W S31
Unit Name: Pleasantine U2



Legend


-  Planting Unit Area
-  Road Blocked
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

1,000 500 0 1,000 Feet



Section III - Unit Map
Tree Planting
Item B - Unit # 19
Unit Name: Oly Blow

Invitation to Bid / Contract # 1304
T29N R04W S05




1,000 500 0 1,000 Feet



Legend

-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

Section III - Unit Map Invitation to Bid / Contract # 1304
Tree Planting
Item B - Unit # 20 T28N R01E S07
Unit Names: Center Blowdown FY08 U2



Legend


-  Planting Unit Area
-  Water Courses by Forest Practices Water Type, Detailed
-  Public Land Survey Sections
-  Roads

**SECTION III-C:
VICINITY MAPS**

DRIVING MAP

SALE NAME: GOOD 2V
AGREEMENT#: 30-081053
TOWNSHIP(S): 27N-13W
TRUST(S): UNIVERSITY TRANSFER

REGION: OLYMPIC
COUNTY(S): JEFFERSON
ELEVATION RGE: 1000 FEET




**VICINITY MAP
NOT TO SCALE**

DRIVING MAP

SALE NAME: Mainsail
 AGREEMENT#: 30-084300
 TOWNSHIP(S): T27 R12W
 TRUST(S): Capitol Grant (07)

REGION: Olympic
 COUNTY(S): Jefferson
 ELEVATION RGE: 600-640'



-  sale area
-  gate

DRIVING DIRECTIONS

Unit 1:
 From Forks drive south on U.S. 101 10.7 miles to the junction with the 2V road (M. P. 180.9). Turn right on the 2V road and travel 0.7 miles to the junction with the G-5000. Turn left on the G-5000 and travel 0.3 miles to the sale boundary.

Units 2 & 3:
 From the junction of U.S. 101 and the 2V Road continue south on U.S. 101 for 0.6 miles to the intersection with the 4V road. Turn right on the 4V and travel for 0.2 miles. At the junction stay right continuing on the 4V road for 0.8 miles to the sale boundary.




DRIVING MAP

SALE NAME: High N Dry
AGREEMENT#: 80-084302
TOWNSHIP(S): 28N-R14W
TRUST(S): Forest Board Transfer(01)

REGION: Olympic
COUNTY(S): Not defined.
ELEVATION RGE: 0-500 feet

Vicinity Map Not To Scale



Legend

- Gate
- ▣ Sale Area

DRIVING DIRECTIONS

Unit 1:
From Forks drive north on U.S. 101 1.2 miles to the junction with Hwy 110. Turn left on Hwy 110 and travel 6.9 miles to the junction with the D-300. Turn left on the D-300 to the sale area.




TIMBER SALE MAP

SALE NAME: SCOTCH
AGREEMENT NO: 30-081556
TRUST(S): Forest Board Transfer

REGION: Olympic
COUNTY(S): Clallam

Vicinity Map Not to Scale





Drawn By: M. Helms
Date: November 8, 2007

TIMBER SALE MAP

SALE NAME: MIDDLE DRIFT
AGREEMENT NO: 30-077385
TRUST(S): Capitol (07)


REGION: Olympic
COUNTY(S): Clallam



Drawn By: M. Helms
 Date: September 20, 2007
 Scale: 1" = 1000'

500 0 500 Feet

Elevation: 0 - 500'




TIMBER SALE MAP

SALE NAME: LIGHTNING FAST
AGREEMENT NO: 30-083211
TOWNSHIP(S): T30N - 14W
TRUST(S): CAPITOL BUILDING (07)

REGION: OLYMPIC
COUNTY(S): CLALLAM
ELEVATION: 500 - 1000'

Vicinity Map Not To Scale




TIMBER SALE MAP

SALE NAME: GUNDERSON LOOKOUT
AGREEMENT NO.: 30-070681
TRUST(S): Capitol, School


REGION: Olympic
COUNTY(S): Clallam

Township 29 North, Range 13 West, W.M.



Legend


- Cable Methods
- Shovel and/or Tracked Skidder (D-5 equivalent or smaller) ...
- Sale Area Boundary Tags
- Management Lines
- Logged Area with Date Logged ... L-94
- Roads
 - Existing
 - Required Reconstruction
 - Optional Construction
- Survey Monument
 - Concrete
 - Other
- Take Trees Outside Sale Boundary. Repeater
- Rock Source
- Gate



Scale: 1" = 1000'
 Drawn By: R. Patton
 Date: August 21, 1998

Horse Feathers Vicinity Map

Section 1 T28N-R12W
Section 36 T29N-R12W




Not to Scale Prepared by: Bryan Huber

TIMBER SALE MAP

SALE NAME: RAINE DROP
AGREEMENT NO: 30-083197
TOWNSHIP(S): 30N - 12W
TRUST(S): FOREST BOARD TRANSFER (01)

REGION: OLYMPIC
COUNTY(S): CLALLAM
ELEVATION: 500 - 1000 FEET



VICINITY MAP
NOT TO SCALE

DRIVING MAP

SALE NAME: Fiberboard Flat

AGREEMENT#: 30-0


TOWNSHIP(S): 30 N-R10 W

TRUST(S): 65% Scientific School (10), 35% Clallam County Forest Board (01)

REGION: Olympic

COUNTY(S): Clallam

ELEVATION RGE: 750 ft-1800 ft



0.5
1 Miles

Legend


● Units

— Roads

⛏ Littleton pit

Driving Directions

From Forks go North on US Hwy 101 for 22.4 miles
Turn Left on the B-8500 road, travel 1.17 miles to Unit 1
From B-8500 road continue East on US Hwy 101 for 4.1 miles
Turn Left on the B-9000 road, Unit 2 is 0.3 miles on right, Unit 3 is 0.7 miles on right.
From B-9000 road continue East on US Hwy 101 for 0.7 miles
Turn Left on B-10000 road, Unit 4 is straight ahead.




TIMBER SALE MAP

SALE NAME: DUC VALLEY BLOWDOWN
AGREEMENT NO: 30-082510
TOWNSHIP(S): T30N-R12W
TRUST(S): COMMON SCHOOL (03)

REGION: OLYMPIC
COUNTY(S): CLALLAM
ELEVATION: 500 - 1000 FEET

Vicinity Map Not To Scale




TIMBER SALE MAP

SALE NAME: BIG TROUT BLOWDOWN
AGREEMENT NO: 30-082513
TOWNSHIP(S): T31N-R15W
TRUST(S): COMMON SCHOOL (03)

REGION: OLYMPIC
COUNTY(S): CLALLAM
ELEVATION: 0 - 500 FEET


VICINITY MAP NOT TO SCALE



DRIVING MAP

SALE NAME: BUCK RUN
AGREEMENT#: 30-083205
TOWNSHIP(S): T32N - R13W
TRUST(S): COMMON SCHOOL (03)


REGION: OLYMPIC
COUNTY(S): CLALLAM
ELEVATION RGE: 236 - 454 FEET



TIMBER SALE MAP

SALE NAME: CARPENTER
 AGREEMENT NO: 30-082512
 TOWNSHIP(S): T32N-13W
 TRUST(S): AGRICULTURAL SCHOOL (04)

REGION: OLYMPIC
 COUNTY(S): CLALLAM
 ELEVATION: 400 FEET




Legend

- | | | | | | |
|-------|---------------------------|--------|-------------------------------|-----|-------------------|
| ~~~~~ | Timber Sale Boundary Tags | ==== | Existing Road | → | Streams |
| ✕-✕ | Property Lines | --- -- | Optional Construction | * | Stream Type Break |
| — | Sale Boundary No Tags | ==== | Required Reconstruction | ③ | Stream Type |
| | Cable | =Δ= | Optional Pre-Haul Maintenance | ●-● | Gate |
| ▨ | Ground | ✕ | Rock Pit | | |
| ⋯ | RMZ | | | | |

TIMBER SALE MAP

SALE NAME: LYRE LOW
AGREEMENT NO: 30-082507
TOWNSHIP(S): T30N-09W
TRUST(S): FOREST BOARD TRANSFER(01)/CAPITOL GRANT (07)


REGION: OLYMPIC
COUNTY(S): CLALLAM
ELEVATION: 1000 - 2000 FEET




DRIVING MAP

SALE NAME: MAJESTIC POWER
AGREEMENT#: 30-082111
TOWNSHIP(S): 31N-9W
TRUST(S): Forest Board Transfer (01)

REGION: Olympic
COUNTY(S): Clallam
ELEVATION RGE: 500 - 1000 feet






Something Else Timber Sale Vicinity Map

December, 2008


NOT TO SCALE



DRIVING MAP

SALE NAME: PIEDMONT HILL
AGREEMENT#: Not Defined.
TOWNSHIP(S): T30R08W, T30R09W
TRUST(S): State Forest Board Transfer(1), Capitol Grant(7)

REGION: Olympic Region
COUNTY(S): CLALLAM
ELEVATION RGE: 666-2162



- Timber Sale Unit
- Other Route
- Haul Route
- Highways
- Town & City Locations
- Distance Indicator
- Gate (AA-1)

DRIVING DIRECTIONS:

From state route 112 turn onto the Joyce-Piedmont county rd. and follow for 2 miles to unit 2.

From unit 2 continue South on the Joyce-Piedmont county rd. and follow for 1.2 mi. Then turn left (East) onto the PA-J-2000 and follow for .7 mi.

From the PA-J-2000 and the Joyce-Piedmont county rd. intersection continue South for .1 mi. Then turn right (West) onto the GC-J-3000 and follow for .6 mi to unit 1. Then turn left (North) onto the PA-J-2040 and follow for .25 mi. to unit 3.


See separate map for Place Pit location and driving directions.



DRIVING MAP

SALE NAME: River View Too Sorts
 AGREEMENT#: 30-084815
 TOWNSHIP(S): 30N-R6,7,8W
 TRUST(S): Clallam County Forest Board (01)

REGION: Olympic
 COUNTY(S): Clallam
 ELEVATION RGE: 500-3,000 ft



0.25 Miles


Legend

- Road
- Units
- Rivers
- Rock Pit
- Gate

Units 1,2,3 and 4; From Port Angeles head west on U.S Hwy 101. Travel 8.1 miles and turn left on Olympic Hot Springs Rd. Travel 0.2 miles and turn left on Little River Road, unit 1 is 1.4 miles ahead. Continue on Little River Rd. for 2.8 miles to unit 2. From unit 2 continue on Little River Rd. for 1.1 miles to unit 3. Unit 4 is 1.7 miles beyond the locked gate on the P.A H-1000.

Unit 5: From Port Angeles travel west on U.S Hwy 101 for 4.8 miles. Turn right on Hwy 112 and travel for 7.7 miles. Turn left on Wasankari Rd. Unit is 1.6 miles ahead.






Driving Map Pleasantine



DRIVING MAP

SALE NAME: OLY BLOW
AGREEMENT#: 30-084779
TOWNSHIP(S): T29R04W
TRUST(S): State Forest Board Transfer(1)

REGION: Olympic Region
COUNTY(S): CLALLAM
ELEVATION RGE: 1366-1505



	Timber Sale Unit
	Haul route
	Other Route
	Highways
	Open Water

DRIVING DIRECTIONS:






From junction of Sequim Avenue and US 101 drive west 3.2 miles on US 101 to Hooker Road (the first traffic light). Turn left (south) on Hooker Road and go 0.3 miles to Atterberry Road. Turn right (west) on Atterberry Road and go 2.3 miles. Turn left (south) onto Cassidy Road and go 0.9 miles. Veer right onto Autumn Road. Go approximately 150 feet and turn into the parking area on the left. Go through the gate at the back of the parking area and proceed up the PA-L-1000 road. Go 3.9 miles and the sale will be on the right.



TIMBER SALE MAP

SALE NAME: Center Blowdown FY08
AGREEMENT NO: 30-081780
TRUST(S): State Forest Board Transfer (01), Common School (03), Capitol Building (07)

REGION: Olympic
COUNTY(S): Clallam, Jefferson



Drawn by: J. Garstang
 Date: January 22, 2009
 Scale: None

Not to Scale

SECTION IV - BID FORM REQUIREMENTS

Bid Form Requirements

Bids must be submitted on the Bid Form (Section IV).

- A. If there are multiple Items to be awarded, the bidder may choose to bid on any combination of Items. A bidder may also bid on all Items or any combination of Items with the specification that all Items awarded be restricted to a specified total acreage. That acreage limit must be entered in the space provided on the bid form and must be at least as large as the largest Item for which a bid is submitted.
- B. A Unit Bid Price and a unit total must be entered for all of the Units in any Item the bidder is bidding on. For Items being offered on a per acre basis, the Unit Total is calculated by multiplying the per acre Unit Bid Price times the Unit acres. For Items being offered on a per thousand basis, the Unit total is calculated by multiplying the per thousand Unit Bid Price times the quantity of seedlings designated in the Unit Description, divided by 1000. All Unit Totals within an Item must be summed and entered as the Item Total. In the event of an error in the extension of Unit Totals or Item Totals, the individual Unit Bid Price shall prevail
- C. All bid forms must be signed in ink. If the bid is made by a corporation, it shall be signed by the corporation's authorized designee. Incomplete or unsigned bids may be rejected.

SECTION IV - BID FORM

TREE PLANTING

INVITATION TO BID/CONTRACT NUMBER **1304**

Award of contract shall be on an **Item** basis

At the following rates, the undersigned hereby offers and agrees to furnish materials, equipment, supplies, supervision, and services in compliance with all terms, conditions and specifications of Invitation to Bid/Contract Number **1304**.

Item No.	Unit No.	Unit Name	Acres ¹	Unit Bid Price (Per Acre)	Unit Total ²
A	1	Good 2V	40	\$ _____	\$ _____
A	2	Mainsail U1	27	\$ _____	\$ _____
A	3	Mainsail U2	9	\$ _____	\$ _____
A	4	Mainsail U3	15	\$ _____	\$ _____
A	5	High N Dry U1	40	\$ _____	\$ _____
A	6	High N Dry U2	10	\$ _____	\$ _____
A	7	Scotch U1	23	\$ _____	\$ _____
A	8	Middle Drift U17	22	\$ _____	\$ _____
A	9	Middle Drift U17A	23	\$ _____	\$ _____
A	10	Lightning Fast U1	23	\$ _____	\$ _____
A	11	Lightning Fast U2	21	\$ _____	\$ _____
A	12	Lightning Fast U3	50	\$ _____	\$ _____
A	13	Gunderson Lookout	45	\$ _____	\$ _____
A	14	Horse Feathers	80	\$ _____	\$ _____
A	15	Raine Drop U1	7	\$ _____	\$ _____
A	16	Raine Drop U2	18	\$ _____	\$ _____
A	17	Raine Drop U3	54	\$ _____	\$ _____
A	18	Fiberboard Flats U1	31	\$ _____	\$ _____
A	19	Duc Valley	25	\$ _____	\$ _____
A	20	Big Trout U1	94	\$ _____	\$ _____
A	21	Big Trout U2	19	\$ _____	\$ _____
A	22	Buck Run U1	26	\$ _____	\$ _____
A	23	Buck Run U2	73	\$ _____	\$ _____
A	24	Carpenter U1	96	\$ _____	\$ _____
A	25	Carpenter U2	4	\$ _____	\$ _____
TOTAL ITEM A ACRES:			875	TOTAL BID PRICE FOR ITEM A:	\$ _____

SECTION IV - BID FORM

TREE PLANTING

INVITATION TO BID/CONTRACT NUMBER **1304**

Item No.	Unit No.	Unit Name	Acres ¹	Unit Bid Price (Per Acre)	Unit Total ²
B	1	Lyre Low U1	48	\$ _____	\$ _____
B	2	Lyre Low U2	76	\$ _____	\$ _____
B	3	Lyre Low U2 BD A	12	\$ _____	\$ _____
B	4	Lyre Low U2 BD B	1	\$ _____	\$ _____
B	5	Lyre Low U3	32	\$ _____	\$ _____
B	6	Susie Mix U1	81	\$ _____	\$ _____
B	7	Susie Mix U2	64	\$ _____	\$ _____
B	8	Susie Mix U3	13	\$ _____	\$ _____
B	9	Majestic Power	29	\$ _____	\$ _____
B	10	Something Else U1	80	\$ _____	\$ _____
B	11	Something Else U2	4	\$ _____	\$ _____
B	12	Something Else U3	18	\$ _____	\$ _____
B	13	Something Else U4	80	\$ _____	\$ _____
B	14	Piedmont Hill U1	60	\$ _____	\$ _____
B	15	River View Too U1	31	\$ _____	\$ _____
B	16	River View Too U2	64	\$ _____	\$ _____
B	17	River View Too U3	87	\$ _____	\$ _____
B	18	Pleasantine U2	32	\$ _____	\$ _____
B	19	Oly Blow	26	\$ _____	\$ _____
B	20	Center Blow FY08 U2	9	\$ _____	\$ _____
TOTAL ITEM B ACRES:			847	TOTAL BID PRICE FOR ITEM B: \$	_____

Please limit my total award to a maximum of _____ acres.

Bidders Name and Address:

Signature: _____

Title: _____

Company: _____

Note:

Detach and return this Section as per Clause 1-05.

¹An approximate number.

**CONTRACTOR'S DECLARATION of
INDUSTRIAL INSURANCE STATUS**

INVITATION TO BID NUMBER _____ 1304 _____

The undersigned represents that they operate as _____ an individual, as _____ a partnership, or as _____ a corporation incorporated in the State of _____.

For the purpose of Industrial Insurance premiums payable to the Department of Labor and Industries, every individual in a partnership or joint venture must sign this bid sheet. Individuals not signing the bid sheet but assisting with the contract Work will be considered Workers for the purpose of Industrial Insurance except at the express approval of the Department of Labor and Industries.

Firm Name _____	Labor & Industries Account # _____
Signature _____	Washington Business License # _____
Title _____	Additional Signatures _____
Address _____	_____
City and State _____	_____
Business Phone _____	_____
Home Phone _____	_____

To whom it may concern:

The purpose of this form is to inform persons engaged in contracting forest activities of their liabilities under the mandatory provisions of the Industrial Insurance Act, Title 51 RCW.

The law provides benefits for a Worker, injured in the course of his employment, or his family or dependents in case of death of the Worker.

Worker is defined in the law as every person employed by an employer or every person working under an independent contract, the essence of which is that person's personal labor.

One who contracts to perform forest activities may require the assistance of other individuals to complete these contracts. If this is the case, you are required to establish an industrial insurance account with the Department of Labor and Industries and pay the prescribed premium on behalf of your Workers.

In the event you obtain the assistance of another person or persons to perform Work in connection with your contract, regardless of the circumstances, you should contact the Department of Labor and Industries at one of its statewide service locations or its Olympia headquarters. You will then be provided with the necessary information regarding opening an account, premium rates, and reporting requirements.

The law also provides that any agency or firm that lets a contract is liable for payment of industrial insurance premiums should the contractor fail to do so. The agency or firm may also withhold money due the contractor to insure payment of premium. Consequently, failure to comply with the above requirements could delay payment of retained funds.

Note:

Return one (1) copy of this form as per Clause I-05.

