

Washington State Department of Natural Resources (DNR)

Bidder's/Purchaser's Inspection of Sale Area and Forest Products

Acreage estimates and volume estimates contained within each timber notice of sale and each timber sale contract are made only for administrative and identification purposes. Except as expressly provided by the timber sale contract, the purchaser shall be responsible for paying the entire purchase price, even if the actual acreage or timber volume varies from the estimated quantity or volume shown.

All prospective bidders have the opportunity and are expected to inspect the sale area and the forest products located thereon. Bidders shall not rely on any representations by the State including, but not limited to, acreage estimates, volume estimates, appraisal or pre-bid documentation. The successful bidder/purchaser will further warrant that they have entered the timber sale contract without any reliance upon the DNR's volume estimates, acreage estimates, appraisals, pre-bid documentation, or any other representation by the DNR.

Any timber sale contract arising out of these public auctions will require the successful purchaser to warrant that they are entering the timber sale contract based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold.

Exclusion and Disclaimer of Warranties

The PARTIES AGREE that the IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, and ALL OTHER WARRANTIES EXPRESS OR IMPLIED, ARE EXCLUDED from this transaction, and shall not apply to the goods sold. For example, THE FOLLOWING SPECIFIC MATTERS ARE NOT WARRANTED, and are EXCLUDED from this transaction:

a. ***The merchantability of the forest products.*** The use of the term “merchantable” in any document is not intended to vary the foregoing.

b. ***The condition of the forest products.*** All forest products will be conveyed “AS IS.”

c. ***The acreage contained within any sale area.*** Any acreage descriptions appearing in the timber notices of sale, timber sale contract, timber sale map or other documents are estimates only, provided solely for administrative and identification purposes.

d. ***The volume, quality, or grade of the forest products.*** The descriptions of the forest products to be conveyed are estimates only, made solely for administrative and identification purposes.

e. ***The correctness of any soil or surface conditions, presale construction appraisals, investigations, and all other pre-bid documents prepared by or for the State.*** These documents have been prepared for the State’s appraisal purposes only.

f. ***That the sale area is free from threatened or endangered species, or their habitat.*** The State is not responsible for any interferences with forestry operations that result from the presence of any threatened or endangered species, or the presence of their habitat, within the sale area.

g. ***That the forestry operations to be performed under this contract will be free from regulatory actions by governmental agencies.*** The State is not responsible for actions to enforce regulatory laws, such as the Washington Forest Practices Act (Chapter 76.09 RCW), taken by the Department of Natural Resources or any other agency that may affect the operability of these timber sales.

h. Items contained in any other documents prepared for or by the State.

Please also see timber sale contract clause G-060 for further information.

BIDDING PROCEDURES FOR TIMBER AUCTIONS

The general requirements that follow are a part of all Timber Notices of Sale to be auctioned by the Department of Natural Resources (DNR).

General Information

The State reserves the right to waive minor irregularities and the right to reject any or all bids.

A. This book contains the timber notices of sale and maps for each timber sale scheduled to be auctioned. More specific information can be obtained by contacting the appropriate region office at the number listed on the back cover of this book.

B. The timber notice of sale is a summary of sale information. For more specific information, interested parties are encouraged to view the Appraisal Packets on the DNR Internet Site @ www.dnr.wa.gov, this will take you directly to the Product Sales Section. The Appraisal Packets contain **DRAFT** copies of the timber notice of sale, map, contract, road plan, cruise data, precruise and cruise narrative, Forest Practices Application (FPA), Hydraulics Project Approval (HPA).

C. The sale preview packets may be obtained at no charge for individual sales by visiting the appropriate region office.

D. Timber sale contracts contain extensive terms and conditions that will be binding upon successful high bidders. Each bidder should carefully review all terms contained in the appropriate **DRAFT** timber sale contract prior to bidding on a sale, and should review the final contract prior to signing. **DRAFT** timber sale contracts are contained in the preview and presales packets and are available upon request at the respective region office.

E. Sales advertised in this book have not been approved by the Board of Natural Resources and are subject to the Board's approval before they will be sold. The Board meets and approves sales approximately six weeks prior to auction. All sales are subject to confirmation by the DNR under RCW 79.15.120.

F. The State does not guarantee the accuracy of any information contained herein pertaining to particular sales. Therefore, all prospective purchasers are expected to make their own independent inspections and appraisals prior to bidding.

G. If any conflict exists between the information in the Timber Notice of Sale, timber sale map, sale preview packets and that in the timber sale contract, the signed contract will prevail.

H. Timber sales are subject to the Washington State Forest Excise Tax (RCW Chapter 84.33).

I. Within 30 days of sale confirmation, the apparent high bidder will provide to the State the Performance Security specified on each Notice of Sale.

J. Each DNR region office has information about sales offered in that region. For further information, contact the respective DNR region office. Region office addresses and telephone numbers appear on the back cover of this booklet.

K. The purchaser assumes the responsibility for any costs associated with extra maintenance or repair levied by a county for any county road used by the purchaser.

BIDDING PROCEDURES FOR TIMBER AUCTIONS (Continued)

Bidding Process

- A. All timber will be auctioned using the sealed bid method.
- B. Bids submitted on day of auction must be in the bid box at the specified auction location before 10:00 a.m. The respective DNR region office must receive mailed bids by 4:30 p.m., on the last business day before the auction. Bidders assume all risk for the method of delivery.
- C. The DNR has the right to reject bid forms that are completed incorrectly. *All bid forms must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. Revised documents are not permissible.* Bidding instructions are on the back of the Sealed Bid Form. A bid deposit must be included in the sealed bid envelope unless using a Timber Sale Statewide Bid Bond.
- D. All bids must include the completed Sealed Bid Form and bid deposit.
- E. Bids will be opened in each respective region in the order in which sales appear in the Public Auction Sale of Timber book (alphabetically by county and by agreement number).
- F. If a tie bid occurs, the names of the tie bidders will be placed in a hat and the successful bidder will be determined by a drawing.
- G. The apparent high bidder on a particular sale will have the option of withdrawing additional sealed bids submitted for any remaining sales to be auctioned. The apparent high bidder must exercise this option within two minutes after the apparent high bidder is announced.

Auction Time and Location

Auctions will start at 10:00 a.m. and close at 4:00 p.m. on the date and at the location specified in each Timber Notice of Sale.

Bid Deposits

- A. Required bid deposits are listed on each Timber Notice of Sale.
- B. Bid deposits must be in the form of cash, certified check, cashiers' check, money order or bid bond.
- C. Bid bonds may be either a Timber Sale Statewide Bid Bond or a Timber Sale Per Sale Bid Bond.
- D. All bid deposits shall be submitted by the person or entity submitting the bid and made payable to the Department of Natural Resources. **Third party deposits will not be accepted.**

Timber Sale Per Sale Bid Bonds

- A. The Per Sale Bid Bond shall guarantee payment of the bid deposit **within ten days of auction.**
- B. The balance between the bid bond and the Initial Deposit payment is due by 4:30 p.m., **on the day of auction.**
- C. Additional forms and instructions for a Per sale Bid Bond are available at any DNR region office.

Timber Sale Statewide Bid Bond

- A. Statewide Bid Bonds shall guarantee payment of the Initial Deposit on any statewide timber sale while the bond is in effect.
- B. The Statewide Bid Bond must be received by the Department of Natural Resources, Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction date. The bond shall be in the amount of \$150,000.00.
- C. The bidder must supply a list of persons authorized to bid using the bond. Bid bonds are subject to approval by the Department of Natural Resources.
- D. Successful bidders using a Statewide Bid Bond must pay the total Initial Deposit payment (10 percent of the total bid price) **by 4:30 p.m. on the day of auction.**
- E. A Statewide Bid Bond cannot be used to secure the Initial Deposit payment due the day of auction.
- F. Additional forms and instructions for a statewide bid bond are available at any DNR region office.

Payments

The initial deposit for a sale is 10% of the total bid value as submitted by the apparent high bidder (25% if the bidder is a defaulter as defined under WAC 332-140-300) and never less than \$5,000.00 for lump sum sales. For Lump Sum sales appraised at less than \$5,000.00, the entire bid value is due on day of auction.

- a. Apparent high bidders using cash, certified check, cashiers' check or money order as a bid deposit must pay the total Initial Deposit amount by 4:30 p.m. on auction day.
- b. Apparent high bidders using a Timber Sale Per Sale Bid Bond as a bid deposit must pay the difference between the bid deposit and the total initial deposit by 4:30 p.m., on the day of auction. The bid bond amount must be replaced with a certified check, cashier's check, bank draft, cash, money order, or wire transfer within ten days of the auction.
- c. Apparent high bidders using a Timber Sale Statewide Bid Bond must pay the entire Initial Deposit amount by 4:30 p.m. on the day of auction.

Fees due on the day of sale must be paid by 4:30 p.m.

All payments must be in the form of a certified check, cashier's check, bank draft, cash, money order or wire transfer.

Eligibility to Bid

In order to bid on State timber sales you must be:

- 18 years of age (or have a co-signer who meets the eligibility requirements),
- Licensed to do business in the State of Washington,
- Eligible to bid on Export Restricted timber, and
- Capable of meeting all contract obligations.

Authorized Representatives

Companies may only use authorized representatives or company officers to bid on State sales, sign State documents or sign checks. A list of authorized representatives and their specific authorities must be submitted in writing to the Department of Natural Resources Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction. A company owner or officer must sign this submittal.

State of Washington
Department of Natural Resources
Doug Sutherland, Commissioner of Public Lands

SEALED BID FORM

Sale Name _____ Agreement Number _____

_____ hereby submits the following bid for timber.
(Print full, legal company name)

(Street address, City, State, Zip Code)

(Phone Number)

Lump Sum Bid (Not Including Fees) \$ _____ **For Total Sale**

Weight Scale Sale Bid (Not Including Fees) \$ _____ / **Ton**

Scribner Scale Sale Bid (Not Including Fees) \$ _____ / **MBF**

BID DEPOSIT

Bid Deposit Amount: \$ _____

Bid Deposit Type:

- Cash, certified check, cashiers check, or money order
 - Per Sale Bid Bond
 - Statewide Bid Bond, Number _____
-
-

The Successful Bidder agrees to furnish, **within 30 days of confirmation date**, Performance Security acceptable to the State in the amount specified on the Notice of Sale. Performance Security must guarantee performance of all provisions of the contract and payment of any damages caused by operations under the contract or resulting from the successful bidders noncompliance with any rule or law.

Bidder's Warranty and Bid Signature

By signing and submitting this bid as an offer to purchaser forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based upon their own judgments of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, appraisals, pre-bid documentation, or any other representation by the Washington State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid)

Date _____

(Print **name and title** of Authorized Representative submitting this bid)

Note: all sales are subject to confirmation by the Commissioner of Public Lands (Refer to RCW 79.15.120)

Instructions For Completing Sealed Bid Form

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks on bid form must be completed including the bid bond number if the bidder is relying upon a bid bond for bid deposit.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box before 10:00 a.m. on the day of auction at the location specified in the Timber Notice of Sale.
 - B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be on the bid bond and timber sale contract. The bid form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Mailed Bids

- A. Bids that are mailed are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED". The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The Sealed Bid Form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope.
 - B. Bids that are mailed will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery. The DNR assumes no responsibility for any delays caused by any delivery service.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Initial Deposit:

Lump Sum Sales - Initial Deposit must equal 10% of the total bid submitted.
(25% if the bidder is a defaulter as defined under WAC 332-140-300)

Weight Scale Sales - Initial Deposit must equal 10% of the bid per ton multiplied by the total sale estimated tonnage. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

Scribner MBF Scale Sales - Initial Deposit must equal 10% of the bid per MBF multiplied by the total sale MBF. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

State of Washington
Department of Natural resources
Doug Sutherland, Commissioner of Public Lands

STATEWIDE BID BOND

Bond Number _____

_____ of _____,
(Principal's Name) (City, State)

hereinafter called PRINCIPAL, and _____ hereinafter called SURETY,

a corporation organized under the laws of the State of _____, and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$150,000.00 Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, a venue shall be proper only in Thurston County Superior Court.

Signed, sealed and dated this ____ day of _____, ____.
(month) (year)

This statewide bid bond may be used for bidding between the following dates:

Starting: _____

Ending: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is an apparent high bidder, PRINCIPAL shall before 4:30 p.m., on day of sale, pay to the STATE the amount of the initial deposit in the form of a certified check, cashier's check, bank draft, cash or money order, then this agreement shall be void for the sale on which the payment is made; otherwise, it will remain in force.

SURETY will make payment to the STATE within ten days after demand by the STATE if the PRINCIPAL shall fail to make timely payment as described above.

The SURETY may cancel this bond by sending a written notice to the STATE, not less than forty-five days before a cancellation date; liability shall terminate as to acts or omissions of the PRINCIPAL that occur after the cancellation date.

The PRINCIPAL and the SURETY executed this bond on the date first mentioned.

Principal: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip Code

Surety: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip Code

Surety: (Local Office of Authorized agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

Above

State & Zip

Notary or Company Seal in Space

Instructions For Completing Timber Sale Statewide Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Statewide Bid Bond may be used as bid guaranty on more than one timber sale.
- C. The full legal name and business address of the PRINCIPAL must be inserted where indicated and must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and title must be shown.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as SURETY, it may leave this signature block blank.
- F. This form must be received by the Department of Natural Resources, Product Sales and Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction.
- G. The PRINCIPAL must submit a list of authorized bidders with the Statewide Bid Bond Form.
- H. **The State reserves the right to reject *incomplete* or *incorrect* bid bond forms, making such forms unacceptable as bid guaranty.**

**State of Washington
 Department of Natural Resources
 Doug Sutherland, Commissioner Of Public Lands**

Timber Sale Per Sale Bid Bond

Bond Number _____

_____ of _____, hereinafter called PRINCIPAL, and _____, hereinafter called SURETY, a corporation organized under the laws of the State of _____ and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$ _____ Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, venue shall be proper only in Thurston County Superior Court.

Signed, sealed, and dated this _____ day of _____, 20____.

BID IDENTIFICATION:

SALES NAME(S)	REQUIRED DEPOSIT	AGREEMENT NUMBER(S)

DATE OF BID: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is the high bidder on the sale(s) identified above and, within ten (10) days of the day of sale, transmits cash, certified check, cashier=s check, bank draft or money order, payable to the STATE, in the amount of the bid guaranty required by the terms of the Notice of Sale, *then* this obligation shall be void; *otherwise*, it shall remain in force.

SURETY will make payment to the STATE within ten (10) days after demand by the STATE whenever the PRINCIPAL shall fail to make timely payment as described above.

IN WITNESS WHEREOF: the PRINCIPAL and the SURETY have caused this bond to be executed on the date first mentioned.

SECOND OFFICER:

Signature: _____

Name: _____

Title: _____

PRINCIPAL: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

SURETY: (Local Office of Authorized Agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

City: _____

State & Zip:

SURETY: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

NOTARY OR COMPANY SEAL IN THE SPACE ABOVE

Instructions For Completing Timber Sale PerSale (s) Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Timber Sale Per Sale Bid Bond may be used as bid guaranty on more than one timber sale auction held the same date at the same location.
- C. The full legal name and business address of the PRINCIPAL must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person, the name typed or printed, and title shown. If PRINCIPAL is a corporation, a second officer must sign in the space to the left of the signature of the officer executing for the PRINCIPAL.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown. If this person is not an officer of the corporation, evidence of authority must be submitted.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as Surety, it may leave the local office signature block blank.
- F. The date of the bid bond must not be later than the auction date.
- G. **The State reserves the right to reject *incomplete or incorrect bid bond forms, making such forms unacceptable as guaranty.***

STATE OF WASHINGTON
DEPARTMENT OF NATURAL RESOURCES
Doug Sutherland, Commissioner of Public Lands

LOG SORT SEALED BID FORM

Sale Name _____ Agreement Number _____ Date _____.

_____ hereby submits the following bid for delivered logs.
(Print Company Name)

_____ Telephone Number _____
(Print Name Authorized Company Representative) (Contact for bid result notification)

(Street Address)

(City, State and Zip)

Agreement Number	Sort Number	Delivered Logs Bid Amount (fill in one only)	
		\$ / MBF	\$ / ton

Bid Deposit Amount \$ _____

Bid Deposit Type: Cash, Certified Check, Cashiers Check, or Money Order
 Per Sale Bid Bond
 Statewide Bid Bond, Number _____

The successful bidder agrees to furnish payment security acceptable to the State in the amount as described in clause P-041 of the Purchaser's contract prior to log delivery and at a date to be determined by the State.

Bidder's Warranty and Bid Signature

By signing and submitting this bid as offer to purchase forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, estimates, appraisals, pre-bid documentation, or any other representation by the State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid)

(Date of Signature)

(Print name and title of Authorized Representative submitting this bid)

NOTES: A separate bid form is required for each log sort bid and must be delivered in a separate envelope. Photocopies of this bid form may be used. Each photocopy must have original signatures. All sales are subject to confirmation by the Commissioner of Public Lands as per RCW 79.15.100.

SUPPLEMENTAL INFORMATION FORM

Sale Name _____

Agreement Number _____

Sort # _____

Provide the following information for log manufacturing specifications, delivery locations, weigh and scaling locations.

Log Manufacturing Specifications:

Enter one or more preferred log lengths for each log length range below.	Bidder's Preferred Log Lengths (Log lengths exclude trim)		
	1	2	3
12 ft. through 18 ft.			
20 ft. through 28 ft.			
30 ft. through 40 ft.			

Minimum log trim: _____ inches.

Additional Log or Pole Length Information:

To provide additional preferred cutting information you may attach a separate sheet or "Cutting card".

Log Delivery Specifications:

Designate the point of delivery and address (must be a street address)

(Location Name)

(Street Address)

(City, State and Zip)

Weigh and Scaling Facilities:

Designate the state approved Weigh and Scaling facility closest to the point of delivery.

State approved Weighing and scaling facility address:

(Location Name)

(Street Address)

(City, State and Zip)

Final contract award is contingent upon the State's haul cost analysis. Actual haul route may vary and is subject to change at the State's discretion.

Instructions for Completing the Log Sort Sealed Bid and Supplemental Information Forms.

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form(s) provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks including Agreement Number, Sort Number, Bid amount (per mbf or ton as appropriate for the sort), Bid deposit amount and type. Signatures and date on bid form must be completed including the bid bond number if bidder is relying upon a bid bond for bid deposit.

Bids may not be accepted if the Supplemental Information Form is not included with the approved Log Sort Sealed Bid form or is incomplete.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box or auction envelope before 10:00 a.m. on the day of sale at the location specified in the notice of sale.
- B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same as the name on the bid bond and timber sale contract. The bid form must be signed by an authorized person. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope, please.
- C. Sealed bid envelopes must contain the following:
 1. A completed Log Sort Sealed Bid form;
 2. A completed Supplemental Information form; and
 3. A bid deposit

Mailed Bids

- A. Mail-in bid envelopes are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED." The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The bid form must be signed by an authorized person. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope, please.
- B. Mail-in or otherwise delivered bids will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery they chose. The DNR assumes no responsibility for any delays caused by any delivery service.
- C. Sealed bid envelopes must contain the following:
 1. A completed Log Sort Sealed Bid form;
 2. A completed Supplemental Information form; and
 3. A bid deposit

Summary Report of All Sales for the Month of April 2007

Board Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Cowlitz	Pacific Cascade	79892	HIDALGO	5,146	\$1,928,000.00
Grays Harbor	Pacific Cascade	79733	HEDGE HOG	6,915	\$2,264,000.00
Klickitat Yakima	Southeast	72843	GRADE THIN SORTS	4,912	\$1,763,531.00
Klickitat	Southeast	78734	GULER	1,856	\$470,000.00
Mason	South Puget	75798	TALL HAM	1,827	\$683,000.00
Mason	South Puget	77661	UNION CITY	2,695	\$913,000.00
Pend Oreille	Northeast	77913	POWER PEAK SORTS	10,285	\$1,614,882.00
Skagit	Northwest	77259	APOLLO AERIAL	2,979	\$680,000.00
Skagit	Northwest	78829	VERBENA	3,736	\$775,000.00
Skamania	Pacific Cascade	79907	PROUD MONKEY VDT	1,680	\$387,000.00
Whatcom	Northwest	79761	SUGAR MAGNOLIA CC & PC	2,510	\$408,000.00
Yakima	Southeast	77383	EWEMHO SORTS	4,606	\$1,213,420.00
Yakima Klickitat	Southeast	78686	SNOW TROUT FI SORTS	7,925	\$1,490,110.00
Total				=====	=====
				57,072	\$14,589,943.00

Region Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Kitsap	South Puget	77667	EGLON HEIGHTS THINNING	926	\$66,000.00
Skamania	Pacific Cascade	78904	DAWGHOUSE VDT	977	\$101,000.00
Yakima	Southeast	80854	BIRD CREEK SORT #6	380	\$109,060.00
Yakima	Southeast	80855	BIRD CREEK SORT #7	356	\$149,520.00
Yakima	Southeast	80856	BIRD CREEK SORT #8	14	\$4,340.00
Yakima	Southeast	80857	BIRD CREEK SORT #9	255	\$75,480.00
Yakima	Southeast	80858	BIRD CREEK SORT #10	42	\$7,630.00
Total				=====	=====
				14,434	\$513,030.00

There is one (1) Notice of Sale and map for the Bird Creek Sorts 6-10 sale, in this book.

TIMBER NOTICE OF SALE

SALE NAME: HIDALGO

AGREEMENT NO: 30-079892

AUCTION: April 26, 2007 starting at 10:00 a.m., **COUNTY:** Cowlitz
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 14 miles east of Kalama, WA

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint, trees bounded out by leave tree area tags, snags and down timber existing three years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod, property line, Unit #1 Spur 2, and the 6230 and 6237 roads in Unit #1; timber sale boundary tags, reprod and the 6230 road in Unit #2; on part(s) of Sections 24 all in Township 7 North, Range 1 East, W.M., containing 85 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	28.2	9	4,898	\$383.70			328	684		3,158	711	17	
Hemlock	17.5	8	138	\$217.00						77	49	12	
Maple	19.1		90	\$174.00						24	44	22	
Red alder	11.6		20	\$174.00							7	13	
Sale Total			5,146										

MINIMUM BID: \$383.7/MBF (est. value \$1,928,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$192,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with ground-based harvesting equipment (shovel, tracked skidder) being restricted to slopes of 35% or less. See Schedule L for further harvesting specifications. Shovel yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 47.43 stations of required reconstruction. 30.35 stations of optional construction. 28.35 stations of optional reconstruction. 264.00 stations of required Pre-haul Maintenance. 5.75 stations of road abandonment. 100.38 stations of road deactivation. Rock is available at no charge from the State's 6335 Road Quarry pit located in Section 24, Township 7 North, Range 1 East, W.M. Rock for work under this contract may be purchased from any commercial source as approved in writing by the Contract Administrator. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS and traverse. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 75% ground-based and 25% cable harvesting.

FEES: \$50,000.00 is due on day of sale. \$12.53 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: If Purchaser chooses to tailhold on private property, Purchaser shall obtain permit(s) and assumes responsibility for all costs associated with permit(s). Purchaser must provide the State with a copy of the executed permit(s) or a letter from the private entity indicating that a satisfactory tailhold permit(s) has been consummated between Purchaser and private entity. See vicinity map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: HIDALGO
 AGREEMENT NO: 30-079892
 TRUST(S): CEP & RI (06)



REGION: Pacific Cascade
 COUNTY(S): Cowlitz

Township 07 North, Range 01 East, W.M.



Legend

- Sale Area
- RMZ
- Sale Boundary Tags (White)
- Property Line
- Existing Roads
- Pre-haul Maintenance
- Required Reconstruction
- Optional Construction
- Optional Reconstruction
- Streams
- Water Type 1 - 5
- Monumented Corner
- Leave Trees
- Existing Rock Pit
- Gate (Weyco)



Drawn By: Shawn B.
 Date: January 23, 2007
 Scale: 1" = 1000'
 Elevation: 720ft. - 1,480ft.

TIMBER NOTICE OF SALE

SALE NAME: HEDGE HOG

AGREEMENT NO: 30-079733

AUCTION: April 26, 2007 starting at 10:00 a.m., **COUNTY:** Grays Harbor
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 3 miles north of Oakville, WA

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint, trees bounded out by yellow leave tree area boundary tags, down timber existing five years prior to the day of sale, snags and pre-existing stumps, bounded by the following: timber sale boundary tags, reprod, and the D-1100 road in Unit #1; timber sale boundary tags and reprod in Unit #2; timber sale boundary tags, reprod, and the D-1000 and D-1085 roads in Unit #3; timber sale boundary tags, reprod, and the D-Line and E-Line roads in Unit #4 on part(s) of Sections 13 all in Township 16 North, Range 5 West, Sections 1, 2, 3, 5, 6, 7, 8, 9, 10 and 22 all in Township 16 North, Range 4 West, Sections 32 all in Township 17 North, Range 4 West, W.M., containing 182 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	18.2	10	6,160			59	81		3,626	2,122	272	
Red alder	13.6		588					11	100	240	237	
Hemlock	14.2	8	70						29	21	20	
Maple	14.7		43							5	38	
Red cedar	16		40						7	26	7	
Cottonwood	36		14						13		1	
Sale Total			6,915									

MINIMUM BID: \$2,264,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$226,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel harvesting equipment being restricted to slopes of 35% or less. See Schedule L for further harvesting specifications. Shovel harvesting is restricted from September 30 to May 1 in all units unless approved in writing by the Contract Administrator. Falling and Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator in Unit #3.

ROADS: 5.18 stations of required reconstruction. 75.32 stations of optional construction. 6.00 stations of optional reconstruction. 852.14 stations of required Pre-haul Maintenance. 81.32 stations of road deactivation. Rock is available at no charge from two State pits. The Low Bank Quarry pit located in Section 15 and the Vantage quarry pit located in Section 22, Township 16 North, Range 04 West, W.M. Rock may also be obtained from any commercial source as approved in writing by the Contract Administrator. Purchaser shall install 3 fish passable pipes along the D-Line as designed in the Road Plan. Purchaser shall apply 4 inch Class B concrete asphalt to 7.18 stations and chip seal to approximately 460.00 stations of the D-Line as described in the Road Plan. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator on the D-1085 road.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS and traverse. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 54% shovel and 46% cable harvesting.

FEES: \$50,000.00 is due on day of sale. \$15.03 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: On Unit #3, north of the unit boundary line, only 2 yarding corridors, no greater than 14 feet in width, will be allowed unless otherwise approved, in writing by the Contract Administrator. Purchaser assumes responsibility for any county road use permits and for

This sale is on lands certified
under the Sustainable Forestry
Initiative® program.
www.aboutsfi.org



WASHINGTON STATE DEPARTMENT OF
Natural Resources

TIMBER NOTICE OF SALE


all costs associated with permits and extra maintenance or repair levied by a county for any county road used by Purchaser, this includes underground utilities along C-Line.

TIMBER SALE MAP

SALE NAME: HEDGE HOG
 AGREEMENT NO: 30-079733
 TRUST(S): Capitol Grant (07) & IFLR (42)



REGION: Pacific Cascade
 COUNTY(S): Thurston

Township 16 North, Range 04 West, W.M.



Legend

- Sale Area
- Leave Tree Area
- RMZ
- Sale Boundary Tags (White)
- Leave Tree Tags (Yellow)
- Existing Roads
- Pre-haul Maintenance
- Required Reconstruction
- Optional Construction
- Optional Reconstruction
- Streams
- Water Type 1 - 5
- Monumented Corner
- Existing Rock Pit
- HCP Culvert Replacement




Drawn By: Shawn B. & Stephanie M.
 Date: January 30, 2007
 Scale: 1" = 1000'
 Elevation: 120ft. - 1,240ft.

TIMBER SALE MAP

SALE NAME: HEDGE HOG
 AGREEMENT NO: 30-079733
 TRUST(S): Capitol Grant (07) & IFLR (42)


REGION: Pacific Cascade
 COUNTY(S): Thurston

Township 16 & 17 North, Range 04 West, W.M.




Legend

- Sale Area
- Leave Tree Area
- RMZ
- Sale Boundary Tags (White)
- Leave Tree Tags (Yellow)
- Existing Roads
- Pre-haul Maintenance
- Required Reconstruction
- Optional Construction
- Optional Reconstruction
- Streams
- Water Type 1 - 5
- Monumented Corner
- Existing Rock Pit
- HCP Culvert Replacement



Drawn By: Shawn B.
 Date: January 30, 2007
 Scale: 1" = 1000'
 Elevation: 120ft. - 1,240ft.



TIMBER NOTICE OF SALE

SALE NAME: GRADE THIN Log Sorts **AGREEMENT NO: 30-080681 -- 080684 and 080841**

AUCTION: April 24, 2007, starting at 10:00 a.m., **COUNTY:** Yakima and Klickitat
Southeast Region Office, Ellensburg, WA

SALE LOCATION: Sale located approximately 2 miles northeast of Glenwood WA off of the Mt Adams Highway.

PRODUCTS SOLD AND SALE AREA: All delivered timber, meeting the specifications described below; on parts of Sections 26, 27, 34, 35 and 36, Township 7 North, Range 12 East, and parts of Section 1, Township 6 North, Range 12 East, W.M., , containing 1166 acres, more or less.

MINIMUM BID AND ESTIMATED LOG SORT VOLUMES:

Agreement #	Sort #	Species and Sort Specifications	Average Log Length	Estimated Volume		Minimum Bid Delivered Prices		Total Appraised Value	Bid Deposit
				mbf	Tons	\$/mbf	\$/Ton		
30-080681	1	DF 5"+	28'	581	4245	\$400.00	-----	\$232,400.00	\$23,240.00
30-080682	2	LP, GF 5"+	----	119	1114	-----	\$39.95	\$43,836.00	\$4,836.00
30-080683	3	PP 5-11"	----	3433	22845	-----	\$45.00	\$1,028,025.00	\$102,802.50
30-080684	4	PP 12"+	30'	779	4670	\$420.00	-----	\$327,180.00	\$32,718.00
30-080841	5	Utility	----	-----	3774	-----	\$35.00	\$132,090.00	\$13,209.00
Totals				4912	36248			\$1,763,531	

BID METHOD: Sealed Bids **UNIT OF MEASURE:** MBF scale/Tonnage scale

EXPIRATION DATE: March 31, 2008 **ALLOCATION:** Export Restricted

PAYMENT SECURITY: To be determined by the State as described in Clause P-041 of the Purchaser's Contract.

BIDDING PROCEDURES: A separate sealed bid and envelope must be submitted for each log sort. Prospective Purchasers may bid on any or all log sorts. On the day of sale the Purchaser must bring their bid deposit up to 10% of their total bid price. Complete bidding procedures and auction information may be obtained from the Southeast Region Office in Ellensburg, WA. Phone number (509) 925-8510.

HARVEST AND DELIVERY COSTS: Purchaser must pay the forest excise taxes associated with the log sorts delivered to them. The tax rate for this sale is 4.2%. Taxable Stumpage = Total Delivered Value – (Harvest Cost + Haul Cost + ARRF). Use the following rates for estimating taxable stumpage: Harvest Cost = tons (\$22.75). Haul Cost = (tons)(\$2.63) + tons(\$0.16 x C miles) + tons(\$0.14 x A miles)). ARRF = \$22.25/mbf.

SPECIAL REMARKS: The successful Purchaser(s) will be required to purchase logs from the sale area upon delivery to their location specified in the bid submitted. Logs will be delivered to the Purchaser's delivery location by the State's contract harvester. Purchaser is responsible for weighing and scaling costs. All mbf and tonnage loads will be weighed and all mbf loads will be scaled at State approved scaling locations. The State reserves the right to determine where logs are authorized to be scaled and weighed.

For more information regarding this log sort sale visit our web site:
<http://www.dnr.wa.gov/htdocs/fr/sales/>. If you have questions call Linda Hazlett at the Southeast Region office at (509) 925-8510.


CONFIRMATION: Each sort is subject to confirmation following auction. No sorts will be confirmed until at least 10 days after all sorts are successfully auctioned.

TIMBER SALE MAP

November 14, 2006


Sale Name: Grade Thin Sorts
Agreement Number: 30-072843
Trust(s): (1) State Forest Board-Transfer, (03) Common School,
 (06) CEP & RI

Region: Southeast
County: Yakima



1 inch equals 1,678 feet

*Elevation Range 1800 - 2160 Feet
 Contour Interval - 40 Feet
 See Road Plan Map for detailed information*



LEGEND

- | | |
|---|---|
|  DNR Managed Land |  Equipment Limitation Zone |
|  Timber Sale Boundary |  Special Management Zone |
|  Road | |
|  Marsh / Bog / Wetland | |
|  F (Fish) | |
|  N (Non-fish) | |
|  Unknown or Unmodeled | |

TIMBER NOTICE OF SALE

SALE NAME: GULER

AGREEMENT NO: 30-078734

AUCTION: April 24, 2007 starting at 10:00 a.m.,
Southeast Region Office, Ellensburg, WA

COUNTY: Klickitat

SALE LOCATION: Sale located approximately 9 miles southwest of Trout Lake to Unit #1 and 6 miles southwest of Trout Lake to Unit #2

PRODUCTS SOLD AND SALE AREA:

All live standing timber NOT marked with blue paint bounded by white timber sale boundary tags on Unit #1 and all live standing timber marked with orange paint bounded by white timber sale boundary tags on Unit #2 on part(s) of Sections 10 all in Township 5 North, Range 10 East, Sections 28 and 29 all in Township 6 North, Range 10 East, W.M., containing 84 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg Ring DBH Count	Total MBF	MBF by Grade									
			1P	2P	3P	SM	1S	2S	3S	4S	UT	
Grand fir	16.6	1,394							429	959	6	
Douglas fir	16	462				21			152	289		
Sale Total		1,856										

MINIMUM BID: \$470,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY:

\$94,000.00

SALE TYPE: Lump Sum

EXPIRATION DATE: November 30, 2007

ALLOCATION: Export Restricted

BID DEPOSIT: \$47,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Felled by hand or by a feller buncher similar to a Timco 425 or smaller (Unit #2 only) and yarded by a rubber tired skidder or tractor no larger than a D-6 cat or equivalent and cable yarding equipment. Falling and Yarding will not be permitted from November 30 to April 30 unless authorized in writing by the Contract Administrator due to wet weather conditions.

ROADS: 2.75 stations of required construction. 52.80 stations of required reconstruction. Prospective purchasers should review the road plan in detail. Road construction will not be permitted from November 30 to April 30 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions. The hauling of forest products will not be permitted from November 30 to April 30 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions.

ACREAGE DETERMINATION

CRUISE METHOD: Sale acres were determined using a GPS. Volume was cruised using a variable plot method and 32 foot log grades except for ponderosa pine which used 16' log grades.

FEES: On the day of sale, purchaser shall provide a check in the amount of \$200.00 made payable to SDS Lumber Company for a road use permit. On the day of sale, purchaser shall provide a check in the amount of \$100.00 made payable to West Wind Properties Inc for a road use permit. On the day of sale, purchaser shall provide a check in the amount of \$75.00 made payable to West Wind Timber Inc for a road use permit. \$24,600.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Unit #1 is a cable yarding regeneration harvest unit, however, ground skidding will be required in the NW portion of the unit to avoid damage to leave trees (see timber sale map). Unit #1 is predominantly grand fir. Unit #2 is a thinning unit, mostly Douglas-fir. A Timco 425 feller buncher or smaller will be the largest harvester allowed in Unit #2. Logging slash shall be returned to the woods in Unit #2. Tops of harvested trees will remain in the area where felling occurred. In Unit #1, a minimum of 400 evenly distributed plantable spots per acre must be created as directed by the Contract Administrator. A log loader and tractor must remain on site until Contract Administrator has approved clean-up.


TIMBER SALE MAP

November 20, 2006

Sale Name: Guler
Agreement Number: 30-078734
Trust(s): State Forest Board-Transfer-01, Common School-03

Region: Southeast
County: Klickitat

Township 5 North, Range 10 East, W.M.



1 inch equals 1,000 feet

*Elevation Range 2,240 - 3,800 Feet
Contour Interval - 40 Feet
See Road Plan Map for detailed information*



0 0.1 0.2 0.4 Miles

-  Timber Sale Boundary
-  Cable Yarding
-  Road
-  Required Reconstruction
-  Required Construction
-  F (Fish)
-  N (Non-fish)
-  Unknown or Unmodeled
-  SMZ


TIMBER SALE MAP

November 20, 2006

Sale Name: Guler
Agreement Number: 30-078734
Trust(s): State Forest Board-Transfer-01, Common School-03

Region: Southeast
County: Klickitat

Township 6 North, Range 10 East, W.M.



1 inch equals 1,000 feet

*Elevation Range 2,240 - 3,800 Feet
Contour Interval - 40 Feet
See Road Plan Map for detailed information*

-  Timber Sale Boundary
-  Road
-  Required Reconstruction
-  Required Construction
-  F (Fish)
-  N (Non-fish)
-  Unknown or Unmodeled
-  SMZ



0 0.1 0.2 0.4 Miles

VICINITY MAP

November 15, 2006

Sale Name: Guler


Region: Southeast

Agreement Number: 30-078734

County: Klickitat

Trust(s): State Forest Board-Transfer-01, and Common School-03

Township 5 and 6 North, Range 10 East, W.M.



4 2 0 4 Miles



Legend

- Unit Boundary
- Haul Route
- State Route
- Other Roads

TIMBER NOTICE OF SALE

SALE NAME: TALL HAM

AGREEMENT NO: 30-075798

AUCTION: April 24, 2007 starting at 10:00 a.m., **COUNTY:** Mason
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 15 miles north of Hoodspport.

PRODUCTS SOLD AND SALE AREA:

All timber bounded by white timber sale boundary tags, property lines marked with yellow flagging, BPA power line Right of Way, the 2480 Road and the 2485 Road, except those trees marked with blue paint in Unit #1; all timber bounded by property lines marked with yellow flagging, and the BPA power line Right of Way, except those trees marked with blue paint in Unit #2, on part(s) of Sections 21 all in Township 24 North, Range 3 West, W.M., containing 55 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	15.1	12	1,641				9		653	766	213		
Hemlock	10.5		101						6	57	38		
Red cedar	9.4		73							21	52		
Red alder	9.8		9								9		
Maple	10.2		3								3		
Sale Total			1,827										

MINIMUM BID: \$683,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2007 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$68,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground based equipment on slopes less than 35 percent and cable equipment on slopes greater than 35 percent. Shovel logging shall be in accordance with the attached Schedule A, which is part of this contract. Timber hauling on the USFS 24 Road and the 2480 Road will not be permitted on weekends or state recognized holidays from Memorial Day through Labor Day.

ROADS: 28.52 stations of optional construction. 131.64 stations of required pre-haul maintenance. 28.52 stations of light abandonment, if constructed. Purchaser Maintenance on the 400 (from the 2480 Road to the rock pit), 2480, and 2485 Roads, and Spurs 1, 2, 3, and 4. Designated Maintenance on the 24 Road (from Highway 101 to the junction of the 24 and 2480 Roads). Road construction will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends or state recognized holidays. In addition, rock haul will not be permitted from October 1 to April 30, nor at all on weekends or state recognized holidays, unless approved in writing by the Contract Administrator. The hauling of forest products will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends or state recognized holidays from Memorial Day through Labor Day on the USFS 24 Road and the 2480 Road.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by traversing boundaries with a Trimble GPS, deducting 4.4 acres for existing roads and Right of Way in Unit #1, and Trimble GPS in Unit #2. All units were cruised using a variable plot sample with a BAF of 40.00/full on a 200x225 foot grid.

FEES: \$24,208.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: Purchaser shall pull vine maple in the ground based areas.

TIMBER SALE MAP

SALE NAME: TALL HAM
AGREEMENT NO: 30-075798
TRUST(S): FOREST BOARD TRANSFER (01)

REGION: SOUTH PUGET SOUND
COUNTY(S): MASON

TOWNSHIP 24 NORTH, RANGE 3 WEST, W.M.




LEGEND

- ~~~~~ White Timber Sale Boundary Tags
- ~~~~~ Property Line marked with yellow flagging
- ==== Existing Road
- Optional Construction
- BPA Powerline
- ▨ Sale Area
- ▤ RMZ
- Stream
- * Water Type Break
- 3 Water Type
- ◆ Survey Corner
- Locked Gate: Master 786
- ⊕ Designated Landing

ELEVATION RANGE: 600-840 feet

**VICINITY MAP
Not to Scale**



Drawn By: A. Mainwaring
 Date: November 27, 2006

TIMBER NOTICE OF SALE

SALE NAME: UNION CITY

AGREEMENT NO: 30-077661

AUCTION: April 24, 2007 starting at 10:00 a.m., **COUNTY:** Mason
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 14 miles west of Belfair

PRODUCTS SOLD AND SALE AREA:

All timber bounded by white timber sale boundary tags, property line with yellow flagging, and the P-2000 Road (Bald Point Road), except those trees marked with blue paint and all trees bounded out by yellow leave tree area tags in Unit #1; all timber bounded by white timber sale boundary tags, and Hahobas Way, except those trees marked with blue paint and all trees bounded out by yellow leave tree area tags in Unit #2, on part(s) of Sections 4 and 21 all in Township 22 North, Range 3 West, Sections 33 all in Township 23 North, Range 3 West, W.M., containing 140 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	13.3	11	2,470						815	1,217	438		
Hemlock	10.6		136						7	82	47		
White pine	11		47						10	20	17		
Red cedar	11.9		42							28	13		
Sale Total			2,695										

MINIMUM BID: \$913,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$91,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground based yarding on slopes less than 35 percent. Cable yarding on slopes greater than 35 percent and as shown on the Timber Sale Map in Unit #1. If Purchaser elects to shovel log, shovel logging shall be in accordance with the attached Schedule A, which is part of this contract. Falling and Yarding will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all weekdays 7:00 PM to 7:00 AM, weekends or state recognized holidays.

ROADS: 10.82 stations of required construction. 4.77 stations of required reconstruction. 49.73 stations of optional construction. 14.93 stations of required abandonment. 49.73 stations of abandonment, if constructed. 10.82 stations of required deactivation. Purchaser maintenance on all roads used except for the Cougar Road. Designated maintenance on the Cougar Road. Road construction will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all weekdays 7:00 PM to 7:00 AM, weekends or state recognized holidays. The hauling of forest products will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all weekdays 7:00 PM to 7:00 AM, weekends or state recognized holidays.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by traversing boundaries with GPS. Units were cruised by using a variable plot sample with a BAF of 27.78 on a 400 x 250 foot grid.

FEES: \$35,709.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: This sale has an Extreme Hazard Abatement requirement. An HPA has been applied for the culvert removal/installation on Hahobas Way. Purchaser shall remove existing fish blockage culvert at station 27+81 and install a 96"x40' culvert per the HPA. Timing restriction will be in effect in Unit #1 prohibiting harvesting, road construction, operation of heavy equipment and timber hauling during Critical Nesting Season (April 1 through August 31) during Daily Peak Activity of the Marbled Murrelet which is from 1 hour before sunrise to 2 hours after sunrise and 1 hour before sunset to 1 hour after sunset. This restriction applies to all acreage within .25 mile (1,320 feet) of the Marbled Murrelet polygon located near the southeast corner of Unit #1.

TIMBER SALE MAP


SALE NAME: UNION CITY
 AGREEMENT NO: 30-077661
 TRUST(S): FOREST BOARD TRANSFER (01)

REGION: SOUTH PUGET SOUND
 COUNTY(S): MASON

TOWNSHIP 22 & 23 NORTH, RANGE 3 WEST, W.M.



TOWNSHIP 22 NORTH, 3 WEST, W.M.



LEGEND

- | | | | | | |
|-----------|---|-----------|-------------------------|---|--|
| ~~~~~ | White Timber Sale Boundary Tags | ——— | Existing Road | * | Water Type Break |
| ~ ~ ~ ~ ~ | Property line with yellow flagging | - - - - - | Required Construction | ⌘ | Leave Tree Clump marked with yellow Leave Tree Area tags |
| ▨ | Cable area | ▬▬▬▬ | Required Reconstruction | Ⓜ | Waste Area |
| ▧ | Sale Area (Ground based <35% slopes, Cable >35% slopes) | - - - - - | Optional Construction | 3 | Water Type |
| ⋯ | Riparian Management Zone | ⊥ ⊥ ⊥ ⊥ | Required Abandonment | ◆ | Survey Corner |
| | | | | → | Stream |


Drawn By: A. Mainwaring
 Date: September 5, 2006

ELEVATION RANGE: 311-516 feet

TIMBER SALE MAP

SALE NAME: UNION CITY
AGREEMENT NO: 30-077661
TRUST(S): FOREST BOARD TRANSFER (01)

REGION: SOUTH PUGET SOUND
COUNTY(S): MASON



MAP 2 OF 2

VICINITY MAP
Not to Scale

TIMBER NOTICE OF SALE

SALE NAME: POWER PEAK SORTS **AGREEMENT NO: 30-080615 to 30-080622 and 30-080626**

AUCTION: April 24, 2007, starting at 10:00 a.m.,

COUNTY: PEND OREILLE

Northeast Region Office, Colville, WA.

SALE LOCATION: Sale located approximately 25 miles northwest of Newport, WA.

PRODUCTS SOLD AND SALE AREA:

All species with in Units 1, 2, 3, and 4 not banded with blue paint bounded by white timber sale boundary tags and red ribbon; all species in Unit 5 not banded with orange paint bounded by white timber sale boundary tags and red ribbon; and all species bounded by right-of-way boundary tags; on parts of Sections 4, 5, 8, 9, and 16 within Township 31 North, Range 43 East, W.M. and parts of Section 16 within Township 32 North, Range 43 East, W.M. , containing 390 acres, more or less.

Agreement #	Sort #	Species and Sort Specifications	Average Log Length	Estimated Volume		Minimum Bid Delivered Prices		Total Appraised Value	Bid Deposit
				mbf	Tons	\$/mbf	\$/Ton		
30-080615	1	DF/WL Sawlogs/Peelers 7"-11" dib	30 feet	2,231	12,219	435.00	N/A	\$970,485.00	\$97,048.50
30-080616	2	DF/WL Sawlogs/Peelers 12"+ dib	30 feet	1,820	9,769	\$447.00	N/A	\$813,540.00	\$81,354.00
30-080617	3	LP/WP/ES/PP Sawlogs 7"+ dib	28 feet	146	773	\$340.00	N/A	\$49,640.00	\$4,964.00
30-080618	4	GF/WH/AF Sawlogs 7"+ dib	28 feet	3,205	19,931	\$350.00	N/A	\$1,121,750.00	\$121,175.00
30-080619	5	Cedar Sawlogs (non-pole grade) 7"+ dib	25 feet	1,115	7,763	\$800.00	N/A	\$892,000.00	\$89,200.00
30-080620	6	Cedar Poles Class 6-35' or greater	N/A	321	1,623	\$1,048.00	N/A	\$336,408.00	\$33,640.80
30-080621	7	DF/WL/RC Chip & Saw 5"-6" dib	N/A	1,056	5,265	N/A	\$60.00	\$315,900.00	\$31,590.00
30-080622	8	GF/WH/LP/WP/ES/AF Chip & Saw 5"-6" dib	N/A	393	2,523	N/A	\$35.00	\$88,305.00	\$8,830.50
30-080626	9	All species (except Cedar) Utility 2"+ dib	N/A		1,150	N/A	\$30.00	\$34,500.00	\$3,450.00
Totals				10,287	61,016			\$4,622,528.00	

MINIMUM BID AND ESTIMATED LOG SORT VOLUMES:

BID METHOD: Sealed Bids

UNIT OF MEASURE: MBF scale/Tonnage scale

EXPIRATION DATE: December 31, 2007

ALLOCATION: Export Restricted

PAYMENT SECURITY:

To be determined by the State as described in Clause P-041 of the Purchaser's Contract.

BIDDING PROCEDURES:

A separate sealed bid and envelope must be submitted for each log sort. Prospective Purchasers may bid on any or all log sorts. On the day of sale the Purchaser must bring their bid deposit up to 10% of their total bid price. Complete bidding procedures and auction



TIMBER NOTICE OF SALE

information may be obtained from the Northeast Region Office in Colville, WA. Phone number (509) 684-7474.

HARVEST AND

DELIVERY COSTS: Purchaser must pay the forest excise taxes associated with the log sorts delivered to them. The tax rate for this sale is 4.2%. Taxable Stumpage = Total Delivered Value – (Harvest Cost + Haul Cost + ARRF). Use the following rates for estimating taxable stumpage: Harvest Cost = tons (\$27.55 for sawlog sorts, \$32.55 for poles, \$6.00 for utility). Haul Cost = (tons) (\$2.63 or \$3.63 for poles) + tons (\$0.16x C miles) + tons (\$0.14 x A miles). ARRF = \$22.25/mbf.

SPECIAL REMARKS: The successful Purchaser(s) will be required to purchase logs from the sale area upon delivery to their location specified in the bid submitted. Logs will be delivered to the Purchaser's delivery location by the State's contract harvester. Purchaser is responsible for weighing and scaling costs. All mbf and tonnage loads will be weighed and all mbf loads will be scaled at State approved scaling locations. The State reserves the right to determine where logs are authorized to be scaled and weighed.

For more information regarding this log sort sale visit our web site:
<http://www.dnr.wa.gov/htdocs/fr/sales/>. If you have questions call Bob McKellar at the Northeast Region office at 509-684-7474 or Mike Chandler at the Product Sales and Leasing Division Office in Olympia at 360-902-1738.


CONFIRMATION: Each sort is subject to confirmation following auction. No sorts will be confirmed until at least 10 days after all sorts are successfully auctioned.

Timber Sale Map

SALE NAME: Power Peak Sorts
 AGREEMENT NO.: 30-079913
 TRUST(S): School


REGION: NORTHEAST
 COUNTY: Pend Oreille

Township 31 North, Range 43 East, W. M.
 (Map 1 of 3)



Note: Road details can Be found in the Road plan in The timber sale Contract.

Acres = Net Acres
Elevation = 2880' - 4240'
Exterior R/W = 15 Ac.



- Ground Skidding
- Cable Skidding
- Timber Sale Boundary Tags
- Existing Road
- New Construction
- Required Reconstruction
- Designated Skid Trail
- Stream
- Section/Property Line




Scale: 1" = 1000
 Drawn By: S. M.
 DATE: 12/11/2006

Timber Sale Map

SALE NAME: Power Peak Sorts
 AGREEMENT NO.: 30-079913
 TRUST(S): School

REGION: NORTHEAST
 COUNTY: Pend Oreille

Township 31 North, Range 43 East, W. M.
 (Map 2 of 3)




Note: Road details can be found in the Road plan in The timber sale Contract.

Acres = Net Acres


Elevation = 3560' - 4320'

External R/W = 15 Ac.

Vicinity Map
 (not to scale)



	Ground Skidding
	Cable Skidding
	Existing Road
	New Construction
	Pre-haul Maintenance
	Designated Skid Trail
	Stream
	Section/Property Line




Scale: 1" = 1000
 Drawn By: S. M.
 DATE: 12/07/2006

Timber Sale Map

SALE NAME: Power Peak Sorts
 AGREEMENT NO.: 30-079913
 TRUST(S): School

REGION: NORTHEAST
 COUNTY: Pend Oreille


Township 32 North, Range 43 East, W. M.
 (Map 3 of 3)



**Note: Road details can
 Be found in the
 Road plan in
 The timber sale
 Contract.**

Acres = Net Acres

Elevation = 2280' - 2560'



Scale: 1" = 1000'
 Drawn By: S. M.
 DATE: 12/07/2006

TIMBER NOTICE OF SALE

SALE NAME: APOLLO AERIAL

AGREEMENT NO: 30-077259

AUCTION: April 23, 2007 starting at 10:00 a.m., **COUNTY:** Skagit
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 5 miles northeast of Sedro-Woolley

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint at DBH and root collar, trees tagged out with yellow leave tree tags, dead and down cedar trees, logs, snags, and stumps, and other blowdown trees, logs and snags that do not have needles or small limbs, bounded by: white timber sale boundary tags and young stands. The above described products on part(s) of Sections 20 all in Township 36 North, Range 5 East, W.M., containing 58 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade									
					1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	27	8	1,619	\$256.00				210		1,111	288	10		
Hemlock	19	8	955	\$55.00						488	337	130		
Red cedar	18		318	\$560.00							260	58		
Red alder	18		80	\$410.00						38	21	21		
Maple	14		6	\$410.00									6	
Other			1	\$20.00										
Sale Total			2,979											

MINIMUM BID: \$256/MBF (est. value \$680,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$68,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Helicopter, Cable and Shovel. Small tagged out area in Unit #1 is delineated by white timber sale boundary tags. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 16.33 stations of required construction. 109.82 stations of required reconstruction. 21.97 stations of optional construction. 17.40 stations of optional reconstruction. 39.37 stations of road to be abandoned if built.

Development of an existing gravel source at station 36+33 of the MC-1320 road will involve processing rock to generate gravel ballast. This rock is available at no cost on State land in Section 20, Township 36 North, Range 5 East, W.M.

Development of an existing hardrock source at milepost 0.5 of the ML-1000 road will include drilling and shooting to generate riprap. This rock is available at no cost on State land in Section 31, Township 37 North, Range 5 East, W.M.

Development of an existing gravel source at milepost 0.11 of the MC-2100 road will include processing rock to generate gravel ballast. This rock is available at no cost on State land in Section 7, Township 36 North, Range 5 East, W.M.

Road construction, road reconstruction, road abandonment and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce damage to water, soil, road and other forest assets. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce damage of water, soil, roads and other forest assets.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse and laser/compass. 64.5 acres gross. 6 acres deducted for green tree retention clumps, an inner gorge, and an existing grade. 58 acres net. Cruised using variable plot method. Expansion factor used is 62.5 for unit 1, 40 for unit



TIMBER NOTICE OF SALE

1-A, and 54.45 for unit 2. Sighting height is 4.5 feet. Grid size plot spacing is 280 X 200 feet in Units 1 and 1-A and 200 X 200 feet for Unit 2. Plot ratio cruise count is 1:1 in Units 1 and 2. All plots were cruised in 1-A. 19 plots were taken in Unit 1, 4 in Unit 1-A, and 38 plots were taken in Unit 2, for a total of 61 plots.

FEES: \$39,458.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Unit #1 was broken into 2 areas due to the extreme difference in volume and species. Small portion to the west is mostly hardwood while remaining portion is mostly large Douglas-fir. Unit #2 contains more defective western hemlock and western red cedar.

The MC-1000 and MC-1300 Roads shall be reconstructed prior to June 1, 2008 as per Road Plan.


"Other" in species is utility as defined under L-10 clause.

TIMBER SALE MAP

SALE NAME: Apollo Aerial
AGREEMENT NO: 30-077259
TRUST(S): Forest Board Transfer (01)

REGION: Northwest
COUNTY(S): Skagit
ELEVATION: 960 - 2,200 Feet

Township 36 North, Range 5 East, W.M.




Drawn By: Mark Arneson
 Date: March 21, 2006
 Version: 1.3

SALE NAME: Apollo Aerial
 AGREEMENT NO: 30-077259
 TRUST(S): Forest Board Transfer

REGION: Northwest
 COUNTY(S): Skagit

Vicinity Map

- Not to Scale -



Drawn By: Mark Arneson
 Date: March 27, 2006

Legend

Units

- ~~~~~ Sale Boundary Tags
- ~~~~~ R/W Boundary Tags

Logging Methods

- //// Sale Area
- XXXX Helicopter

Roads

- ==== Existing Road
- Optional Construction
- ==== Required Reconstruction
- ==== Paved Road

Streams

- Type 1-5
- RMZ

Symbols

- * Water Type Break
- ⊕ Marked Leave Trees
- ⊗ Rock Pit
- ⊕ Landing
- 3 Water Type
- Gate
- ◆ Survey Corner

TIMBER NOTICE OF SALE

SALE NAME: VERBENA

AGREEMENT NO: 30-078829

AUCTION: April 23, 2007 starting at 10:00 a.m., **COUNTY:** Skagit
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 18 miles east of Sedro-Woolley

PRODUCTS SOLD AND SALE AREA: All timber including trees marked with orange paint (and orange paint plus blue special unit management tags), except trees marked with blue paint on the bowl and root collar, forest products tagged out by yellow leave tree area tags, and forest products tagged out by blue special unit management tags and NOT marked with orange paint, bounded as follows: by white timber sale boundary tags and property line in Unit #1; by white timber sale boundary tags and property line in Unit #2. All timber bounded by orange right of way tags. The above products on part(s) of Sections 25, 26 and 27 all in Township 36 North, Range 6 East, W.M., containing 73 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	15	8	2,369						1,034	1,050	285	
Douglas fir	20	8	664						371	251	42	
Silver fir	20		581						349	173	58	
Red cedar	14		63							41	22	
Red alder	19		44							41	3	
Cottonwood	18		15						14		1	
Sale Total			3,736									

MINIMUM BID: \$775,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$77,500.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and Shovel. Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from October 16 to May 30 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 72.09 stations of required construction. 14.26 stations of required reconstruction. 19.04 stations of optional construction. 5.40 stations of existing road to be abandoned. 19.04 stations of road to be abandoned if built. Transportation and installation of a gate and lock box on the HO-2010 road.

Development of an existing hardrock source (Extra Innings Hardrock Pit) at station 22+00 of the HO-2940 Road will involve drilling, shooting, and processing rock to generate approximately 235 cubic yards of riprap. This rock is available at no cost on State land in Section 27, Township 36 North, Range 6 East, W.M.

Development of an existing gravel source (Section 2 Pit) at station 17+00 of the HO-2010 Road will involve processing rock to generate approximately 12,060 cubic yards of gravel ballast rock. This rock is available at no cost on State land in Section 2, Township 35 North, Range 6 East, W.M.

Road construction, road reconstruction, road abandonment and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. Acreage deducted for green tree retention clumps and existing road. 72.5 acres net. Cruised using variable plot method in Unit #1, Unit #2, Unit #1 R/W; and 100% in Unit #2 R/W. Expansion factor used is 40.00 in the WMZ; 54.45 in Unit #1, Unit #2, and Unit #1 R/W. Sighting height is 4.5 feet. Grid size plot spacing is 320 X 200 feet in Units #1 and #2, and in WMZ; 600 feet apart in Unit #1 R/W. Plot ratio cruise count is 1:1 in Units #1 and #2; cruised all in the WMZ and Unit #1 R/W; cruised



TIMBER NOTICE OF SALE

1:5 in Unit #2 R/W. 13 plots were taken in Unit #1, 31 plots taken in Unit #2, 3 plots taken in the WMZ, and 3 plots taken in Unit #1 R/W, for a total of 50 plots. Note: WMZ volume included in Estimated Sale Volumes and Quality section, but the 5.7 acres are not included in the Products Sold and Sale Area section above.



FEES: \$49,502.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Blue special management tags represent a WMZ with individual marked tree removal. Trees with blue tags may only be removed if the trees are also marked with orange paint.

TIMBER SALE MAP

SALE NAME: Verbenia
 AGREEMENT NO: 78829
 TRUST(S): Forest Board 01


REGION: Northwest
 COUNTY(S): Skagit
 Elevation: 2700 - 3050



- Legend**
- WMZ partial cut area
 - Existing Road
 - Required Construction
 - Required Reconstruction
 - Optional Construction
 - Sale Boundary Tags
 - RW Boundary Tags
 - Management Unit Boundary Tags
 - Logged Area Boundary
 - Leave Tree Area
 - Survey Monument
 - Rock Pit
 - Water Type
 - Type 1-S Stream
 - Sale Area

Vicinity Map

Not To Scale



Drawn By: S.N. Clark
 Date: October 4, 2006

TIMBER NOTICE OF SALE

SALE NAME: PROUD MONKEY VDT

AGREEMENT NO: 30-079907

AUCTION: April 26, 2007 starting at 10:00 a.m., **COUNTY:** Skamania
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 8 miles north of Stevenson, WA

PRODUCTS SOLD AND SALE AREA:

All timber as described in Schedule A, except leave trees tagged out with leave tree area boundary tags, leave trees marked with blue paint, snags, pre-existing stumps and down timber existing two years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod, and right of way tags along the CG-2037 road in Units #1; timber sale boundary tags, special management boundary tags (facing into Special Management Unit identifying regeneration harvest) and right of way tags along the CG-2037 road in Units #2; timber sale boundary tags and the right of way tags along the CG-2037 road, except timber between the right of way tags in Unit #3; all timber bounded by right-of-way boundary tags on part(s) of Sections 1, 2, 10, 11 and 12 all in Township 3 North, Range 7 East, W.M., containing 136 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	13.4	8	1,676	11,275	\$34.25						429	1,097	150	
Hemlock	13.8	8	4	25	\$34.25						2	2		
Sale Total			1,680	11,300										

MINIMUM BID: \$34.25/ton (est. value \$387,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$77,400.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Hemlock, Douglas fir

BID DEPOSIT: \$38,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable, Shovel, Track skidder and Forwarder. Cable harvesting equipment, with ground-based harvesting equipment (shovel, tracked equipment and forwarder) being restricted to slopes of 35% or less during dry soil conditions. Intermediate support will/may be required to prevent soil rutting in Units #2 and #3 off the CG-2037 Road. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. All corridors within Units #2 and #3 will be marked and pre-approved by the Contract Administrator before logging. If Purchaser tailholds on State land, tailhold straps shall be used when tailholding on live trees to minimize damage and approved in writing by the Contract Administrator. See Schedule L for additional harvesting restrictions. See Schedule A for harvesting descriptions.

ROADS: 47.99 stations of required reconstruction. 5.11 stations of optional construction. 19.54 stations of required pre-haul maintenance. 5.11 stations of road abandonment. 9.97 feet of road deactivation. Rock is available at no charge from the State's Spring Rock Pit (CG-2037) located in Section 10, Township 03 North, Range 07 West, W.M. Work in the Spring Rock Pit (CG-3037) is prohibited from March 1 to August 31, due to northern spotted owl restrictions. Rock may also be obtained from any commercial source as approved in writing by the Contract Administrator. Purchaser shall stockpile 1,000 cubic yards of 3-INCH JAWRUN rock and 300 cubic yards of PITRUN rock at the Spring Rock Pit (CG-3037). Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Acres were determined by aerial photo dot grid for the units, and length times width for the right of way acres. The sale was cruised using a variable plot method in the units and Individual Tree Species along the right of ways.. Harvesting activities are estimated to be 20% cable and 80% ground-based harvesting systems..

FEES: \$22,260.00 is due on day of sale. \$1.37 per ton is due upon removal. These are in addition to the bid price.



TIMBER NOTICE OF SALE


SPECIAL REMARKS: All timber shall be yarded and hauled within 90 days of being felled. Special Management Units (SMU's), regeneration harvest patches, are bounded by blue SMU boundary tags that face into the patches (See map for details). No harvesting operations will be permitted, including cable lines, in the leave tree areas (skips). Timing restrictions are described as no operation of heavy equipment within the Spring Rock pit (CG-2037) between March 1 to August 31 due to spotted owl timing restrictions.

TIMBER SALE MAP

SALE NAME: PROUD MONKEY VDT
AGREEMENT NO: 30-079907
TRUST(S): State Forest Board Transfer (01) & Scientific School (10)


REGION: Pacific Cascade
COUNTY(S): Skamania

Township 03 North, Range 07 East, W.M.




Legend

- Thinning Area
- Special Management Area
- Leave Tree Area
- RMZ
- Sale Boundary Tags (White)
- Leave Tree Tags (Yellow)
- Special Management Tags (Blue)
- Right of Way Boundary Tags (Orange)
- Existing Roads
- Pre-haul Maintenance
- Required Reconstruction
- Optional Construction
- Streams
- Water Type 1 - 5
- Monumented Corner
- Leave Trees
- Existing Rock Pit



Drawn By: Shawn B. & Jared L.
 Date: January 26, 2007
 Scale: 1" = 1000'
 Elevation: 2,380ft. - 2,820ft.



TIMBER NOTICE OF SALE

SALE NAME: SUGAR MAGNOLIA CC & PC

AGREEMENT NO: 30-079761

AUCTION: April 23, 2007 starting at 10:00 a.m., **COUNTY:** Whatcom
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 10 miles east of Deming

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint at DBH and root collar and trees tagged out by yellow leave tree boundary tags, existing down logs and old stumps that do not have needles or small limbs, snags that do not have needles or small limbs, cedar snags, and dead and down cedar, bounded by white timber sale boundary tags in Unit A. All timber as described in Schedule B, all timber in yarding corridors, except trees marked with yellow paint at DBH and root collar and existing down logs and old stumps that do not have needles or small limbs, snags that do not have needles or small limbs, cedar snags, and dead and down cedar, bounded by white timber sale boundary tags in Units B, C, D and RMZs A, B and C. All timber bounded by orange right-of-way tags. The above described products on part(s) of Sections 9, 10 and 16 all in Township 38 North, Range 6 East, W.M., containing 110 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	11	6	1,514	\$92.00				16		199	782	517	
Douglas fir	18	6	688	\$269.75						369	254	65	
Silver fir	11		129	\$92.00						20	71	38	
Red alder	12		106	\$247.00							19	87	
Red cedar	17		73	\$622.00							70	3	
Sale Total			2,510										

MINIMUM BID: \$269.75/MBF (est. value \$408,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$81,600.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$40,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable, Shovel and Forwarder. Cable; cable or shovel on slopes 25% or less. Cutting and yarding will not be permitted in Units B, C and D during the bark slippage season unless authorized in writing by the Contract Administrator. This season is estimated to run from April 1- July 1 but will vary dependent on weather conditions. If permission is granted to operate during the bark slippage season the purchaser will be required to provide a plan outlining mitigation measures. Falling and Yarding will not be permitted from November 15 to March 1 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

ROADS: 12.41 stations of optional construction. 12.41 stations of road to be abandoned if built.

Existing stockpile of gravel ballast at milepost 2.4 of the USFS 38 road and existing stockpile of gravel ballast at milepost 0.1 of the PC-1000 road are available for use at no cost on State land.

Development of an existing gravel source (S-1100 Pit) at milepost 0.4 of the S-1100 Road will involve processing rock to generate gravel ballast. Rock from this pit may be used for gravel ballast rock if there is not enough available in the two stockpiles. This rock is available at no cost on State land. If the S-1100 pit is used, the following timing restrictions must be adhered to: Activities may occur at the rock-pit between Dec.1st and Feb.15th of any year, but only during daylight hours. (NON-WAIVABLE).

Development of an existing hardrock source (McCoy Pit) at milepost 2.3 of the JP-1300 Road will involve drilling, shooting, and processing rock to generate riprap. This rock is available at no cost on State land.



TIMBER NOTICE OF SALE

Road construction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 15 to March 1 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 114.3 acres gross. 4.7 acres deducted for existing roads and leave tree areas. 109.6 acres net. Cruised using variable plot method. Expansion factor used is 40.00 for all stand assessment and entered as count plots. Cruise plots were taken using 40.00 BAF except for Unit A where a 54.45 BAF was used. Sighting height is 4.5 feet. Grid size plot spacing is 300 x 300 feet in Unit A and 400 x 400 in Units B, C and D. Plot ratio cruise count is 1:1. 18 plots were taken in Unit A, and 34 plots taken in Unit B, for a total of 52 plots. Note: This sale is comprised of 26.8 acres of regeneration harvest, 5.3 acres of right of way harvest, and 77.5 acres of partial cut.

FEES: \$33,257.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: (1) As part of the "Certification of Fallers and Yarder Operators", the Contract Administrator and faller/harvester operator will jointly review the take tree selection criteria as outlined in Schedule B of the sale contract. This must take place on site. (2) Orange marked trees do not have any meaning on this sale. This marking can be ignored. (3) This sale is comprised of 26.8 acres of regeneration harvest, 5.3 acres of right of way harvest, and 77.5 acres of partial cut.

Schedule B
Sugar Magnolia CC & PC Thinning Prescription

UNIT (S) B, C & D:

- Cut all Hardwoods
- Cut PSF up to 14 inches DBH
- Cut WH up to 14 inches DBH

Special Thinning Conditions: In areas where thinning is not necessary, i.e., prescription is met, do not put in yarding corridors or skid trails. These areas must be identified and agreed upon in advance with the Contract Administrator.

Ground yarding corridors: Corridors are limited to 14 feet wide (including rub trees) and no less than 70 feet apart as measured from the center of the corridor. Where possible corridors should be located in a manner to minimize the damage to or removal of leave trees. No yarding will take place on slopes greater than 25%.

Cable corridors: Landings will be located to provide for parallel yarding corridors whenever possible. Corridors will be limited to 12-feet including rub trees. Corridors will be at least 100 feet apart when parallel as measured from the center of the corridors. When radial yarding corridors are required from a central landing, the distance between yarding corridors must be no closer than 100 feet where the corridor leaves the unit as measured from the center of the corridors. Where possible corridors should be located in a manner to minimize the damage to or removal of leave trees. When corridors are field located, only leave trees within 3 – 5 feet of the center of the corridor should be removed prior to yarding. Following completion of yarding of each corridor, rub trees within 6 feet of the center of the corridor may be felled and yarded to the landing. It is not required to remove all leave trees from the 12-foot corridor.

Compartments for assessment of damage
Per contract clauses H-012 and D-040.

- D1 Easternmost area above main road, CW-1000
- D2 Easternmost area below main road, CW-1000
- C Center unit
- B Westernmost unit.

Down wood and snag recruitment: Trees marked with a yellow band have been designated for riparian habitat enhancement and are to be treated as listed in the chart below:

	Total trees marked in each RMZ*	Number of trees to be topped above 20 feet*	Number of trees to be felled into stream**
RMZ A	30	12	0**
RMZ B	8	3	0**
RMZ C	18	7	0**
Total	56	22	0**

There are a total of 56 trees marked; only 22 of the trees marked will receive treatment. The trees to receive treatment must be allocated to each RMZ as directed by the chart.

The decision was made to not have any trees felled into the streams. There is no lack of DWD in these streams.

Compliance

Diameter limit compliance will be monitored using a stump diameter- breast height diameter regression equation.

Certification of Fallers and Yarder Operators

(additional requirements beyond those outlined in H-011)

The Contract Administrator and faller/harvester operator will jointly review the take tree selection criteria as outlined in Schedule B of the sale contract.

In conjunction with the Contract Administrator, the faller/harvest operator will mark a designated area as a test plot within the sale area boundary. Satisfactory thinning of the test plot completes the certification process.


Certifications will be issued to individuals when they demonstrate to the Contract Administrator their ability to perform within the requirements set forth in the contract.

TIMBER SALE MAP

SALE NAME: Sugar Magnolia CC & PC
AGREEMENT NO: 30-079761
TRUST(S): School

REGION: Northwest
COUNTY(S): Whatcom
ELEVATION: 1,800 to 2,400 feet

T 38 N, R 6 E



Legend

Units

- ~~~~~ Sale Boundary Tags
- ~~~~~ R/W Boundary Tags

Logging Methods

- ////// Regeneration Harvest
- ////// Partial Cut
- ==== RMZ Harvest Area

Roads

- ==== Existing Road
- - - - Optional Construction

Streams


- Type 1-5
- RMZ

Symbols

- ⊗ Survey Corner
- ⊙ Leave Tree Area
- * Water Type Break
- ⊙ Landing
- ⊙ Water Type
- Gate
- ◆ Survey Corner
- ⊗ Bridge

Vicinity Map

Not To Scale



Drawn By: Mark Arneson
 Date: October 25, 2006
 Version: 1.1

TIMBER NOTICE OF SALE

SALE NAME: *EWEWHO Log Sorts*

AGREEMENT NO: *30-080659 -- 30-080633 and 30-080728*

AUCTION: April 24, starting at 10:00 a.m.,
Southeast Region Office, Ellensburg , WA.

COUNTY: Yakima

SALE LOCATION: Sale located approximately 30 miles west of Yakima WA.

PRODUCTS SOLD AND SALE AREA: All delivered timber, meeting the specifications described below; on parts of Sections 3, 4 and 5 all in Township 12 North, Range 14 East, Sections 33 all in Township 13 North, Range 14 East, W.M., , containing 323 acres, more or less.

MINIMUM BID AND ESTIMATED LOG SORT VOLUMES:

Agreement #	Sort #	Species and Sort Specifications	Average Log Length	Estimated Volume		Minimum Bid Delivered Prices		Total Appraised Value	Bid Deposit
				mbf	Tons	\$/mbf	\$/Ton		
30-080659	1	DF, WL 12" dib and larger	30'	354	1929	\$350.00	---	\$123,900.00	\$12,390.00
30-080660	2	AF, ES, LP 12" dib and larger	30'	237	1283	\$300.00	---	\$71,100.00	\$7,110.00
30-080661	3	DF, WL 6" to 11" dib	---	594	3284	---	\$65.00	\$213,460.00	\$21,346.00
30-080662	4	AF, ES, LP 6" to 11" dib	---	1167	6705	---	\$40.00	\$268,200.00	\$26,820.00
30-080663	5	GF 6" dib and larger	27'	388	2174	\$350.00	---	\$135,800.00	\$13,580.00
30-080728	6	Utility 2" and larger	---	1866	11456	---	\$35.00	\$400,960.00	\$40,096.00
Totals				4606	26831			\$1,213,420	

BID METHOD: Sealed Bids

UNIT OF MEASURE: MBF scale/Tonnage scale

EXPIRATION DATE: January 31, 2008

ALLOCATION: Export Restricted

PAYMENT SECURITY: To be determined by the State as described in Clause P-041 of the Purchaser's Contract.

BIDDING PROCEDURES: A separate sealed bid and envelope must be submitted for each log sort. Prospective Purchasers may bid on any or all log sorts. On the day of sale the Purchaser must bring their bid deposit up to 10% of their total bid price. Complete bidding procedures and auction information may be obtained from the Southeast Region Office in Ellensburg, WA. Phone number (509) 925-8510.

HARVEST AND DELIVERY COSTS: Purchaser must pay the forest excise taxes associated with the log sorts delivered to them. The tax rate for this sale is 4.2%. Taxable Stumpage = Total Delivered Value – (Harvest Cost + Haul Cost + ARRF). Use the following rates for estimating taxable stumpage: Harvest Cost = tons(\$24.41). Haul Cost = (tons)(\$2.63) + tons(\$0.16x C miles) + tons(\$0.141 x A miles)). ARRF = \$22.25/mbf.

SPECIAL REMARKS: The successful Purchaser(s) will be required to purchase logs from the sale area upon delivery to their location specified in the bid submitted. Logs will be delivered to the Purchaser's delivery location by the State's contract harvester. Purchaser is responsible for weighing and scaling costs. All mbf and tonnage loads will be weighed and all mbf loads will be scaled at State approved scaling locations. The State reserves the right to determine where logs are authorized to be scaled and weighed.

For more information regarding this log sort sale visit our web site:
<http://www.dnr.wa.gov/htdocs/fr/sales/>. If you have questions call Linda Hazlett at the Southeast Region office at (509) 925-8510.

CONFIRMATION: Each sort is subject to confirmation following auction. No sorts will be confirmed until at least 10 days after all sorts are successfully auctioned.


TIMBER SALE MAP

February 7, 2006

Sale Name: Ewewho
Agreement Number: 77380
Trust(s): Common School / Indemnity

Region: Southeast
County(s): Klickitat

Township 12 North, Range 14 East, W.M.



- Timber Sale Boundary
- Existing Road
- Required Pre-haul Maint.
- Required Construction - ROW Tagged
- Forested Wetland - with Timber Sale Tags
- Streams
- Water Type
- PIP

Elevation 4,800 ft - 6,175 ft

1:15,000





VICINITY MAP

February 8, 2006

Sale Name: Ewewho
Agreement Number: 77380
Trust(s): Common School / Indemnity

Region: Southeast
County(s): Klickitat



TIMBER NOTICE OF SALE

SALE NAME: SNOW TROUT FI Log Sorts **AGREEMENT NO:** 30-80712 - 30-80718

AUCTION: April 24, 2007, starting at 10:00 a.m., **COUNTY:** Klickitat and Yakima
Southeast Region Office, Ellensburg, WA.

SALE LOCATION: Sale located approximately 4 miles west northwest of Trout Lake WA off of State Route 141 and approximately 7 miles northwest of Glenwood WA off of the Mt Adams Highway.

PRODUCTS SOLD AND SALE AREA: All delivered timber, meeting the specifications described below; on parts of Section 18, Township 6 North, Range 10 East, and parts of Sections 2, 22 and 23, Township 7 North, Range 12 East, and parts of Sections 22, 26, 27 and 34, Township 7 North, Range 12 East, W.M., containing 1078 acres, more or less.

MINIMUM BID AND ESTIMATED LOG SORT VOLUMES:

Agreement #	Sort #	Species and Sort Specifications	Estimated Volume		Minimum Bid Delivered Prices		Total Appraised Value	Bid Deposit
			Tons	Mbf	\$/Ton	\$/Mbf		
30-080712	1	DF/WL 7"+ dib Saw	3,857	599	\$55.00	-----	\$212,135.00	\$21,213.50
30-080713	2	GF/AF/ES 7"+ dib Saw	10,058	2112	\$45.00	-----	\$452,610.00	\$45,261.00
30-080714	3	LP 7"+ dib Saw	4,318	843	\$40.00	-----	\$172,720.00	\$17,272.00
30-080715	4	PP 12"+ dib Saw	1,083	245	-----	\$420	\$102,900.00	\$10,290.00
30-080716	5	PP 6"-11" dib Saw	4,999	986	\$35.00	-----	\$174,965.00	\$17,496.50
30-080717	6	All Species 4.5"- 6" dib	7,814	1899	\$35.00	-----	\$273,490.00	\$27,349.00
30-080718	7	All Species Pulp 2.5" - 4"	2,894	1241	\$35.00	-----	\$101,290.00	\$10,129.00
Totals			35,023	7925			\$1,490,110	

BID METHOD: Sealed Bids **UNIT OF MEASURE:** Tonnage scale

EXPIRATION DATE: March 30, 2008 **ALLOCATION:** Export Restricted

PAYMENT SECURITY: To be determined by the State as described in Clause P-041 of the Purchaser's Contract.

BIDDING PROCEDURES: A separate sealed bid and envelope must be submitted for each log sort. Prospective Purchasers may bid on any or all log sorts. On the day of sale the Purchaser must bring their bid deposit up to 10% of their total bid price. Complete bidding procedures and auction information may be obtained from the Southeast Region Office in Ellensburg, WA. Phone number (509) 925-8510.

HARVEST AND DELIVERY COSTS: Purchaser must pay the forest excise taxes associated with the log sorts delivered to them. The tax rate for this sale is 4.2%. Taxable Stumpage = Total Delivered Value - (Harvest Cost + Haul Cost + ARRF). Use the following rates for estimating taxable stumpage: Harvest Cost = tons(\$19.75/ton). Haul Cost = (tons)(\$2.63) + tons(\$0.16x C miles) + tons(\$0.14 x A miles)). ARRF = \$22.25/mbf.

SPECIAL REMARKS: The successful Purchaser(s) will be required to purchase logs from the sale area upon delivery to their location specified in the bid submitted. Logs will be delivered to the Purchaser's delivery location by the State's contract harvester. Purchaser is responsible for weighing and scaling costs. All mbf and tonnage loads will be weighed and all mbf loads will be scaled at State approved scaling locations. The State reserves the right to determine where logs are authorized to be scaled and weighed.

For more information regarding this log sort sale visit our web site:
<http://www.dnr.wa.gov/htdocs/fr/sales/>. If you have questions call Rod Pfeifle at the Southeast Region office at (509)925-8510.


CONFIRMATION: Each sort is subject to confirmation following auction. No sorts will be confirmed until at least 10 days after all sorts are successfully auctioned.

TIMBER SALE MAP *Map 1 of 3 - UNIT 1*

Sale Name: Snowtrout FI Sorts
Agreement Number: 30-078686
Trust(s): (1) State Forest Board-Transfer, (03) Common School,
 (05) University Transfer, (06) CEP & RI

Region: Southeast
County: Klickitat


Township 6 North, Range 10 East, W.M.



1 inch equals 1,000 feet

*Elevation Range 3160 - 3400 Feet
 Contour Interval - 40 Feet
 See Road Plan Map for detailed information*


- ~~~~~ Timber Sale Boundary
- Existing Road
- >—> Fish
- >->-> Non-Fish



Sale Name: Snowtrout FI Sorts
Agreement Number: 30-078686
Trust(s): Common School,

Region: Southeast
County: Klickitat

Township 7 North, Range 11 East, W.M.



1 inch equals 1,000 feet

*Elevation Range 3640 - 4880 Feet
 Contour Interval - 40 Feet
 See Road Plan Map for detailed information*


- ~~~~~ Timber Sale Boundary
- - - - Required Construction
- ==== Required Reconstruction
- Existing Road
- ////// RMZ
- ➡ Fish
- ➡➡➡ Non-Fish
- 🟦 NS Pond



Sale Name: Snowtrout FI Sorts
Agreement Number: 30-078686
Trust(s): (03) Common School, (05) University Transfer, (10) Scientific School

Region: Southeast
County: Klickitat

Township 7 North, Range 12 East, W.M.



1 inch equals 1,000 feet

Elevation Range 3160 - 3400 Feet
Contour Interval - 40 Feet
See Road Plan Map for detailed information


- ~~~~~ Timber Sale Boundary
- - - - Required Construction
- ==== Required Reconstruction
- Existing Road
- XXXXX ELZ
- > Fish
- - - -> Non-Fish



Sale Name: Snowtrout FI Sorts
Agreement Number: 30-078686
Trust(s): Common School,

Region: Southeast
County: Klickitat

Township 7 North, Range 11 East, W.M.



1 inch equals 1,000 feet

Elevation Range 3640 - 4880 Feet
Contour Interval - 40 Feet
See Road Plan Map for detailed information

- ~~~~~ Timber Sale Boundary
- Existing Road
- > Fish
- - -> Non-Fish



0 0.1 0.2 0.4 Miles


VICINITY MAP

Map 1 of 2 - UNIT 1

October 25, 2006

Sale Name: Snowtrout FI Sorts
Agreement Number: 30-078686
Trust(s): (1) State Forest Board-Transfer, (03) Common School,
(05) University Transfer, (06) CEP & RI


Region: Southeast
County: Yakima



1:40,000

● Station points

Travel 2.55 miles west on SR-141 from Trout Lake to the start of the T-6000. Take the T-6000 2.8 miles up to the start of Unit 1.




VICINITY MAP

Map 2 of 2 - UNIT 2,3,4,5

October 25, 2006

Sale Name: Snowtrout FI Sorts
Agreement Number: 30-078686
Trust(s): (1) State Forest Board-Transfer, (03) Common School,
 (05) University Transfer, (06) CEP & RI

Region: Southeast
County: Yakima



1:70,000

Travel East from Glenwood 0.51 miles then turn north 2.1 miles on Mt. Adams Highway to the K-1000 blacktop. Turn left going east on the K-1000 for 0.4 miles to unit 5 or 1.3 miles to the K-4000. Turn left onto the K-4000 where you can do the following to access units:
 UNIT 3 Continue on the K-4000 for 6.4 miles.
 UNIT 4 Continue on the K-4000 for 4.7 miles to the K-5420 then turn north 0.9 miles to the K-5000. Continue north on the K-5000 for 1.3 miles and then turn left NW onto the K-5600 for 0.9 miles.
 UNIT 2: From the Trout Lake Hwy (0.41 miles west of Glenwood) take the S-2100 a distance of 1.1 miles north to the S-4000. Drive the S-4000 for 2.2 miles to the K-2000. Drive the K-2000 for 0.66 miles where the K-2000 temporarily becomes the K-3000 for 622 feet. Continue left on the K-2000 for 1.1 miles. Turn right onto the K-2300 and drive for 1.3 miles. Turn right onto the K-3121 for 0.3 miles and then turn right on the K-3120 for 0.38 miles. Turn left onto the K-3100 for 1.26 miles. Here you take the tie road north for 1205 feet to the K-3000. Turn left going west for 0.36 miles to unit 2.



TIMBER NOTICE OF SALE

SALE NAME: EGLON HEIGHTS THINNING

AGREEMENT NO: 30-077667

AUCTION: April 24, 2007 starting at 10:00 a.m., **COUNTY:** Kitsap
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 3 miles north of Kingston

PRODUCTS SOLD AND SALE AREA: All timber as described in Schedule A bounded by white timber sale boundary tags, property lines marked with yellow flagging, and the PA-1 Road in Unit #1; all timber as described in Schedule B bounded by white timber sale boundary tags, PA-15 and PA-1 Roads are marked with pink flagging in Unit #2; all timber bounded by orange Right of Way boundary tags on part(s) of Sections 10, 11 and 14 all in Township 27 North, Range 2 East, W.M., containing 193 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	11.4	5	796	6,336	\$8.00							529	267	
Red alder	9.8		97	685	\$19.00									97
Grand fir	22.2		18	108	\$8.00						13	4		1
Maple	10.5		15	95	\$19.00									15
Sale Total			926	7,224										

MINIMUM BID: \$8/ton (est. value \$66,000.00) **BID METHOD:** Sealed Bids
PERFORMANCE SECURITY: \$13,200.00 **SALE TYPE:** Tonnage Scale
EXPIRATION DATE: October 31, 2008 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Grand fir, Douglas fir Combined

BID DEPOSIT: \$6,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground based equipment. Falling and Yarding will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends, state recognized holidays or Monday through Friday from 7 pm to 7 am.

ROADS: 59.33 stations of optional construction. 40.34 stations of optional reconstruction. 0.75 stations of optional deactivation, if constructed. Purchaser maintenance on all roads used. Road construction will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends, state recognized holidays or Monday through Friday from 7 pm to 7 am. The hauling of forest products will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends, state recognized holidays or Monday through Friday from 7 pm to 7 am.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by GPS. Unit #1 acres were recalculated following the cruise. The cruise is based on 154 acres in Unit #1, but was recalculated as 133 acres. Unit #2 and Right of Way acres are the same as the cruise. Units #1 and #2 were cruised using a variable plot sample with a BAF of 20 on a 600 x 600 foot grid. Right of Way was cruised using a variable plot sample with a BAF of 20 every 500 feet.

FEES: \$12,270.00 is due on day of sale. \$1.02 per ton is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: This sale may have an Extreme Hazard Abatement requirement.

TIMBER SALE MAP

SALE NAME: EGLON HEIGHTS THINNING
 AGREEMENT NO: 30-077667
 TRUST(S): COMMON SCHOOL, UNIVERSITY ORIGINAL

REGION: SOUTH PUGET SOUND REGION
 COUNTY(S): KITSAP

TOWNSHIP 27 NORTH, RANGE 2 EAST, W.M.




ELEVATION: 226 feet

LEGEND

- ~~~~~ White Timber Sale Boundary Tags
- Property Line marked with yellow flagging
- Orange Right of Way Boundary Tags
- ===== Existing Road
- Optional Construction
- Optional Reconstruction
- ▨ Harvest Area
- ▤ RMZ/WMZ
- Stream
- * Water Type Break
- ⊕ Designated Landing
- 🏠 Structure
- ⏟ Wetland
- 3 Water Type
- ◆ Survey Corner

VICINITY MAP Not to Scale



Drawn By: A. Mainwaring
 Date: November 7, 2006

TIMBER NOTICE OF SALE

SALE NAME: DAWGHOUSE VDT

AGREEMENT NO: 30-078904

AUCTION: April 26, 2007 starting at 10:00 a.m., **COUNTY:** Skamania
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 10 miles northeast of Washougal, WA

PRODUCTS SOLD AND SALE AREA: All timber, except leave trees as described in Schedule A, pre-existing stumps, snags and down timber existing two years prior to the day of sale, bounded by timber sale boundary tags, special management boundary tags (facing into Special Management Unit), reprod and the W-1300 and W-1330 roads in Unit #1; timber sale boundary tags and the W-1220A and W-1222A roads in Unit #2; timber sale boundary tags, special management boundary tags (facing into Special Management Unit), reprod and the W-1225 and W1225D roads in Unit #3; all timber bounded by right-of-way boundary tags and orange painted trees on part(s) of Sections 10, 15, 21, 22, 23 and 26 all in Township 2 North, Range 5 East, W.M., containing 148 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	11.5	5	719	4,809	\$14.10						168	329	222	
Red alder	11.4		229	1,827	\$16.00						5	44	180	
Maple	12.2		27	251	\$16.00						1	1	25	
Hemlock	18.2	6	2	15	\$14.10						2			
Sale Total			977	6,902										

MINIMUM BID: \$14.1/ton (est. value \$101,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$20,200.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: October 31, 2008 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Hemlock and Douglas fir combined.

BID DEPOSIT: \$10,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel and tracked harvesting equipment being restricted to slopes of 35% or less during dry soil conditions. Intermediate supports will be needed on some settings to avoid blind leads and maintain lead-end suspension. See clause H-140 for further harvest requirements.

ROADS: 18.35 stations of required construction. 125.78 stations of required reconstruction. 34.12 stations of optional construction. 15.37 stations of optional reconstruction. 5.14 stations of Required Pre-haul Maintenance. 49.49 stations of road abandonment. Rock for construction, reconstruction, and/or pre-haul maintenance under this contract may be obtained from the sources listed below or any commercial source, as approved in writing by the Contract Administrator. Longview Fibre's W-1230 road pit located in Section 10 and W-1300 road pit located in Section 25, Township 2 North, Range 5 East, W.M. Road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator or unless the purchaser elects to provide more rock, at their own cost, than specified in the road plan, which would be sufficient for wet weather hauling.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acreage was determined by aerial photo dot grid count, and the sale area was cruised using a variable plot cruise method adjusted for volume removals. Harvesting activities are estimated to be 35% ground based and 65% cable harvesting.

FEES: \$12,950.00 is due on day of sale. \$1.27 per ton is due upon removal. These are in addition to the bid price.




SPECIAL REMARKS: Special Management Units (SMU's) are bounded by blue SMU boundary tags that face into the SMU's (See map for details). Purchaser shall furnish and install a 20 feet wide permanent steel gate mounted on steel gateposts at station 0.20 on the W-1220 road. Gate keys may be obtained from the Region office. See vicinity map for gate locations.

TIMBER SALE MAP


SALE NAME: DAWGHOUSE VDT
AGREEMENT NO: 30-078904
TRUST(S): State Forest Board Transfer (01) & Common School (03)

REGION: Pacific Cascade
COUNTY(S): Skamania

Township 02 North, Range 05 East, W.M.



Drawn By: Shawn B. & Ellen S.
 Date: January 25, 2007
 Scale: 1" = 1000'
 Elevation: 680ft. - 1,720ft.



TIMBER NOTICE OF SALE

SALE NAME: *Bird Creek Log Sorts* **AGREEMENT NO:** *30-080854 - 30-080858*

AUCTION: April 24, 2007, starting at 10:00 a.m.,
Southeast Region Office, Ellensburg, WA.

COUNTY: Yakima

SALE LOCATION: Sale located approximately 5 miles north northwest of Glenwood.

PRODUCTS SOLD

AND SALE AREA: All delivered timber, meeting the specifications described below; on parts of Sections 36, Township 7 North, Range 11 East and parts of Sections 31, Township 7 North, Range 12 East, containing 274 acres, more or less.

MINIMUM BID AND ESTIMATED LOG SORT VOLUMES:

Agreement No.	Sort #	Sort Description Species / DIB	Estimated Volume Mbf/Tons	Minimum Bid Delivered Prices	Total Appraised Value	Bid Deposit	Average Log Length
30-080854	6	PP 6"-11" Saw	3116 Tons	\$35.00/Ton	\$109,060.00	\$10,906.00	N/A
30-080855	7	PP 12"+ Saw	356 Mbf	\$420.00/Mbf	\$149,520.00	\$14,952.00	30' Saw
30-080856	8	GF, Other 4.5"-6" Hew Saw	124 Tons	\$35.00/Ton	\$4,340.00	\$434.00	N/A
30-080857	9	GF, Other 7"+ Saw	1887 Tons	\$40.00/Ton	\$75,480.00	\$7,548.00	N/A
30-080858	10	Utility - Conifer	218 Tons	\$35.00/Ton	\$7,630.00	\$736.00	N/A

BID METHOD: Sealed Bids

UNIT OF MEASURE: MBF scale/Tonnage scale

EXPIRATION DATE: July 31, 2007

ALLOCATION: Export Restricted

PAYMENT SECURITY:

To be determined by the State as described in Clause P-041 of the Purchaser's Contract.

BIDDING PROCEDURES:

A separate sealed bid and envelope must be submitted for each log sort. Prospective Purchasers may bid on any or all log sorts. On the day of sale the Purchaser must bring their bid deposit up to 10% of their total bid price. Complete bidding procedures and auction information may be obtained from the Southeast Region Office in Ellensburg, WA. Phone number (509) 925-8510.

HARVEST AND DELIVERY COSTS:

Purchaser must pay the forest excise taxes associated with the log sorts delivered to them. The tax rate for this sale is 4.2%. Taxable Stumpage = Total Delivered Value - (Harvest Cost + Haul Cost + ARRF). Use the following rates for estimating taxable stumpage: Harvest Cost = tons (\$15.50/ton, \$9.00/ton for utility). Haul Cost = (tons)(\$2.10) + tons (\$0.13x C miles) + tons (\$0.11 x A miles)). ARRF = \$22.25/mbf.

SPECIAL REMARKS: The successful Purchaser(s) will be required to purchase logs from the sale area upon delivery to their location specified in the bid submitted. Logs will be delivered to the Purchaser's delivery location by the State's contract harvester. Purchaser is responsible for weighing and scaling costs. All mbf and tonnage loads will be weighed and all mbf loads will be scaled at State approved scaling locations. The State reserves the right to determine where logs are authorized to be scaled and weighed.

For more information regarding this log sort sale visit our web site:
<http://www.dnr.wa.gov/htdocs/fr/sales/>. If you have questions call Linda Hazlett at the Southeast Region office at (509) 925-8510 or Mike Chandler at the Product Sales and Leasing Division Office in Olympia at (360) 902-1738.

CONFIRMATION: Each sort is subject to confirmation following auction. No sorts will be confirmed until at least 10 days after all sorts are successfully auctioned.

Sale Name: Bird Creek Sorts


Region: Southeast


Agreement Number: #30-77408

County: Yakima

Trust: Charitable, Educational, Penal and Reformatory Institutions, School

Township 7 North, Ranges 11 & 12 East, W.M.



-  Road
-  Required Reconstruction
-  Timber Sale Boundary
-  Fence

Sale Name: Bird Creek Sorts

Region: Southeast

Agreement Number: #30-77408

County: Yakima

Trust: Charitable, Educational, Penal and Reformatory Institutions, School

Township 7 North, Ranges 11 & 12 East, W.M.

