

Washington State Department of Natural Resources (DNR)

Bidder's/Purchaser's Inspection of Sale Area and Forest Products

Acreage estimates and volume estimates contained within each timber notice of sale and each timber sale contract are made only for administrative and identification purposes. Except as expressly provided by the timber sale contract, the purchaser shall be responsible for paying the entire purchase price, even if the actual acreage or timber volume varies from the estimated quantity or volume shown.

All prospective bidders have the opportunity and are expected to inspect the sale area and the forest products located thereon. Bidders shall not rely on any representations by the State including, but not limited to, acreage estimates, volume estimates, appraisal or pre-bid documentation. The successful bidder/purchaser will further warrant that they have entered the timber sale contract without any reliance upon the DNR's volume estimates, acreage estimates, appraisals, pre-bid documentation, or any other representation by the DNR.

Any timber sale contract arising out of these public auctions will require the successful purchaser to warrant that they are entering the timber sale contract based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold.

Exclusion and Disclaimer of Warranties

The PARTIES AGREE that the IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, and ALL OTHER WARRANTIES EXPRESS OR IMPLIED, ARE EXCLUDED from this transaction, and shall not apply to the goods sold. For example, THE FOLLOWING SPECIFIC MATTERS ARE NOT WARRANTED, and are EXCLUDED from this transaction:

- a. ***The merchantability of the forest products.*** The use of the term “merchantable” in any document is not intended to vary the foregoing.
- b. ***The condition of the forest products.*** All forest products will be conveyed “AS IS.”
- c. ***The acreage contained within any sale area.*** Any acreage descriptions appearing in the timber notices of sale, timber sale contract, timber sale map or other documents are estimates only, provided solely for administrative and identification purposes.
- d. ***The volume, quality, or grade of the forest products.*** The descriptions of the forest products to be conveyed are estimates only, made solely for administrative and identification purposes.
- e. ***The correctness of any soil or surface conditions, presale construction appraisals, investigations, and all other pre-bid documents prepared by or for the State.*** These documents have been prepared for the State’s appraisal purposes only.
- f. ***That the sale area is free from threatened or endangered species, or their habitat.*** The State is not responsible for any interferences with forestry operations that result from the presence of any threatened or endangered species, or the presence of their habitat, within the sale area.
- g. ***That the forestry operations to be performed under this contract will be free from regulatory actions by governmental agencies.*** The State is not responsible for actions to enforce regulatory laws, such as the Washington Forest Practices Act (Chapter 76.09 RCW), taken by the Department of Natural Resources or any other agency that may affect the operability of these timber sales.
- h. Items contained in any other documents prepared for or by the State.

Please also see timber sale contract clause G-060 for further information.

BIDDING PROCEDURES FOR TIMBER AUCTIONS

The general requirements that follow are a part of all Timber Notices of Sale to be auctioned by the Department of Natural Resources (DNR).

General Information

The State reserves the right to waive minor irregularities and the right to reject any or all bids.

A. This book contains the timber notices of sale and maps for each timber sale scheduled to be auctioned. More specific information can be obtained by contacting the appropriate region office at the number listed on the back cover of this book.

B. The timber notice of sale is a summary of sale information. For more specific information, interested parties are encouraged to view the Appraisal Packets on the DNR Internet Site @ www.dnr.wa.gov, this will take you directly to the Product Sales Section. The Appraisal Packets contain **DRAFT** copies of the timber notice of sale, map, contract, road plan, cruise data, precruise and cruise narrative, Forest Practices Application (FPA), Hydraulics Project Approval (HPA).

C. The sale preview packets may be obtained at no charge for individual sales by visiting the appropriate region office.

D. Timber sale contracts contain extensive terms and conditions that will be binding upon successful high bidders. Each bidder should carefully review all terms contained in the appropriate **DRAFT** timber sale contract prior to bidding on a sale, and should review the final contract prior to signing. **DRAFT** timber sale contracts are contained in the preview and presales packets and are available upon request at the respective region office.

E. Sales advertised in this book have not been approved by the Board of Natural Resources and are subject to the Board's approval before they will be sold. The Board meets and approves sales approximately six weeks prior to auction. All sales are subject to confirmation by the DNR under RCW 79.15.120.

F. The State does not guarantee the accuracy of any information contained herein pertaining to particular sales. Therefore, all prospective purchasers are expected to make their own independent inspections and appraisals prior to bidding.

G. If any conflict exists between the information in the Timber Notice of Sale, timber sale map, sale preview packets and that in the timber sale contract, the signed contract will prevail.

H. Timber sales are subject to the Washington State Forest Excise Tax (RCW Chapter 84.33).

I. Within 30 days of sale confirmation, the apparent high bidder will provide to the State the Performance Security specified on each Notice of Sale.

J. Each DNR region office has information about sales offered in that region. For further information, contact the respective DNR region office. Region office addresses and telephone numbers appear on the back cover of this booklet.

K. The purchaser assumes the responsibility for any costs associated with extra maintenance or repair levied by a county for any county road used by the purchaser.

BIDDING PROCEDURES FOR TIMBER AUCTIONS (Continued)

Bidding Process

- A. All timber will be auctioned using the sealed bid method.
- B. Bids submitted on day of auction must be in the bid box at the specified auction location before 10:00 a.m. The respective DNR region office must receive mailed bids by 4:30 p.m., on the last business day before the auction. Bidders assume all risk for the method of delivery.
- C. The DNR has the right to reject bid forms that are completed incorrectly. *All bid forms must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. Revised documents are not permissible.* Bidding instructions are on the back of the Sealed Bid Form. A bid deposit must be included in the sealed bid envelope unless using a Timber Sale Statewide Bid Bond.
- D. All bids must include the completed Sealed Bid Form and bid deposit.
- E. Bids will be opened in each respective region in the order in which sales appear in the Public Auction Sale of Timber book (alphabetically by county and by agreement number).
- F. If a tie bid occurs, the names of the tie bidders will be placed in a hat and the successful bidder will be determined by a drawing.
- G. The apparent high bidder on a particular sale will have the option of withdrawing additional sealed bids submitted for any remaining sales to be auctioned. The apparent high bidder must exercise this option within two minutes after the apparent high bidder is announced.

Auction Time and Location

Auctions will start at 10:00 a.m. and close at 4:00 p.m. on the date and at the location specified in each Timber Notice of Sale.

Bid Deposits

- A. Required bid deposits are listed on each Timber Notice of Sale.
- B. Bid deposits must be in the form of cash, certified check, cashiers' check, money order or bid bond.
- C. Bid bonds may be either a Timber Sale Statewide Bid Bond or a Timber Sale Per Sale Bid Bond.
- D. All bid deposits shall be submitted by the person or entity submitting the bid and made payable to the Department of Natural Resources. **Third party deposits will not be accepted.**

Timber Sale Per Sale Bid Bonds

- A. The Per Sale Bid Bond shall guarantee payment of the bid deposit **within ten days of auction.**
- B. The balance between the bid bond and the Initial Deposit payment is due by 4:30 p.m., **on the day of auction.**
- C. Additional forms and instructions for a Per sale Bid Bond are available at any DNR region office.

Timber Sale Statewide Bid Bond

- A. Statewide Bid Bonds shall guarantee payment of the Initial Deposit on any statewide timber sale while the bond is in effect.
- B. The Statewide Bid Bond must be received by the Department of Natural Resources, Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction date. The bond shall be in the amount of \$150,000.00.
- C. The bidder must supply a list of persons authorized to bid using the bond. Bid bonds are subject to approval by the Department of Natural Resources.
- D. Successful bidders using a Statewide Bid Bond must pay the total Initial Deposit payment (10 percent of the total bid price) **by 4:30 p.m. on the day of auction.**
- E. A Statewide Bid Bond cannot be used to secure the Initial Deposit payment due the day of auction.
- F. Additional forms and instructions for a statewide bid bond are available at any DNR region office.

Payments

The initial deposit for a sale is 10% of the total bid value as submitted by the apparent high bidder (25% if the bidder is a defaulter as defined under WAC 332-140-300) and never less than \$5,000.00 for lump sum sales. For Lump Sum sales appraised at less than \$5,000.00, the entire bid value is due on day of auction.

- a. Apparent high bidders using cash, certified check, cashiers' check or money order as a bid deposit must pay the total Initial Deposit amount by 4:30 p.m. on auction day.
- b. Apparent high bidders using a Timber Sale Per Sale Bid Bond as a bid deposit must pay the difference between the bid deposit and the total initial deposit by 4:30 p.m., on the day of auction. The bid bond amount must be replaced with a certified check, cashier's check, bank draft, cash, money order, or wire transfer within ten days of the auction.
- c. Apparent high bidders using a Timber Sale Statewide Bid Bond must pay the entire Initial Deposit amount by 4:30 p.m. on the day of auction.

Fees due on the day of sale must be paid by 4:30 p.m.

All payments must be in the form of a certified check, cashier's check, bank draft, cash, money order or wire transfer.

Eligibility to Bid

In order to bid on State timber sales you must be:

- 18 years of age (or have a co-signer who meets the eligibility requirements),
- Licensed to do business in the State of Washington,
- Eligible to bid on Export Restricted timber, and
- Capable of meeting all contract obligations.

Authorized Representatives

Companies may only use authorized representatives or company officers to bid on State sales, sign State documents or sign checks. A list of authorized representatives and their specific authorities must be submitted in writing to the Department of Natural Resources Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction. A company owner or officer must sign this submittal.

State of Washington
Department of Natural Resources
Doug Sutherland, Commissioner of Public Lands

SEALED BID FORM

Sale Name _____ Agreement Number _____

_____ hereby submits the following bid for timber.
(Print full, legal company name)

(Street address, City, State, Zip Code)

(Phone Number)

Lump Sum Bid (Not Including Fees) \$ _____ **For Total Sale**

Weight Scale Sale Bid (Not Including Fees) \$ _____ / **Ton**

Scribner Scale Sale Bid (Not Including Fees) \$ _____ / **MBF**

BID DEPOSIT

Bid Deposit Amount: \$ _____

Bid Deposit Type:

- Cash, certified check, cashiers check, or money order
- Per Sale Bid Bond
- Statewide Bid Bond, Number _____

The Successful Bidder agrees to furnish, **within 30 days of confirmation date**, Performance Security acceptable to the State in the amount specified on the Notice of Sale. Performance Security must guarantee performance of all provisions of the contract and payment of any damages caused by operations under the contract or resulting from the successful bidders noncompliance with any rule or law.

Bidder's Warranty and Bid Signature

By signing and submitting this bid as an offer to purchaser forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based upon their own judgments of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, appraisals, pre-bid documentation, or any other representation by the Washington State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid) Date _____

(Print **name and title** of Authorized Representative submitting this bid)

Note: all sales are subject to confirmation by the Commissioner of Public Lands (Refer to RCW 79.15.120)

Instructions For Completing Sealed Bid Form

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks on bid form must be completed including the bid bond number if the bidder is relying upon a bid bond for bid deposit.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box before 10:00 a.m. on the day of auction at the location specified in the Timber Notice of Sale.
 - B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be on the bid bond and timber sale contract. The bid form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Mailed Bids

- A. Bids that are mailed are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED". The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The Sealed Bid Form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope.
 - B. Bids that are mailed will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery. The DNR assumes no responsibility for any delays caused by any delivery service.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Initial Deposit:

Lump Sum Sales - Initial Deposit must equal 10% of the total bid submitted.
(25% if the bidder is a defaulter as defined under WAC 332-140-300)

Weight Scale Sales - Initial Deposit must equal 10% of the bid per ton multiplied by the total sale estimated tonnage. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

Scribner MBF Scale Sales - Initial Deposit must equal 10% of the bid per MBF multiplied by the total sale MBF. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

State of Washington
Department of Natural resources
Doug Sutherland, Commissioner of Public Lands

STATEWIDE BID BOND

Bond Number _____

_____ of _____,
(Principal's Name) (City, State)

hereinafter called PRINCIPAL, and _____ hereinafter called SURETY,

a corporation organized under the laws of the State of _____, and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$150,000.00 Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, a venue shall be proper only in Thurston County Superior Court.

Signed, sealed and dated this ____ day of _____, _____.
(month) (year)

This statewide bid bond may be used for bidding between the following dates:

Starting: _____

Ending: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is an apparent high bidder, PRINCIPAL shall before 4:30 p.m., on day of sale, pay to the STATE the amount of the initial deposit in the form of a certified check, cashier's check, bank draft, cash or money order, then this agreement shall be void for the sale on which the payment is made; otherwise, it will remain in force.

SURETY will make payment to the STATE within ten days after demand by the STATE if the PRINCIPAL shall fail to make timely payment as described above.

The SURETY may cancel this bond by sending a written notice to the STATE, not less than forty-five days before a cancellation date; liability shall terminate as to acts or omissions of the PRINCIPAL that occur after the cancellation date.

The PRINCIPAL and the SURETY executed this bond on the date first mentioned.

Principal: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip Code

Surety: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip Code

Surety: (Local Office of Authorized agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

Above

State & Zip

Notary or Company Seal in Space

Instructions For Completing Timber Sale Statewide Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Statewide Bid Bond may be used as bid guaranty on more than one timber sale.
- C. The full legal name and business address of the PRINCIPAL must be inserted where indicated and must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and title must be shown.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as SURETY, it may leave this signature block blank.
- F. This form must be received by the Department of Natural Resources, Product Sales and Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction.
- G. The PRINCIPAL must submit a list of authorized bidders with the Statewide Bid Bond Form.
- H. **The State reserves the right to reject *incomplete* or *incorrect* bid bond forms, making such forms unacceptable as bid guaranty.**

**State of Washington
 Department of Natural Resources
 Doug Sutherland, Commissioner Of Public Lands**

Timber Sale Per Sale Bid Bond

Bond Number _____

_____ of _____, hereinafter called PRINCIPAL, and _____, hereinafter called SURETY, a corporation organized under the laws of the State of _____ and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$ _____ Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, venue shall be proper only in Thurston County Superior Court.

Signed, sealed, and dated this _____ day of _____, 20____.

BID IDENTIFICATION:

SALES NAME(S)	REQUIRED DEPOSIT	AGREEMENT NUMBER(S)

DATE OF BID: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is the high bidder on the sale(s) identified above and, within ten (10) days of the day of sale, transmits cash, certified check, cashier=s check, bank draft or money order, payable to the STATE, in the amount of the bid guaranty required by the terms of the Notice of Sale, *then* this obligation shall be void; *otherwise*, it shall remain in force.

SURETY will make payment to the STATE within ten (10) days after demand by the STATE whenever the PRINCIPAL shall fail to make timely payment as described above.

IN WITNESS WHEREOF: the PRINCIPAL and the SURETY have caused this bond to be executed on the date first mentioned.

SECOND OFFICER:

Signature: _____

Name: _____

Title: _____

PRINCIPAL: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

SURETY: (Local Office of Authorized Agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

City: _____

State & Zip:

SURETY: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

NOTARY OR COMPANY SEAL IN THE SPACE ABOVE

Instructions For Completing Timber Sale PerSale (s) Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Timber Sale Per Sale Bid Bond may be used as bid guaranty on more than one timber sale auction held the same date at the same location.
- C. The full legal name and business address of the PRINCIPAL must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person, the name typed or printed, and title shown. If PRINCIPAL is a corporation, a second officer must sign in the space to the left of the signature of the officer executing for the PRINCIPAL.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown. If this person is not an officer of the corporation, evidence of authority must be submitted.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as Surety, it may leave the local office signature block blank.
- F. The date of the bid bond must not be later than the auction date.
- G. **The State reserves the right to reject *incomplete or incorrect* bid bond forms, making such forms unacceptable as guaranty.**

Summary Report of All Sales for the Month of November 2007

Board Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clallam	Olympic	81051	LANDING STRIP	4,147	\$412,000.00
Grays Harbor	Pacific Cascade	80641	NEWBIE	4,533	\$1,458,000.00
Jefferson	Olympic	77387	HIVIS	2,372	\$556,000.00
Kitsap	South Puget	78756	YUHU	1,482	\$515,000.00
Klickitat	Southeast	80927	STRANGE BREW	2,546	\$337,000.00
Lewis	Pacific Cascade	81022	RED PANDA HARDWOOD	1,519	\$724,000.00
Pacific	Pacific Cascade	79905	FALLS FORKS	6,441	\$1,223,000.00
Pacific	Pacific Cascade	80874	SUSTAINABLE SALMON	8,140	\$2,139,000.00
Skagit	Northwest	80593	GINGERBREAD HARDWOOD	1,184	\$551,000.00
Skamania	Pacific Cascade	78638	LITTLE TIGER THINNING	1,315	\$270,000.00
Snohomish	Northwest	79721	PORO	3,778	\$606,000.00
Snohomish	Northwest	81039	LOWER MARSH	5,240	\$1,402,000.00
Whatcom	Northwest	80924	WELCOME SOUTH	2,501	\$842,000.00
				=====	=====
			Total	45,198	\$11,035,000.00

Region Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clallam	Olympic	81049	LYRE RAIL COMMERCIAL THINNING	1,050	\$148,000.00
Jefferson	Olympic	81063	ITFT BLOWDOWN	67	\$12,000.00
Klickitat	Southeast	78760	TRUCK SHOP	764	\$122,000.00
Okanogan	Northeast	79914	SWEET N LOW	2,523	\$215,000.00
Snohomish	Northwest	80737	EBEY SWT	1,417	\$147,000.00
Whatcom	Northwest	77837	FORCEPS PC	2,062	\$111,000.00
				=====	=====
			Total	7,883	\$755,000.00

TIMBER NOTICE OF SALE

SALE NAME: *LANDING STRIP*

AGREEMENT NO: *30-081051*

AUCTION: November 27, 2007 starting at 10:00 a.m., **COUNTY:** Clallam
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 8 miles west of Clallam Bay, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags, property lines and the S-1300 Road, except trees marked with blue paint on part(s) of Sections 17 all in Township 32 North, Range 13 West, W.M., containing 96 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Hemlock	15.8	6	3,364						1,236	1,809	319		
Spruce	22.3	5	599						377	204	19		
Douglas fir	20.4	5	104						59	40	4		
Red cedar	16.9		47							38	9		
Red alder	21.2		33						22	5	5		
Sale Total			4,147										

MINIMUM BID: \$412,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$82,400.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$41,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel and Cable methods, with shovel methods restricted to slopes less than 30%. Shovel Yarding will not be permitted from October 15 to April 30 unless authorized in writing by the Contract Administrator.

ROADS: 27.63 stations of optional construction. 11.62 stations of required pre-haul maintenance. 8.0 stations of optional pre-haul maintenance. A 1/2 acre of stripping or reclamation is required in the Box Car or Mary Clark Pit, as directed by the Contract Administrator. Purchaser maintenance on all roads used. Rock haul, pre-haul maintenance and road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 100% GPS'd. Sale area was cruised using a variable plot sample with a BAF of 54.45F on a 330 x 210 foot grid.



FEES: \$54,935.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There is a locked gate at the Mary Clark Pit - contact the Olympic Region Dispatch Center at 360-374-6131, to obtain a AA-1 key.

TIMBER SALE MAP

SALE NAME: LANDING STRIP
AGREEMENT NO: 30-081051
TRUST(S): Capitol Building Grant (07)


REGION: Olympic
COUNTY(S): Clallam



Drawn By: M. Helms
 Date: August 8, 2007
 Scale: 1" = 1000'

500 0 500 Feet

Elevation: 0 - 500'



TIMBER NOTICE OF SALE

SALE NAME: NEWBIE

AGREEMENT NO: 30-080641

AUCTION: November 29, 2007 starting at 10:00 a.m., **COUNTY:** Grays Harbor
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 8 miles southwest of Porter, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber, except leave trees tagged out with yellow leave tree area boundary tags, leave trees marked with blue paint, snags and pre-existing down timber existing 3 years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod, and the L-2100, R-1000, R-1400 and R-1410 roads in Unit #1; all timber, except leave trees tagged out with yellow leave tree area boundary tags, snags and pre-existing down timber existing 3 years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod, and the R-1400 and R-1460 roads in Unit #2 on part(s) of Sections 1 and 12 all in Township 16 North, Range 6 West, W.M., containing 137 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	25.1	6	4,004						2,739	1,144	121	
Red alder	14.5		467						134	191	142	
Hemlock	12.3	7	62						8	40	14	
Sale Total			4,533									

MINIMUM BID: \$1,458,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$145,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with ground-based (shovel and tracked skidders) harvesting equipment being restricted to slopes of 35% and less. Tracked skidding is restricted to the yarding of poles only. See Clause H-140 and Schedule L for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator, this applies to the tracked skidding of poles only.

ROADS: 72.53 stations of optional construction. 15.15 stations of optional reconstruction. 85.45 stations of required pre-haul maintenance. 11.15 stations of optional pre-haul maintenance. 48.90 stations of road deactivation. Provisions for the sale of rock from, and use of, the Minot Peak Rock Quarry are specified in the Weyerhaeuser Company Road Use Permit (File # TH2007-202) on file at the Pacific Cascade Region office. Rock from other sources must be approved, in writing, by the Contract Administrator. Purchaser shall manufacture 13,000 cubic yards truck measure of crushed rock. The Purchaser shall stockpile 2,998 cubic yards of 2½ INCH MINUS CRUSHED rock and 1,732 cubic yards of 4 INCH JAW RUN rock. This rock shall be stockpiled at station 26+31 of the R-2000. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS and traverse. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 60% ground-based and 40% cable harvesting.

FEES: \$50,000.00 is due on day of sale. \$11.22 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Trees marked with blue paint in Unit #2 shall be considered part of the sale volume. Designated haul roads have been designed to allow for the transport of poles 52 feet in length or less. If Purchaser chooses to remove poles greater than 52 feet in length a haul plan must be submitted in writing to the Contract Administrator, which details the desired

TIMBER NOTICE OF SALE




haul route, additional reconstruction needs, and mitigation for damage, which is a result of hauling oversize material. If approved in writing by the Contract Administrator, all work shall be at the expense of the Purchaser.

TIMBER SALE MAP

SALE NAME: NEWBIE
AGREEMENT NO: 30-080641
TRUST(S): Common School (03)

REGION: Pacific Cascade
COUNTY(S): Grays Harbor

Township 16 North, Range 06 West, W.M.



Drawn By: Shawn B.
 Date: August 7, 2007
 Scale: 1" = 1000'
 Elevation: 360ft. - 1,080ft.

TIMBER NOTICE OF SALE

SALE NAME: HIVIS

AGREEMENT NO: 30-077387

AUCTION: November 27, 2007 starting at 10:00 a.m., **COUNTY:** Jefferson
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 3 miles southwest of Quilcene, WA

PRODUCTS SOLD AND SALE AREA:

All timber bounded by timber sale boundary tags, logged areas, and special management unit boundary tags, except trees marked with blue paint or bounded by leave tree area tags in Unit 1; all timber as described in Schedule B, bounded by timber sale boundary tags, logged areas and special management unit boundary tags except those trees as described in Schedule A in Unit 2; all timber bounded by timber sale boundary tags and special management unit boundary tags, except trees marked with blue paint or bounded by leave tree area tags in Unit 3; all timber bounded by timber sale boundary tags, except trees marked with blue paint or bounded by leave tree area tags in Unit #4; all timber marked with red paint, bounded by timber sale boundary tags, and special management unit boundary tags in Unit 5; all timber bounded by right of way boundary tags on part(s) of Sections 26 and 27 all in Township 27 North, Range 2 West, W.M., containing 82 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	19.3	18	2,004	\$256.50			31	227		1,095	547	103	
Hemlock	12.2	15	297	\$41.00						67	185	44	
Red cedar	11.7		61	\$449.00							37	24	
Red alder	16.1		6	\$300.00							4	2	
Maple	21.6		4	\$300.00							4		
Sale Total			2,372										

MINIMUM BID: \$256.50/MBF (est. value \$556,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: March 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$55,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Unit 1 - cable and ground methods as shown on timber sale map (no feller bunchers). Ground yarding restricted to shovel only.

Unit 2 - cable and ground methods as shown on timber sale map (feller bunchers allowed). Ground yarding restricted to shovel and/or tracked skidder. A clamping motorized carriage with a 75' lateral yarding capability must be used.

Units 3 and 5 - cable and hand falling methods only.

Unit 4 - ground methods (feller bunchers allowed) Ground yarding restricted to shovel and/or tracked skidder.

Feller buncher operations are only allowed in ground method areas on slopes less than 40%.

A 90 foot tower is recommended in order to achieve lead end suspension. Use of a cable yarding system with a shorter tower may require the use of intermediate supports on a portion of the cable ground. Falling and Yarding will not be permitted from April 1 to June 15 unless authorized in writing by the Contract Administrator in Unit 2 due to the sap flow season

ROADS: 30.19 stations of required construction. 41.70 stations of required reconstruction. 7.02 stations of optional reconstruction. 156.14 stations of required pre-haul maintenance. Road construction activities will not be permitted on weekends or State recognized holidays. Rock haul, reconstruction, pre-haul maintenance and road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.



TIMBER NOTICE OF SALE

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 100% GPS'd. Unit 1 was cruised using a variable plot sample with a BAF of 54.45F on a 400 x 200 foot grid; Units 2 and 3 were cruised using a variable plot sample with a BAF of 40.00F on a 400 x 200 foot grid; Unit 4 was cruised using a variable plot sample with a BAF of 40.00F on a 200 x 200 foot grid; Unit 5 was 100% cruised and the right of way was cruised using a variable plot sample with a BAF of 40.00F.



FEES: \$31,429.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Tailholding outside the sale area will be permitted, however any tailhold or guyline anchor outside the timber sale boundary or in leave tree area must be pre-approved by the Contract Administrator. There is a locked gate located on the Claybanks Road - this gate must remain locked at all times. Contact the Olympic Region's timber sale office at 360-374-6131 to obtain the combination.

TIMBER SALE MAP

SALE NAME: HIVIS
 AGREEMENT NO: 30-077387
 TRUST(S): Forest Board Transfer/Common School

REGION: Olympic
 COUNTY(S): Jefferson



Legend

- ~~~~~ Timber Sale Boundary Tags
- ~~~~~ Special Management Unit Boundary Tags
- Cable
- Ground
- RMZ
- Existing Road
- Required Reconstruction
- Required Construction
- Optional Reconstruction
- Streams
- Stream Type
- Stream Type Break
- Leave Tree Area (bounded by Leave Tree Area Tags)
- Survey Monument
- Wetland
- Rock Pit

Drawn By: M. Helms
 Date: August 17, 2007
 Scale: 1" = 1000'



TIMBER NOTICE OF SALE

SALE NAME: YUHU

AGREEMENT NO: 30-078756

AUCTION: November 27, 2007 starting at 10:00 a.m., **COUNTY:** Kitsap
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 11 miles north of Belfair

PRODUCTS SOLD AND SALE AREA: All timber bounded by white timber sale boundary tags, and property lines marked with yellow flagging, and orange right of way boundary tags, except those trees marked with blue paint or bounded by yellow leave tree area tags with flashers; all timber bounded by orange right of way boundary tags, on part(s) of Sections 18 all in Township 24 North, Range 1 West, W.M., containing 62 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	15.4	9	1,135				17		434	558	126		
Red alder	10.1		239						4	6	229		
Hemlock	11.2		89							62	27		
White pine	15.5		15							15			
Red cedar	13.6		4									4	
Sale Total			1,482										

MINIMUM BID: \$515,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: November 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$51,500.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground based equipment. Ground based yarding may be restricted during wet weather conditions if excessive rutting occurs in the opinion of the Contract Administrator. If Purchaser elects to shovel log, shovel logging shall be in accordance with the attached Schedule A, which is a part of this contract. Falling and Yarding will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends, state recognized holidays and weekdays from 7pm to 7am.

ROADS: 60.54 stations of required reconstruction. 25.39 stations of optional construction. 25.39 stations of abandonment, if constructed. Purchaser maintenance on the GM 9 Road and Spur 1. Road construction will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends, state recognized holidays and weekdays from 7pm to 7am. The hauling of forest products will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends, state recognized holidays and weekdays from 7pm to 7am.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by traversing boundaries with GPS in Unit #1. R/W acreage was determined by traversing boundaries by multiplying length x width. Unit #1 was cruised using a variable plot sample with a BAF of full 40.00 and full 27.78 on a 300x150 foot grid. R/W was cruised using an Individual Tree Sample with a BAF of 10 with a plot ratio of 1 in 10 with a total of 4 plots.

FEES: \$19,637.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: There is 300+ mbf of high quality Douglas-fir within the sale area based on the cruise. This sale has an extreme hazard abatement requirement along the northwest boundary line. Directional yarding away from low wet areas will be required. Skid trail design will require approval from the Contract Administrator.

TIMBER SALE MAP

SALE NAME: YUHU
 AGREEMENT NO: 30-078756
 TRUST(S): FOREST BOARD TRANSFER (01)

REGION: SOUTH PUGET SOUND REGION
 COUNTY(S): KITSAP

TOWNSHIP 24 NORTH, RANGE 1 WEST, W.M.




LEGEND

- ~~~~~ White Timber Sale Boundary Tags
- ~~~~~ Property Line marked with yellow flagging
- ~~~~~ Orange Right of Way Boundary Tags
- ==== Existing Road
- Required Reconstruction
- Optional Construction
- ▨ Sale Area
- ▤ Riparian Management Zone
- 🌲 Leave tree clumps marked with yellow leaf tree area tags
- ⚡ Wetlands
- ⛏ Rock Pit
- 3 Water Type
- ◆ Survey Corner
- Streams
- Locked Gate: Master 786

Drawn By: A. Mainwaring
 Date: May 22, 2007

VICINITY MAP Not to Scale



TIMBER NOTICE OF SALE

SALE NAME: *STRANGE BREW*

AGREEMENT NO: *30-080927*

AUCTION: November 27, 2007 starting at 10:00 a.m., Southeast Region Office, Ellensburg, WA **COUNTY:** Klickitat

SALE LOCATION: Sale located approximately 17 miles north of Lyle WA

PRODUCTS SOLD AND SALE AREA: All live standing timber marked with orange paint bounded by white timber sale boundary tags on Unit #1; all live standing timber NOT marked with blue paint bounded by white timber sale boundary tags on Unit #2; and all timber bounded by orange right of way boundary tags on part(s) of Sections 5 all in Township 4 North, Range 13 East, Sections 2 all in Township 4 North, Range 12 East, W.M., containing 334 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade									
					1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	12.8	12	997	\$242.00						167	693	137		
Grand fir	13		92	\$76.00							80	12		

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	\$/Ton	MBF by Grade								
						P	SM	1S	2S	3S	4S	5S	6S	UT
Ponderosa pine	17.1		878	\$94.00						13	865			
Ponderosa pine	8		579		\$2.00									
Sale Total			2,546											

MINIMUM BID: \$242/MBF (est. value \$337,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$67,400.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$33,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Rubber tired skidder or tractor no larger than a D-5 cat or equivalent. Falling and Yarding will not be permitted from November 30 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions.

ROADS: 78.40 stations of required construction. 25.00 stations of required reconstruction. 15.00 stations of required pre-haul maintenance. 118.40 stations of required light abandonment. Prospective purchasers should review road plan. Road construction will not be permitted from October 31 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions. The hauling of forest products will not be permitted from November 30 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions.

ACREAGE DETERMINATION

CRUISE METHOD: Acres were determined using a GPS. Cruise was done using a variable plot method and graded in 32' logs, except for ponderosa pine which used 16' log grades.

FEES: \$33,735.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Flat tractor logging ground with little road construction. Unit #1 - orange painted take trees. Unit #2 - blue painted leave trees. No Douglas-fir, ponderosa pine or larch with a diameter of 28 inches and larger and more than 160 years old will be cut. On the day of sale Purchaser shall pay \$1,000.00 for utility wood. Utility yarded to or produced at landing will be separately decked and approved by the Contract Administrator prior to haul. Ponderosa pine 6-10" will be paid for on a per ton basis, approximately 3227 tons at \$2.00 per ton plus \$1.25 per ton in fees.

TIMBER SALE MAP

August 30, 2007

Sale Name : Strange Brew

Region : Southeast


Agreement # : 30-080927

County : Klickitat

Trusts : State Forest Board Transfer (1)

Unit : 1

Township 04 Range 13 East, Section 5



1: 12,000 One inch equals 1,000 feet

Elevation Range: 2240' - 2360'



* Bounded by Right of Way Tags

- x— Fence
- ~~~~ Timber Sale Boundary
- New Construction*
- ==== Reconstruction*
- ... Prehaul maintenance
- Existing Roads
- County Road
- XXXXX ELZ

TIMBER SALE MAP

August 11, 2007

Sale Name : Strange Brew

Region : Southeast


Agreement # : 30-080927

County : Klickitat


Trusts : State Forest Board Transfer (1)

Unit : 2

Township 04 Range 12 East, Section 2



1: 12,000 One inch equals 1000 feet



- ~~~~ Timber Sale Boundary
- - - New Construction*
- = = = Prehaul maintenance
- ==== Existing Roads
- == County Road
- *-* Fence

Elevation Range: 2160' - 2240'

* Bounded by Right of Way Tags

VICINITY MAP

May 21, 2007

Sale Name : Strange Brew



Region : Southeast

Agreement # : 30-080927

County : Klickitat

Trusts : State Forest Board Transfer (1)

Unit : 1 & 2



Legend

Haul Route

Starting in Lyle, travel 0.5 miles northwest to Old Highway 8. Drive 1.1 miles up the hill to the Canyon Road (H-3000). Travel on Canyon Road for 7.1 miles to the Shippey Cutoff. Continue for 1.1 miles on the Shippey Cutoff to the Fisher Hill Road (P-2000). Drive on Fisher Hill North for 4.6 miles. Here you may continue on Fisher Hill for 1 mile to unit 2 or you can turn east over the cattle guard for 3.4 miles to Unit 1.

TIMBER NOTICE OF SALE

SALE NAME: RED PANDA HARDWOOD

AGREEMENT NO: 30-081022

AUCTION: November 29, 2007 starting at 10:00 a.m., **COUNTY:** Lewis
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 12 miles southwest of Mossyrock, WA

PRODUCTS SOLD AND SALE AREA: All timber, except leave trees tagged out with yellow leave tree area boundary tags, leave trees marked with blue paint, snags, pre-existing stumps and pre-existing down timber existing 2 years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod and the W-549 road in Unit #1 on part(s) of Sections 13 and 14 all in Township 11 North, Range 2 East, W.M., containing 76 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Red alder	14.1		1,358						292	291	775		
Hemlock	12.3		90						24	30	36		
Douglas fir	16.5		38						27	7	4		
Cottonwood	25.9		20						17		3		
Red cedar	28.5		13							13			
Sale Total			1,519										

MINIMUM BID: \$724,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$72,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with ground-based harvesting equipment being restricted to slopes of 40% and less during dry soil conditions. See clause H-140 and Schedule L for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Shovel Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 3.16 stations of required reconstruction. 10.04 stations of optional construction. 121.54 stations of required pre-haul maintenance. 29.85 stations of optional pre-haul maintenance. 10.04 stations of road abandonment, if road is built. Rock for construction, reconstruction or pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. Purchaser shall install a 16 foot by 40 foot steel bridge, to be provided by the State, at station 13+23 on the W-549 road as detailed in the Road Plan as part of this contract. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Unit acres were determined by GPS and the sale was cruised using a variable plot method. Harvesting activities are estimated to be 10% cable and 90% ground-based harvesting.

FEES: \$20,127.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: Purchaser shall abate dust on the W-540 road from STA 0+00 to 7+86, as outlined in the Road Plan. This will be achieved by using lignin sulfonate (also know as spent sulfite liquor) or magnesium chloride at a minimum rate of .5 gallons per square yard of road surface. No operations shall occur on any weekends, State recognized holidays, or from 7 p.m. to 7 a.m. on weekdays. See driving map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: RED PANDA HARDWOOD
AGREEMENT#: 30-081022
TRUST(S): Capitol Grant (07) & Scientific School (10)

REGION: Pacific Cascade
COUNTY(S): Lewis
ELEVATION RGE: 1,190ft. - 1,960ft.

Township 11 North, Range 02 East, W.M.



	Sale Area		Required Reconstruction
	Riparian Mgt Zone		Optional Construction
	Leave Tree Area		Old Grade / Trail
	Sale Boundary Tags		Streams
	Leave Tree Area Tags		Stream Type
	Existing Road		Leave Trees
	Required Pre-Haul Maintenance		Bridge Installation
	Optional Pre-Haul Maintenance		Gate




DRIVING MAP

SALE NAME: RED PANDA HARDWOOD
 AGREEMENT#: 30-081022
 TRUST(S): Capitol Grant (07) & Scientific School (10)

REGION: Pacific Cascade
 COUNTY(S): Lewis
 ELEVATION RGE: 1,190ft. - 1,960ft.

Township 11 North, Range 02 East, W.M.



- Highways
- Haul Route
- Milepost
- Distance Indicator
- Gate (PCP 1-1)

DRIVING DIRECTIONS:

From State Route 12 (milepost 83), turn east onto Winston Creek Road
 Head south on Winston Creek Road for 3.7 miles
 Winston Creek Road becomes Salmon Creek Road at Longbell Road
 Follow Salmon Creek Road for 2.8 miles
 Turn left (east) onto the W-540, through two gates for 0.9 miles and through another gate
 Turn left (east) onto the W-549 for 0.3 miles



TIMBER NOTICE OF SALE

SALE NAME: FALLS FORKS

AGREEMENT NO: 30-079905

AUCTION: November 29, 2007 starting at 10:00 a.m., **COUNTY:** Pacific
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 4 miles west of Menlo, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber, except trees marked with blue paint, trees bounded out by leave tree area tags, pre-existing stumps and down timber existing 2 years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod and property line marked with orange paint in Unit #1; timber sale boundary tags, reprod and the A-1100 road in Unit #2; timber sale boundary tags, reprod and the A-400 Ext. road in Unit #3; all timber bounded by right-of-way boundary tags on part(s) of Sections 12 all in Township 13 North, Range 9 West, Sections 7, 17 and 18 all in Township 13 North, Range 8 West, W.M., containing 142 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Hemlock	14.5	9	5,931						2,004	3,283	644		
Spruce	13.4		289						115	144	30		
Red alder	14.8		142					21	18	54	49		
Douglas fir	24.2	7	79						64	12	3		
Sale Total			6,441										

MINIMUM BID: \$1,223,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$122,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel harvesting equipment being restricted to slopes of 35% or less during dry soil conditions. See Clause H-140 and Schedule L for further harvesting specifications. Shovel Yarding will not be permitted from October 15 to May 15 unless authorized in writing by the Contract Administrator.

ROADS: 7.03 stations of required construction. 17.87 stations of required reconstruction. 141.43 stations of optional construction. 133.30 stations of required pre-haul maintenance. 7.70 stations of abandonment. Rock for construction or reconstruction is available at no cost to the Purchaser from the B-1321 pit on State land, located in Section 30, Township 13 North, Range 8 West, W.M. Rock for construction or reconstruction of roads under this contract may also be obtained at no charge to the Purchaser from the existing B-Line stockpile on State land, located in Section 30, Township 13 North, Range 8 West, W.M. Purchaser shall remove no more than 110 cubic yards of 2 1/2 INCH MINUS CRUSHED rock. Rock for construction and reconstruction under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. Purchaser is required to replace an existing 36 inch CMP on the Browning B-Line with a 96 inch by 65 foot CMP and reconstruct road per Site #1 Installation Plan in the Road Plan. Road construction will not be permitted from September 30 to July 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 90% shovel and 10% cable harvesting.

FEES: \$50,000.00 is due on day of sale. \$14.49 per MBF is due upon removal. These are in addition to the bid price.




SPECIAL REMARKS: Timing restrictions are described as no operation of heavy equipment within the critical marbled murrelet nesting season (April 1 to August 31) during the daily peak activity periods (one hour before official sunrise to two hours after official sunrise and one hour before official sunset to one hour after official sunset) within the NW 1/4 of the SW 1/4 of Section 7, Township 13 North, Range 8 West, W.M. See vicinity map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: FALLS FORKS
AGREEMENT NO: 30-079905
TRUST(S): State Forest Board Transfer (01), Common School (03), & Agricultural School (04)


REGION: Pacific Cascade
COUNTY(S): Pacific

Township 13 North, Range 08 West, W.M.



0 500 1,000 1,500 2,000

Feet
 Drawn By: Shawn B. & Paul L.
 Date: August 27, 2007
 Scale: 1" = 1000'
 Elevation: 120ft. - 800ft.



TIMBER NOTICE OF SALE

SALE NAME: SUSTAINABLE SALMON

AGREEMENT NO: 30-080874

AUCTION: November 29, 2007 starting at 10:00 a.m., **COUNTY:** Pacific
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 15 miles east of Naselle, WA

PRODUCTS SOLD AND SALE AREA: All timber, except trees bounded out with yellow leave tree area tags, all downed timber existing 3 years prior to day of sale, snags and pre-existing stumps, bounded by the following: timber sale boundary tags and the 5970 and 5973 roads in Unit #1; timber sale boundary tags and the 5970 and 5973.5 roads in Unit #2; timber sale boundary tags and the 5970 road in Unit #3 on part(s) of Sections 18, 19, 20 and 21 all in Township 11 North, Range 7 West, W.M., containing 118 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade									
					1P	2P	3P	SM	1S	2S	3S	4S	UT	
Hemlock	16.9	8	4,511	\$172.00				35		2,147	2,107	222		
Douglas fir	25.1	8	3,340	\$356.00						2,595	714	31		
Red alder	16.3		214	\$621.00					12	36	88	78		
Red cedar	16.6		75	\$551.00							54	21		
Sale Total			8,140											

MINIMUM BID: \$356/MBF (est. value \$2,139,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: May 31, 2010 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$213,900.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel harvesting equipment being restricted to slopes of 40% and less during dry soil conditions. See Clause H-140 and Schedule L for further harvest specifications. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Shovel Yarding will not be permitted from September 30 to March 31 unless authorized in writing by the Contract Administrator.

ROADS: 20.29 stations of optional construction. 379.37 stations of required pre-haul maintenance. 20.29 stations of road abandonment, if road is built. Rock for construction and pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. The Purchaser shall stockpile 2,000 cubic yards of 1½ INCH MINUS CRUSHED rock which is to be stockpiled on the 5973-A5 road as directed by the Contract Administrator. Purchaser shall apply two 2-inch layers of Class B concrete asphalt to 12.65 stations of the 4900 road as described in the Road Plan. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator on the 5900 road in all Units

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by GPS. Cruise was completed using variable plot cruise methods. Harvesting activities are estimated to be 75% cable and 25% shovel harvesting.

FEES: \$50,000.00 is due on day of sale. \$16.11 per MBF is due upon removal. These are in addition to the bid price.





SPECIAL REMARKS: Intermediate supports may be required to prevent soil rutting in Unit #2, off the 5973.5 road. No operations will be permitted, including cable lines, east of the Unit #2 boundary.

TIMBER SALE MAP

SALE NAME: SUSTAINABLE SALMON
AGREEMENT NO: 30-080874
TRUST(S): State Forest Board Purchase (02)

REGION: Pacific Cascade
COUNTY(S): Pacific

Township 11 North, Range 07 West, W.M.



0 500 1,000 1,500 2,000
 Feet
 Drawn By: Shawn B.
 Date: April 11, 2007
 Scale: 1" = 1000'
 Elevation: 520ft. - 1,040ft.

TIMBER NOTICE OF SALE

SALE NAME: GINGERBREAD HARDWOOD

AGREEMENT NO: 30-080593

AUCTION: November 26, 2007 starting at 10:00 a.m., **COUNTY:** Skagit
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 6 miles NE of Sedro Woolley

PRODUCTS SOLD AND SALE AREA: All timber bounded by white timber sale boundary tags, the CR-ML Road, the CR-33 Road, recently harvested areas and young stands, except trees marked with blue paint on the bole and root collar, and forest products tagged out by yellow leave tree area tags on part(s) of Sections 2 and 3 all in Township 35 North, Range 5 East, Sections 34 and 35 all in Township 36 North, Range 5 East, W.M., containing 55 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Red alder	15		879						316	165	397		
Red cedar	14		138							105	33		
Cottonwood	27		107	49				39	9		10		
Hemlock	11	5	49							26	24		
Douglas fir	12	5	10						5	2	3		
Maple	20		1								1		
Sale Total			1,184										

MINIMUM BID: \$551,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$55,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

ROADS: 1.00 stations of required reconstruction. 24.59 stations of optional construction. 24.59 stations of road to be abandoned if built.

Development of an existing gravel source (Section 2 Pit) at milepost 0.3 of the HO-2010 Road will involve processing rock to generate gravel ballast. This rock is available at no cost on State land in Sec. 2, T35N, R6E, W.M.

On site boulders excavated during road construction or reconstruction (CR-34, CR-3402, CR-35, and CR-38 road prisms) may be used as riprap for culvert inlets and outlets.

Total ballast and riprap needed for road work is estimated to be approximately 3,075 cubic yards of ballast and 51 cubic yards of riprap.

Road construction, road reconstruction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 57.6 acres gross. 3.0 acres deducted for green tree retention clumps. 54.6 acres net. Cruised using variable plot method. Expansion factor used is 40.00. Sighting height is 4.5 feet. Grid size plot spacing is 234 x 200feet in the Unit. Plot ratio cruise count is 1:1 in the Unit. 50 plots were taken in the Unit.



FEES: \$15,697.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: None.

TIMBER SALE MAP

SALE NAME: *Gingerbread*
 AGREEMENT NO: 80593
 TRUST(S): *State Forest Board Transfer (01)*

REGION: *Northwest*
 COUNTY(S): *Skagit*



Legend

- Sale Area
- RMZ
- Type 1-5 Streams
- Sale Area Boundary Tags
- Non-Tagged Boundary (Cutline)
- Existing Roads
- Required Reconstruction
- Optional Construction
- Tagged Leave Tree Areas
- Scattered Leave Trees
- Property/Section Corners
- Rock Pit
- Landings
- Bridge
- Gate

Drawn By: C. McDonald
 Date: July 31, 2007
 Scale: 1" = 1000'
 Elevation: 1800 ft.
 Version: 1.3

TIMBER NOTICE OF SALE

SALE NAME: *LITTLE TIGER THINNING*

AGREEMENT NO: 30-078638

AUCTION: November 29, 2007 starting at 10:00 a.m., **COUNTY:** Skamania
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 8 miles northwest of Stevenson, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber as described in Schedule A bounded by the following: timber sale boundary tags and the CG-2050 road in Unit #1; timber sale boundary tags, reprod and the CG-2002 road in Unit #2; timber sale boundary tags and the CG-2002 road in Unit #3; timber sale boundary tags and the CG-2070 and CG-2071 roads in Unit #4; timber sale boundary tags, reprod and the CG-2070 and CG-2070C roads in Unit #5; timber sale boundary tags and the CG-2070 road in Unit #6; timber sale boundary tags and reprod in Unit #7; timber sale boundary tags, reprod and the CG-2070 road in Unit #8; all timber marked with orange paint and within special management boundary tags, except timber marked with blue paint; all timber bounded by right-of-way boundary tags. Any spur road or portion of spur road not constructed shall be thinned in accordance with the specifications listed in Schedule A. on part(s) of Sections 17 and 18 all in Township 3 North, Range 7 East, Sections 2, 11, 12, 14 and 15 all in Township 3 North, Range 6 East, W.M., containing 124 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	10.6	8	1,166	7,625	\$29.55						93	644	429	
Hemlock	9.4		85	627	\$29.55						9	62	14	
Red alder	12.9		39	279	\$64.00						3	19	17	
Maple	10		13	95	\$64.00							3	10	
Silver fir	9.4		12	80	\$29.55							10	2	
Sale Total			1,315	8,706										

MINIMUM BID: \$29.55/ton (est. value \$270,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$54,000.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: October 31, 2010 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: *Combined* – Silver fir, Hemlock, Douglas fir

BID DEPOSIT: \$27,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with tracked harvesting equipment being restricted to slopes of 35% and less during dry soil conditions. See Clause H-140 and Schedule A for further Harvest specifications.

ROADS: 115.59 stations of required reconstruction. 33.75 stations of optional construction. 4.39 stations of optional reconstruction. 28.51 miles of pre-haul maintenance. Rock for construction, reconstruction, and pre-haul maintenance under this contract may be obtained at no cost to the Purchaser from the State CG 2002 road rock pit located and the existing CG 2060 road stockpile, both located in Section 12, Township 3 North, Range 6 East. 2½ INCH MINUS CRUSHED rock specified in the ROCK LIST under this contract may be obtained from the existing CG 2060 road stockpile. Purchaser shall remove no more than 70 cubic yards of 2½ INCH MINUS CRUSHED rock. Road construction will not be permitted from November 1 to April 15 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by digitized P&T map based on best photo estimate. Cruise was completed using variable plot cruise methods with some units being adjusted for the basal area target. Harvesting activities are estimated to be approximately 45% ground-based and 55% cable.

FEES: \$17,423.75 is due on day of sale. \$1.36 per ton is due upon removal. These are in addition to the bid price.

TIMBER NOTICE OF SALE




SPECIAL REMARKS: Intermediate supports will be needed on some settings to avoid blind leads and maintain lead-end suspension. All leave trees are marked with blue paint in Units #2 and #6. In small gaps, all take trees are marked with orange paint; those trees within the gaps that are not marked shall be left. Large gaps in Unit #3 are bound by blue special management boundary tags; inside these tags, all trees are to be cut except those scattered residual trees marked with blue paint.

TIMBER SALE MAP

SALE NAME: LITTLE TIGER THINNING
AGREEMENT NO: 30-078638
TRUST(S): State Forest Board Transfer (01) & Common School (03)

REGION: Pacific Cascade
COUNTY(S): Skamania

Township 03 North, Range 06 East, W.M.




Drawn By: Shawn B.
 Date: August 30, 2007
 Scale: 1" = 1000'
 Elevation: 720ft. - 2,400ft.

TIMBER SALE MAP

SALE NAME: LITTLE TIGER THINNING
AGREEMENT NO: 30-078638
TRUST(S): State Forest Board Transfer (01) & Common School (03)


REGION: Pacific Cascade
COUNTY(S): Skamania

Township 03 North, Range 06 East, W.M.



Legend

- Thinning Area
- Leave Tree Area
- RMZ
- Sale Boundary Tags (White)
- Leave Tree Tags (Yellow)
- Right of Way Boundary Tags (Orange)
- Existing Roads
- Pre-haul Maintenance
- Required Construction
- Required Reconstruction
- Optional Construction
- Optional Reconstruction
- Old Grade / Trail
- Streams
- Water Type 1 - 5
- Monumented Corner
- Gap (Orange Paint)
- Gap (Special Mgmt Tags)
- Existing Rock Pit



Drawn By: Shawn B.
 Date: July 30, 2007
 Scale: 1" = 1000'
 Elevation: 720ft. - 2,400ft.



TIMBER NOTICE OF SALE

SALE NAME: *PORO*

AGREEMENT NO: *30-079721*

AUCTION: November 26, 2007 starting at 10:00 a.m., **COUNTY:** Snohomish
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 7 miles northeast of Sultan

PRODUCTS SOLD AND SALE AREA:

All timber (which shall also include dead and downed cedar logs and stumps) bounded by white timber sale boundary tags, and the MC-ML Road, except dead and downed cedar stumps and logs marked with blue paint, trees marked with blue paint on the bole and root collar, forest products tagged out with yellow leave tree tags, and forest products tagged out by blue special management tags, in the Unit.

All timber as described for removal in Schedule B located in the WMZ and RMZ areas tagged out by blue special management tags within the Unit.

27 trees marked with orange paint on the bole and root collar located in the WMZ located adjacent to the southern boundary of the Unit.

All timber bounded by orange right of way tags. The above described products on part(s) of Sections all in Township 29 North, Range 8 East, W.M., containing 87 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Hemlock	14	8	2,451						811	1,223	417		
Douglas fir	24	8	690						548	122	20		
Red cedar	11		358							244	114		
Silver fir	15		279						97	113	69		
Sale Total			3,778										

MINIMUM BID: \$606,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$60,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

ROADS: 133.00 stations of required reconstruction. 48.24 stations of optional construction. 48.24 stations of road to be abandoned if built.

Development of an existing hardrock source (MC-3102 Hardrock Pit) at station 12+00 of the MC-31 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate riprap, 2-inch-minus crushed surfacing rock, and 3-inch-minus ballast rock. This rock is available at no cost on State land.

Creation of a stockpile of 500 cubic yards of 2-inch-minus crushed surfacing rock. Stockpile shall be located at the MC-3102 Hardrock Pit.

Road construction, road reconstruction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 90.4 acres gross. 3.3 acres deducted for green tree retention clumps. 87.1 acres net. Cruised using variable plot method. Expansion factor used is 40.00 in WMZ and 54.45 in the Unit. Sighting height is 4.5 feet. Grid size plot spacing is 400 x 200 feet in the Unit. Plot ratio cruise count is 1:1 in the Unit and cruised



TIMBER NOTICE OF SALE

all in the WMZ. 36 plots were taken in the Unit, and 9 plots taken in the WMZ, for a total of 45 plots.

FEES: \$50,058.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: None.

Schedule B
Poro - RMZ/WMZ Thinning

RMZ/WMZ PRESCRIPTION:

Cut all western hemlock (WH) less than 15 inches DBH.

Cut all red alder (RA) and big leaf maple (BM), if present.

Leave all Douglas-fir (DF) and western redcedar (RC), except those located in yarding corridors.

SPECIAL THINNING CONDITIONS:

In areas where thinning is not necessary, i.e., prescription is met, do not put in yarding corridors or skid trails. These areas must be identified and agreed upon in advance with the Contract Administrator.

Trees marked with blue special management area tags may be removed if they either meet the prescription or are necessary for yarding corridors.

GROUND YARDING CORRIDORS:

Corridors are limited to 14 feet wide (including rub trees) and no less than 70 feet apart as measured from the center of the corridor. Where possible corridors should be located in a manner to minimize the damage to or removal of leave trees. No yarding will take place on slopes greater than 25%.

CABLE CORRIDORS:

Landings will be located to provide for parallel yarding corridors whenever possible. Corridors will be limited to 12-feet including rub trees. Corridors will be at least 100 feet apart when parallel as measured from the center of the corridors. When radial yarding corridors are required from a central landing, the distance between yarding corridors must be no closer than 100 feet where the corridor leaves the unit as measured from the center of the corridors. Where possible corridors should be located in a manner to minimize the damage to or removal of leave trees. When corridors are field located, only leave trees within 3 – 5 feet of the center of the corridor should be removed prior to yarding. Following completion of yarding of each corridor, rub trees within 6 feet of the center of the corridor may be felled and yarded to the landing. It is not required to remove all leave trees from the 12-foot corridor.

COMPARTMENTS FOR ASSESSMENT OF DAMAGE:

All RMZ/WMZ where thinning will take place will be considered one compartment.

DOWN WOOD AND SNAG RECRUITMENT:

Two trees per acre (34 total trees) are to be directionally felled toward the nearest stream and left on the ground for down woody debris. These trees have been marked with the letter "F" with orange paint. The Purchaser must obtain written approval from the Contract Administrator prior to felling these trees. This approval shall specify what method will be used to ensure that these trees are not removed with prescription trees to be harvested. It may be necessary for a faller to hand fell these trees after all other prescription trees have been removed.

Three trees per acre (51 total trees) are to be topped above 20' (higher if possible) for snag recruitment. These trees have been marked with the letter "S" in orange paint. These trees have generally been located in the outer portion of the stream buffers, with the intent of permitting a feller-buncher to fell the prescription and top these trees. If it is not possible for the feller-buncher to reach any trees marked with the letter "S", the Purchaser may top a suitable replacement with written approval from the Contract Administrator.

CERTIFICATION OF FALLERS AND YARDER OPERATORS

The Contract Administrator and faller/harvester operator will jointly review the take tree selection criteria as outlined in Schedule B of the sale contract.

In conjunction with the Contract Administrator, the faller/harvest operator will mark a designated area as a test plot within the sale area boundary. Satisfactory thinning of the test plot completes the certification process.

Certifications will be issued to individuals when they demonstrate to the Contract Administrator their ability to perform within the requirements set forth in the contract.

All persons engaged in the felling and yarding of timber must receive certification in writing from the Contract Administrator. Certification may be revoked when the Contract Administrator determines that non-compliance of leave tree selection criteria or cut tree selection criteria is occurring, or excessive damage to leave trees or skid trails is occurring.

When leave tree damage exceeds the limits set forth in clause below, Purchaser shall be subject to liquidated damages set forth below.

LEAVE TREE DAMAGE DEFINITION

Leave tree damage exists when one or more of the following criteria are satisfied as a result of Purchaser's operation:

- a. A leave tree has one or more scars on its trunk exposing the cambium layer, which in total exceeds 100 square inches.
- b. A leave tree top is broken or the live crown ratio is reduced below 30 percent.
- c. A leave tree has more than 1/3 of the circumference of its root system injured such that the cambium layer is exposed.

Excessive damage is established when more than 5 percent of the leave trees are damaged in a unit. The damaged trees will be identified by the Contract Administrator.


LEAVE TREE EXCESSIVE DAMAGE

When Purchaser's operations exceed the damage limits set forth above, Leave Tree Damage Definition, the trees damaged result in substantial injury to the State. The value of the damaged leave trees at the time of the breach is not readily ascertainable. Therefore, Purchaser agrees to pay the State as liquidated damages at the rate of \$100 per tree for all damaged trees in the unit.

TIMBER SALE MAP

SALE NAME: Poro
AGREEMENT NO: 30-079721
TRUST(S): 01 Forest Board Transfer
 03 Common School Indemnity

REGION: Northwest
COUNTY(S): Snohomish
ELEVATION: 1300' - 1700'




1000 0 1000 Feet

Legend

- Gate
- ⊗ Rock Pit
- * Water Type Break
- 🌲 Tagged Leave Tree Area
- × Orange Painted Take Trees
- ⊕ Landing
- ⏟ Wetlands
- ③ Water Type
- ✓ Equipment Crossing
- ⊕ HCP Cliff
- ⊕ Small Cave (mine shaft)
- ◆ Survey Monument
- Ⓢ Waste Area
- Timing Restricted Area to South
- Existing Road
- - - Optional Construction
- ▭ Required reconstruction
- ➔ Type 1-5
- Wetland Boundary
- ~ ~ ~ Management Unit Boundary Tags
- ~ ~ ~ Sale Boundary Tags
- ~ ~ ~ Right-of-Way Boundary Tags
- ▨ Cable
- ▨ Shovel
- ⋯ RMZ/WMZ

Vicinity Map not to scale



← 1 mile to Sultan

Drawn By: Calvin Ohlson-Kiehn
Date: October 30, 2006
Scale: 1" = 1000'
Version: 1.0

TIMBER NOTICE OF SALE

SALE NAME: LOWER MARSH

AGREEMENT NO: 30-081039

AUCTION: November 26, 2007 starting at 10:00 a.m., **COUNTY:** Snohomish
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 5 miles north of Sultan

PRODUCTS SOLD AND SALE AREA:

All timber bounded by white timber sale tags, adjacent young stands, and the MC-22 and MC-2212 roads, except trees marked with blue paint on the bole and root collar, forest products tagged out by yellow leave tree area tags, downed cedar stumps and logs with blue paint or located within or extending from areas tagged out by yellow leave tree area tags, and forest products tagged out by blue special management tags, in Unit #1 (Unit #1 collectively labeled #1A, #1B, and #1C).

All timber bounded by white timber sale tags, adjacent young stands, and the MC-05 Road, except trees marked with blue paint on the bole and root collar, forest products tagged out by yellow leave tree area tags, downed cedar stumps and logs with blue paint or located within or extending from areas tagged out by yellow leave tree area tags, in Unit #2.

All timber as described for removal in Schedule B located in the two WMZ areas tagged out by blue special management tags within Unit #1 (one is within the western portion of Unit #1 labeled WMZ A and one is located in the eastern portion of Unit #1 labeled WMZ B on the prospectus map).

The above described products on part(s) of Sections 4 and 5 all in Township 28 North, Range 8 East, Sections 32 and 33 all in Township 29 North, Range 8 East, W.M., containing 106 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	21	8	3,022			57	571			1,458	805	131	
Hemlock	16	8	2,082							1,018	839	225	
Red cedar	12		117								80	37	
Cottonwood	28		19					12	7				
Sale Total			5,240										

MINIMUM BID: \$1,402,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$140,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY in the Units except the WMZs) to reduce soil damage and erosion. Ground-based harvest operations in the area tagged out with blue special management unit boundary tags will be allowed ONLY between June 1 and October 15. Ground-based operations will NOT be permitted in the portion of WMZ marked by two special management unit boundary tags, or areas where the slope exceeds 25%. Cutting and yarding beyond blue special management unit boundary tags will not be permitted during the bark slippage season unless authorized in writing by the Contract Administrator. This season is estimated to run from April 1 to July 15 but will vary dependent on weather conditions. If permission is granted to operate during the bark slippage season the purchaser will be required to provide a plan outlining mitigation measures.

ROADS: 23.00 stations of required construction. 64.37 stations of required reconstruction. 73.91 stations of optional construction. 6.02 stations of optional reconstruction. 15.52 stations of existing road to be abandoned. 73.91 stations of road to be abandoned if built.

Development of an existing hardrock source (MC-3102 Hardrock Pit) at station 12+00 of the MC-31 road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 120 cubic yards of rip rap and approximately 11,440 cubic



TIMBER NOTICE OF SALE

yards of 3-inch-minus ballast rock. This rock is available at no cost on State land in section 28 of T29N R08E.

Road construction and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 112.7 acres gross. 7.0 acres deducted for green tree retention clumps and existing roads. 105.7 acres net. Cruised using variable plot method. Expansion factor used is 54.45 for Units 1 and 2 and 40.00 for the WMZ. Sighting height is 4.5 feet. Grid size plot spacing is 400 X 200 feet in Units 1, 2, and WMZ. Plot ratio cruise count is 1:2 in Unit 1 and 1:1 in Unit 2. Cruised all in WMZ. 35 plots were taken in Unit 1, 10 plots in Unit 2, and 7 plots in WMZ, for a total of 52 plots.

FEES: \$69,439.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: (1.) An on-site pre-work meeting shall be scheduled with the Contract Administrator, which shall include the operator and fallers, prior to commencement of any activities on site. (2.) The WMZ area tagged out by a set of two blue special management tags (i.e. two blue tags per tree) represents an equipment limitation zone in the WMZ. Ground-based operations will not be permitted in this area.

Schedule B
Lower Marsh - WMZ Thinning

Thinning Prescription

WMZ PRESCRIPTION:

Cut all western hemlock (WH), Douglas-fir (DF), and black cottonwood (CW) that are less than or equal to 19.0 inches DBH. Retain all Sitka spruce (SS) and western redcedar (RC).

SPECIAL THINNING CONDITIONS:

In areas where thinning is not necessary, i.e., prescription is met, do not put in yarding corridors or skid trails. These areas must be identified and agreed upon in advance with the Contract Administrator. Trees marked with single or double blue special management tags along the WMZ boundary may be removed if they either meet the prescription as described in this Schedule B, or are necessary for yarding corridors.

GROUND YARDING CORRIDORS:

Corridors are limited to 14 feet wide (including rub trees) and no less than 70 feet apart as measured from the center of the corridor. Where possible, corridors should be located in a manner to minimize the damage to or removal of leave trees. No ground yarding will take place on slopes greater than 25%.

CABLE CORRIDORS:

Landings will be located to provide for parallel yarding corridors whenever possible. Corridors will be limited to 12-feet including rub trees. Corridors will be at least 100 feet apart when parallel as measured from the center of the corridors. When radial yarding corridors are required from a central landing, the distance between yarding corridors must be no closer than 100 feet where the corridor leaves the unit as measured from the center of the corridors. Where possible, corridors should be located in a manner to minimize the damage to or removal of leave trees. When corridors are field located, only leave trees within 3 – 5 feet of the center of the corridor should be removed prior to yarding. Following completion of yarding of each corridor, rub trees within 6 feet of the center of the corridor may be felled and yarded to the landing. It is not required to remove all leave trees from the 12-foot corridor.

COMPARTMENTS FOR ASSESSMENT OF DAMAGE:

All WMZ where thinning will take place will be considered one compartment.

CERTIFICATION OF FALLERS AND YARDER OPERATORS

All persons engaged in the felling and yarding of timber must receive certification in writing from the Contract Administrator. Certification may be revoked when the Contract Administrator determines that non-compliance of leave tree selection criteria or cut tree selection criteria is occurring, or excessive damage to leave trees or skid trails is occurring.

When leave tree damage exceeds the limits set forth in clause below, Purchaser shall be subject to liquidated damages set forth below.

LEAVE TREE DAMAGE DEFINITION

Leave tree damage exists when one or more of the following criteria are satisfied as a result of Purchaser's operation:

- a. A leave tree has one or more scars on its trunk exposing the cambium layer, which in total exceeds 100 square inches.
- b. A leave tree top is broken or the live crown ratio is reduced below 30 percent.
- c. A leave tree has more than 1/3 of the circumference of its root system injured such that the cambium layer is exposed.

Excessive damage is established when more than 5 percent of the leave trees are damaged in a unit. The damaged trees will be identified by the Contract Administrator.

LEAVE TREE EXCESSIVE DAMAGE

When Purchaser's operations exceed the damage limits set forth above, Leave Tree Damage Definition, the trees damaged result in substantial injury to the State. The value of the damaged leave trees at the time of the breach is not readily ascertainable. Therefore, Purchaser agrees to pay the State as liquidated damages at the rate of \$100 per tree for all damaged trees in the unit.

The Contract Administrator and faller/harvester operator will jointly review the take tree selection criteria as outlined in Schedule B of the sale contract.


In conjunction with the Contract Administrator, the faller/harvest operator will mark a designated area as a test plot within the sale area boundary. Satisfactory thinning of the test plot completes the certification process.

Certifications will be issued to individuals when they demonstrate to the Contract Administrator their ability to perform within the requirements set forth in the contract.




TIMBER SALE MAP

SALE NAME: Lower Marsh
 AGREEMENT NO: 30-081039
 TRUST(S): Forest Board Transfer (01)

REGION: Northwest
 COUNTY(S): Snohomish
 ELEVATION: 700' to 1,100'



Unit 1 = 68 Acres
 1A = 59.0
 1B = 5.7
 1C = 3.6



Legend

Roads	Symbols
— Existing Road	* Water Type Break
▬ Required Reconstruction	⊕ Landing
=== Required Construction	⊕ Wetlands
--- Optional Construction	③ Water Type
≡≡≡ Optional Reconstruction	⌘ Leave Tree Area
Streams / Wetlands	● Gate
> Type 1-5	Logging Methods
— Wetland Boundary	/// Cable
⋯ WMZ	\\ Shovel
Units	
~ ~ Sale Boundary Tags	
~ ~ Special Management Unit Boundary Tags (1 per tree)	
~ ~ Special Management Unit Boundary Tags (2 per tree)	
— Logged Area/Road Boundary	

Drawn By: Matt Leise
 Date: April 18, 2007
 Scale: 1" = 1000'
 Version 1.2

TIMBER NOTICE OF SALE

SALE NAME: WELCOME SOUTH

AGREEMENT NO: 30-080924

AUCTION: November 26, 2007 starting at 10:00 a.m., **COUNTY:** Whatcom
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 2 miles northeast of Deming

PRODUCTS SOLD AND SALE AREA: All timber bounded by white timber sale boundary tags, young stands, and property lines, except trees marked with blue paint on the bole and root collar and trees tagged out by yellow leave tree area tags, in Unit #1 and #2 on part(s) of Sections 20, 21, 28 and 29 all in Township 39 North, Range 5 East, W.M., containing 56 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	21	9	1,869				603			742	449	75	
Hemlock	15	7	325							157	135	33	
Red cedar	16		156								120	36	
Red alder	13		136							30	68	38	
Maple	9		15									15	
Sale Total			2,501										

MINIMUM BID: \$842,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$84,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

ROADS: 4.69 stations of optional construction. 4.69 stations of road to be abandoned if built. Landing construction at Purchaser designated locations on the D-6100 Road.

Development of an existing gravel source (S-1100 Pit) at milepost 0.4 of the S-1100 Road will involve processing rock to generate gravel ballast. Activities at the pit between December 1 and February 15 may occur only during daylight hours from one hour after sunrise to one hour before sunset. This restriction is a condition of the Hatchery/Bear Creek Roost Bald Eagle Management Plan. This rock is available at no cost on State land in Section 1, Township 39 North, Range 5 East, W.M.

Development of an existing hardrock source (Red Mountain Rock Quarry) at milepost 0.5 of the K-1500 Road will involve drilling, shooting, and processing rock to generate riprap and shot rock for landing construction. This rock is available at no cost on State land in Section 23, Township 40 North, Range 5 East, W.M.

Road construction, road abandonment and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS and Hand traverses. 65.4 acres gross. 9.2 acres deducted for green tree retention clumps, riparian area, and existing roads. 56.2 acres net. Cruised using variable plot method. Expansion factor used is 62.5 in Unit #1 and 54.45 in Unit #2. Sighting height is 4.5 feet. Grid size plot spacing is 240 x 200 feet in Units #1 and #2. Plot ratio cruise count is 1:1 in Unit #1 and Cruised All in Unit #2. 36 plots were taken in Unit #1, and 12 plots taken in Unit #2, for a total of 48 plots.

FEES: \$33,138.25 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

This sale is on lands certified
under the Sustainable Forestry
Initiative® program.
www.aboutsfi.org



WASHINGTON STATE DEPARTMENT OF
Natural Resources

TIMBER NOTICE OF SALE



SPECIAL REMARKS: Trees repainted with black paint are removal trees. Lateral yarding may be necessary in the northeast portion of Unit #2.

TIMBER SALE MAP

SALE NAME: Welcome South
 AGREEMENT NO: 80924
 TRUST(S): Forest Transfer (01), Scientific (10), Indemnity (03)

REGION: Northwest
 COUNTY(S): Whatcom

Township 39 North, Range 5 East, W.M.



Legend

- Existing Roads
- Optional Construction
- Streams
- Sale Boundary Tags
- Logged Area Boundary
- Sale Area
- RMZ
- Survey Monument
- Landing
- Leave Tree Area
- Rock Pit
- Gate
- Water Type Break

Drawn By: T.Klepl
 Date: June 4, 2007
 Scale: 1" = 1000'
 Elevation: 671 - 1805 feet

TIMBER NOTICE OF SALE

SALE NAME: LYRE RAIL COMMERCIAL THINNING

AGREEMENT NO: 30-081049

AUCTION: November 28, 2007 starting at 10:00 a.m., **COUNTY:** Clallam
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 15 miles west of Port Angeles, WA

PRODUCTS SOLD AND SALE AREA: All timber as described in Schedule D, bounded by timber sale boundary tags, management lines, property lines, the PA-J-3000 and the PA-J-3010 Roads in Units 1 and 2 on part(s) of Sections 34 and 35 all in Township 31 North, Range 9 West, W.M., containing 142 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade							UT	
						1P	2P	3P	SM	1S	2S	3S		4S
Douglas fir	10.7	7	749	5,153	\$25.00							301	448	
Spruce	10.8	6	242	1,453	\$5.00							137	106	
Hemlock	10.7	7	38	278	\$5.00							9	29	
Red alder	7.9	7	21	125	\$90.00							9	12	
Sale Total			1,050	7,009										

MINIMUM BID: \$25.00/ton (est. value \$148,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$29,600.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$14,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: 100% ground methods. Ground based yarding equipment restricted tracked skidder with grapple with one end fully suspended. Falling and Yarding will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator. All activities are restricted between one hour before to two hours after official sunrise and from one hour before to one hour after official sunset between April 1 and August 31.

ROADS: 6.61 stations of required construction. 105.97 stations of required pre-haul maintenance. Purchaser maintenance on the PA-J-3000, PA-J-3100 and PA-J-3101 roads and all new construction. Designated maintenance on any other roads used. Road construction and maintenance shall not commence prior to notification of the Crescent Water Association and the BPA - see road plan for details. No road construction activities on weekends or State recognized holidays. Purchaser is required to install a temporary 3 foot diameter culvert - see road plan for details. Road construction will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator. All activities are restricted between one hour before to two hours after official sunrise and from one hour before to one hour after official sunset between April 1 and August 31.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 90% photo traversed and 10% GPS'd. Units were cruised using a variable plot sample with a BAF of 20 on a 300' grid.




FEES: \$13,913.00 is due on day of sale. \$1.35 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There are locked gates on the PA-J-3000 Road and the PA-I-2600 (Place Road Pit); contact the Olympic Region Dispatch Center at 360-374-6131 to obtain a AA-1 key. Purchaser must notify the Crescent Water Association and the BPA prior to beginning operations - see the road plan for details.

TIMBER SALE MAP

SALE NAME: LYRE RAIL COMMERCIAL THINNING
 AGREEMENT NO: 30-081049
 TRUST(S): Forest Board Transfer

REGION: Olympic
 COUNTY(S): Clallam



Legend			
~~~~~	Timber Sale Boundary Tags	=====	Existing Road
~~~~~	Management Lines (no tags)	-----	Required Construction
→	Streams	[Hatched Box]	Cable/Forwarder/Processor
[3]	Stream Type	◆	Survey Monument
*	Stream Type Break	⬇	Wetland
●-●-●	Crescent Waterline	[Cross-hatched Box]	Thin to 75 TPA
⊗	Rock Pit		
●-●	Gate		

TIMBER NOTICE OF SALE

SALE NAME: ITFT BLOWDOWN

AGREEMENT NO: 30-081063

AUCTION: November 28, 2007 starting at 10:00 a.m.,
Olympic Region Office, Forks, WA

COUNTY: Jefferson

SALE LOCATION: Sale located approximately 11 miles southwest of Forks, WA

PRODUCTS SOLD AND SALE AREA:

All timber bounded by timber sale boundary tags and the G-2000 Road, except trees marked with blue paint in Unit #1; all timber bounded by timber sale boundary tags, the G-2500 Road, and a property line, except trees marked with blue paint in Unit #2 on part(s) of Sections 6 all in Township 27 North, Range 13 West, Sections 36 all in Township 28 North, Range 14 West, W.M., containing 5 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	12.7	6	33	1					4	21	6	
Douglas fir	14.7	4	32						3	23	5	
Spruce	14.9	4	2							1	1	
Sale Total			67									

MINIMUM BID: \$12,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY:

\$2,400.00

SALE TYPE: Lump Sum

EXPIRATION DATE: December 31, 2007

ALLOCATION: Export Restricted

BID DEPOSIT: \$1,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel methods only.

ROADS: Purchaser maintenance on the G-2000 and G-2500 Roads.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 100% GPS'd.





FEES: \$888.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There is a locked gate located on the G-2000 Road - contact the Olympic Region Dispatch Center at 360-374-6131 to obtain a AA-1 key.


TIMBER SALE MAP

SALE NAME: ITFT BLOWDOWN
AGREEMENT NO: 30-081063
TRUST(S): Common School/University Transfer

REGION: Olympic
COUNTY(S): Jefferson



Drawn By: M. Helms
 Date: July 10, 2007
 Scale: 1" = 1000'



Elevation: 0 - 500'

Legend

- | | | | |
|------|---------------------------|-----|-------------------|
| ~~~~ | Timber Sale Boundary Tags | → | Stream Type |
| ✕-✕ | Property Line | 3 | Stream Type |
| | Sale Area | * | Stream Type Break |
| | RMZ | ◆ | Survey Monument |
| == | Existing Road | ●-● | Gate |

TIMBER NOTICE OF SALE

SALE NAME: TRUCK SHOP

AGREEMENT NO: 30-078760

AUCTION: November 27, 2007 starting at 10:00 a.m., Southeast Region Office, Ellensburg, WA **COUNTY:** Klickitat

SALE LOCATION: Sale located approximately 12 miles southeast of Glenwood WA

PRODUCTS SOLD AND SALE AREA: All live standing timber NOT marked with orange paint bounded by white timber sale boundary tags on Unit #1 and Unit #2 and all timber bounded by orange right of way tags on part(s) of Sections 36 all in Township 6 North, Range 13 East, W.M., containing 159 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	10.6	14	653	6,326	\$19.00						45	410	198	

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade							
						P	SM	1S	2S	3S	4S	5S	6S
Ponderosa pine		11	111	1,026	\$2.00						8	103	
Sale Total			764	7,352									

MINIMUM BID: \$19/ton (est. value \$122,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$24,400.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: November 30, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$12,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Rubber tired skidder or tractor no larger than a D-6 cat or equivalent. Falling and Yarding will not be permitted from October 31 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions.

ROADS: 65.89 stations of required construction. 5.41 stations of required reconstruction. 5.00 stations of required pre-haul maintenance. Prospective purchasers should review the road plan in detail. Purchaser must supply and apply 165 CY of ballast rock from a commercial source. Road construction will not be permitted from October 31 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions. The hauling of forest products will not be permitted from October 31 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions.

ACREAGE DETERMINATION

CRUISE METHOD: Acres were determined using survey data and Garmin and Trimble GPS. Cruise was done using a variable plot method and 32' logs except for ponderosa pine which used 16' logs.

FEES: \$10,120.00 is due on day of sale. \$0.93 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There is a locked gate on the P-1800 road. Contact the region office for access information. Purchaser shall scatter slash and construct water bars on skid trails on approximately 14 acres in Units #1 and #2 as designated by the Contract Administrator. Purchaser will not be able to start work within 1/2 mile of the sale from April 1 to August 31 due to Goshawk and western gray squirrel restrictions. No ponderosa pine or Douglas fir with a diameter of 28" and larger and more than 160 years old will be cut. On the day of sale purchaser shall pay a lump sum amount of \$1000.00 for utility wood. Prior to removal, all utility loads must be decked and approved by the Contract Administrator.


Timber Sale Map

August 30, 2007


Sale Name: Truckshop Timber Sale
 Agreement Number: 30-078760
 Trust(s): (03) Common School

Region: Southeast
 County: Klickitat

Township 6 North, Range 13 East, W.M.



1:12,000



- | | |
|----------------------------------|------------------|
| ~~~~~ Timber Sale Boundary | XXXXXX ELZ |
| - - - Required Construction | → Fish |
| ==== Required Reconstruction | → Non-Fish |
| == Required Pre-haul Maintenance | * Squirrel Nests |
| ==== Existing Roads | |

Elevation Range 1,400' - 2,480'



VICINITY MAP

July 17, 2007

Sale Name: Truckshop Timber Sale


Region: Southeast

Agreement Number: 30-078760

County: Klickitat

Trust: (03) Common School

Township 6 North, Range 13 East, W.M.



1:75,000

0 5,000 10,000 20,000 30,000 40,000 Feet



Travel 0.51 miles east from Glenwood to the Glenwood -Goldendale Highway. Take the Glenwood - Goldendale Highway for 2.6 miles and turn right to the gate just past the mill pond to the P-1000. Continue on P-1000 for 2.4 miles to the P-1800. Continue on the P-1800 for 2.1 miles to the P-8000. Turn onto the P-8000 for 4.5 miles just short of Truckshop's southern boundary. Entrance to Spur A occurs on the P-8000 at 196+50 or at 3.7 miles. Spur C starts on the P-8000 at 227+00 or 4.3 miles in. Spur B starts on the P-8000 at 236+70 or 4.35 miles in on the P-8000.

TIMBER NOTICE OF SALE

SALE NAME: SWEET N LOW

AGREEMENT NO: 30-079914

AUCTION: November 27, 2007 starting at 10:00 a.m.,
Northeast Region Office, Colville, WA

COUNTY: Okanogan

SALE LOCATION: Sale located approximately 6 miles north of Conconully, WA

PRODUCTS SOLD AND SALE AREA:

All green Douglas fir, western larch, and ponderosa pine less than 28 inches in diameter at breast height not banded with purple paint and all other green conifer species not banded with purple paint within Units #1, #2, #3, #4, #5, #6, #8, and #9 bounded by white timber sale boundary tags and red ribbon; all green Douglas fir and western larch less than 28 inches in diameter at breast height not banded with purple paint and all green Engelmann spruce, alpine fir, and lodgepole pine not banded with purple paint within Unit #7 bounded by white timber sale boundary tags and red ribbon; and all timber bounded by road right of way boundary tags on part(s) of Sections 5, 6, 7 and 18 all in Township 36 North, Range 25 East, Sections 1 and 12 all in Township 36 North, Range 24 East, Sections 31 and 32 all in Township 37 North, Range 25 East, W.M., containing 346 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				P	SM	1S	2S	3S	4S	5S	6S	UT
Douglas fir	12.6		1,227		4		299	274	650			
Spruce	12.5		525				16	258	251			
Larch	11.9		380		4		101	65	210			
Alpine fir	10.8		242				5	59	178			
Lodgepole	9.4		102					9	93			
Ponderosa pine	14.8		47						4	43		
Sale Total			2,523									

MINIMUM BID: \$215,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY: \$43,000.00

SALE TYPE: Lump Sum

EXPIRATION DATE: October 31, 2010

ALLOCATION: Export Restricted

BID DEPOSIT: \$21,500.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Rubber tired skidder and Track skidder. If a northern goshawk nesting site is discovered during the spring season, all falling, yarding, hauling, and road work within one half mile of a nesting site will be restricted from March 15 to August 1 or later. Falling and Yarding will not be permitted from March 15 to August 1 unless authorized in writing by the Contract Administrator due to spring breakup and lynx denning restrictions.

ROADS: 7.00 stations of required construction. 535.18 stations of prehaul maintenance required. 40.32 stations of road abandonment required. Rock haul will not be permitted from December 1 to August 1 and on Saturdays and Sundays during the contract period on USFS Roads 38 and 3810 due to spring breakup and USFS recreational restrictions. Road construction will not be permitted from March 15 to August 1 unless authorized in writing by the Contract Administrator due to spring breakup and lynx denning restrictions. The hauling of forest products will not be permitted from December 1 to August 1 unless authorized in writing by the Contract Administrator and on Saturdays and Sundays during the contract period on USFS Roads 38 and 3810 due to spring breakup and USFS recreational restrictions. Purchaser's Contractor shall post "Caution Log Truck" signs on the USFS Road 38 north of the town of Conconully, on the USFS Road 3810 at the junction with USFS Road 38, on the E362423A road, on the E362507A road, and at the junction of the E372516A road and the Sinlahekin County Road.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage determined using GPS methods. Acreage shown above is net harvest acres in harvest units and external road right of ways. There are 370 gross acres which includes other existing road right of ways. All species, except ponderosa pine, 7.0 - 17.5 inches dbh cruised to a 4.6 inch dib top. Ponderosa pine 8.0 - 17.5 inches dbh cruised to 5.6 inch dib top. All species 17.6 inches dbh and greater cruised to 40% of dob at 16 feet.

FEES: \$33,450.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

This sale is on lands certified
under the Sustainable Forestry
Initiative® program.
www.aboutsfi.org



WASHINGTON STATE DEPARTMENT OF
Natural Resources

TIMBER NOTICE OF SALE


SPECIAL REMARKS: Purchaser's contractor shall thoroughly clean all skidding, falling, harvesting, and loading equipment prior to entry onto State land to remove contaminated soils and noxious weed seed. Equipment shall be cleaned at a location approved by the Contract Administrator. Timber sale documents are available at the DNR Product Sales website:
http://www.dnr.wa.gov/htdocs/fr/sales/appraisalpackets/mth_sum.html

Timber Sale Map

SALE NAME: Sweet N Low
 AGREEMENT NO.: 30-079914
 TRUST(S): Indemnity

REGION: NORTHEAST
 COUNTY: Okanogan

Township 36 North, Range 25 East, W. M.
 Township 37 North, Range 25 East, W. M.
 (Map 1 of 2)




**Note: Road details can
 Be found in the
 Road plan in
 The timber sale
 Contract.**

Acres = Net Acres

ROW = 3 Acres

Elevation = 4440' - 4960'

Vicinity Map (not to scale)



- Ground Skidding
- Timber Sale Boundary Tags
- Existing Road
- Prehaul Maintenance
- Stream
- Section/Property Lines
- Fence

Sale Area



Scale: 1" = 1000'
 Drawn By: S. M.
 DATE: 08/14/2007



Timber Sale Map

SALE NAME: Sweet N Low
 AGREEMENT NUMBER: 30 – 079914
 GRANT(S): Indemnity

REGION: NORTHEAST
 COUNTY: Okanogan


Township 36 North, Range 24 East, W. M.
 Township 36 North, Range 25 East, W. M.

(Map 2 of 2)



	Ground Skidding
	Timber Sale Boundary Tags
	Existing Road
	Required Construction
	Prehaul Maintenance
	Lake/Pond
	Section/Property Lines
	Stream
	Fence

Scale: 1" = 1000'
 Drawn By: S. M.
 DATE: 08/30/2007



TIMBER NOTICE OF SALE

SALE NAME: *EBEY SWT*

AGREEMENT NO: 30-080737

AUCTION: November 26, 2007 starting at 10:00 a.m., **COUNTY:** Snohomish
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 13 miles , by road, east of Arlington

PRODUCTS SOLD AND SALE AREA:

All timber as described in Schedule B, except cedar snags, dead and down cedar trees, logs and stumps, bounded by white timber sale boundary tags, the EB-ML and EB-34 roads, and a young stand in Unit #1. All timber as described in Schedule B, except cedar snags, dead and down cedar trees, logs and stumps, bounded by white timber sale boundary tags in Unit #2. All timber as described in Schedule B, except cedar snags, dead and down cedar trees, logs and stumps, bounded by white timber sale boundary tags and the EB-21 road in Unit #3. All timber as described in Schedule B, except cedar snags, dead and down cedar trees, logs and stumps, bounded by white timber sale boundary tags, a young stand, and the EB-2108-03 road in Unit #4. All timber as described in Schedule B, except cedar snags, dead and down cedar trees, logs and stumps, bounded by white timber sale boundary tags and young stands in Unit #5. The above described on part(s) of Sections 19 and 30 all in Township 32 North, Range 7 East, Sections 13, 14, 23, 24 and 25 all in Township 32 North, Range 6 East, W.M., containing 173 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade						UT		
						1P	2P	3P	SM	1S	2S		3S	4S
Douglas fir	10	4	1,153	7,483	\$15.00							622	531	
Hemlock	11	5	248	1,948	\$15.00							112	136	
Red alder	11		15	115	\$54.00									15
Other			1		\$2.00									
Sale Total			1,417	9,546										

MINIMUM BID: \$15/ton (est. value \$147,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$29,400.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: September 30, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Hemlock, Douglas fir combined.

BID DEPOSIT: \$14,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground-based yarding equipment that shall be capable of forwarding the logs (carrying, not skidding) on slopes less than 35% and by cable. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion. Falling and yarding will not be permitted during the bark slippage season unless authorized in writing by the Contract Administrator. This season is estimated to run from April 1 to July 15, but may vary dependent on weather conditions. If permission is granted to operate during the bark slippage season the purchaser will be required to provide a plan outlining mitigation measures.

ROADS: 13.50 stations of optional construction. 24.00 stations of existing road to be abandoned. 13.50 stations of road to be abandoned if built. The optional construction is on an abandoned grade.

Development of an existing hardrock source (EB-2108-03 Hardrock Pit) at milepost 0.3 of the EB-2108 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 18 cubic yards of riprap and approximately 300 cubic yards of 3-inch-minus ballast rock. This rock is available at no cost on State land.

Road construction, road abandonment and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION



TIMBER NOTICE OF SALE

CRUISE METHOD: Acres determined by GIS/orthophoto interpretation. 183.0 acres gross. 172.9 acres net. Cruised using fixed plot method. Expansion factor used is 1/40-acre. Sighting height is 4.5 feet. Grid size plot spacing is 280 x 280 feet in Units #1 - 5. Plot ratio cruise count is Cruised All in Units #1 - 5. 99 plots were taken in total.

FEES: \$18,762.00 is due on day of sale. \$1.34 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: 1). Blue Special Management tags bound equipment exclusion zones only. Tagged trees may only be cut if the trees meet the prescription in Schedule B. (2). Sale was designed with ground-based yarding intended.

Schedule B
Ebey SWT Prescription

GENERAL REQUIREMENTS FOR ALL UNITS

Isolated areas dominated by hardwood species will not be thinned. High-quality red alder scattered throughout the units may be left according to the criteria below. Do not cut any western redcedar. Western redcedar and cherry will not be counted towards leave tree targets.

Timber in the yarding corridor must be felled prior to the falling of adjacent timber.

Ground-based yarding corridors shall not cover more than 20 percent of the total acreage on one unit. If cable yarding is used, cable yarding corridors in combination with any ground-based yarding corridor areas shall not cover more than 20% of the total acreage on one unit.

INDIVIDUAL UNIT PRESCRIPTIONS: LEAVE TREE SPACING

Unit #	Trees Per Acre	Spacing
1	170	16'x16'
2	194	15'x15'
3	120	19'x19'
4	120	19'x19'
5	120	19'x19'

LEAVE TREE DEFINITION

Leave trees in all units will be selected by comparing their characteristics with other trees in the stand. Leave trees will be the best trees from the largest diameter classes available, as uniformly distributed as possible, and free of major defects.

Preferred leave tree species in order of preference are:

1. Western redcedar
2. Douglas-fir
3. Red alder
4. Western hemlock

Best tree definition is having the following characteristics:

1. Best form: tallest tree, straightest boles, and smallest limb diameters.
2. Free of disease, major defect and damage.
3. Fullest and most vigorous crowns.

Uniformly distributed means:

Openings created by felling trees shall not exceed 30 feet between leave trees. If openings in the stand approach this diameter, sufficient trees shall be left on the perimeter of the opening to maintain the appropriate number of trees per acre.

Major defects:

Two or more of the following deformities: forked tops, broken tops, severe cat faces (bark removed on more than half the circumference of the tree), or stem deformities in bole of tree.

GROUND-BASED YARDING CORRIDOR REQUIREMENTS :

A ground-based yarding corridor is defined as an area that is used for more than three passes by any equipment. Ground-based yarding corridors will be limited to 14 feet including rub trees. Corridors will be located to provide for parallel yarding corridors to the extent possible, and will be located at least 70 feet apart as measured from the center of the corridors. Where possible corridors should be located in a manner to minimize the damage to or removal of leave trees. No yarding will take place on slopes greater than 35%.

Tops of trees shall be lopped and scattered where trees are felled and/or placed on skid trails to create a mat for equipment to operate on.

Equipment limitation zones on type-5 streams a have been marked with blue special management tags in unit 1 only. Trees within these areas may be harvested, according to the

prescription, but equipment entry is prohibited except for three designated stream crossings in units 1 and 2.

Stream integrity shall be maintained during all harvest operations. This may require the use of temporary crossing structures (i.e. log cribbing) when water is present. Location of the ground-based yarding corridors, including stream crossings, must be marked by Purchaser and approved by the Contract Administrator.

Purchaser will not have more than two ground-based yarding corridors open to active yarding at any one time. All other ground-based yarding corridors used for yarding timber will not be active.

Once a ground-based yarding corridor is closed, which will include water bars if necessary, Purchaser will not reopen a ground-based yarding corridor unless approved in writing by the Contract Administrator.

Purchaser will suspend operations during periods of wet weather when rutting occurs. Excessive soil damage is not permitted on the ground-based yarding corridor. Ground-based yarding corridor damage is considered excessive when more than 10 percent of the active corridor has ruts over 4 inches in depth.

CABLE HARVESTING REQUIREMENTS:

This sale was designed for ground-based harvesting as described above. However, if the Purchaser chooses to remove timber with cable yarding equipment, the following will apply:

FALLING: Only hand falling will be permitted in areas where cable yarding will be conducted.

CABLE CORRIDORS: Landings will be located to provide for parallel yarding whenever possible. Corridors will be limited to 12 feet including rub trees. Corridors will be at least 100 feet apart when parallel as measured from the center of the corridors. When radial yarding corridors are required from a central landing, the distance between yarding corridor must be no closer than 100 feet where the corridor leaves the unit as measured from the center of the corridors. Where possible, corridors should be located in a manner to minimize the damage to or removal of leave trees. When corridors are field located, only leave trees within 3-5 feet of the center to the corridor should be removed prior to yarding. Following completion of yarding of each corridor, damaged leave trees within 6 feet of the center of the corridor may be felled and yarded to the landing. It is not required to remove all leave trees from the 12-foot corridor.

COMPLIANCE:

A 1/20 acre fixed radius plot (26.3 feet) will be measured to determine trees per acre. Plots will be evenly distributed at a density of at least 2 plots per five acres. The number of trees in a plot will be multiplied by 20 to determine the trees per acre for that plot. The average of all plots in a unit will determine the trees per acre for that unit. Only trees greater than or equal to 7" DBH will be counted towards leave tree targets.

Trees per acre (fixed-radius plots) will be considered a hard target.

CERTIFICATION OF FALLERS AND YARDER OPERATORS (ADDITIONAL REQUIREMENTS BEYOND THOSE OUTLINED IN H-011)

The sale administrator and faller/harvester operator will jointly review the take tree selection criteria as outlined in Schedule B of the sale contract. In conjunction with the sale administrator, the faller/harvest operator will mark a designated area as a test plot within the sale area boundary. Satisfactory thinning of the test plot completes the certification process. Certifications will be issued to individuals when they demonstrate to the contract administrator their ability to perform within the requirements set forth in the contract. Certification may be


revoked when the Contract Administrator determines that non-compliance of leave tree selection criteria, or excessive damage to leave trees or ground-based yarding corridors is occurring.

Excessive damage for leave trees is defined in clause H-012.

TIMBER SALE MAP


SALE NAME: Ebey SWT (Small Wood Thin)
AGREEMENT NO: 30-080737
TRUST(S): Forest Board Transfer (01)

REGION: Northwest
COUNTY(S): Snohomish
ELEVATION: 1000 - 1600 Feet



Legend	
Units	Sale Boundary Tags
~ ~ ~ ~ ~	Management Unit
~ ~ ~ ~ ~	Boundary Tags
~ ~ ~ ~ ~	(Equipment Limitation Zone)
—	Logged Area Boundary
Streams	Type 1-5
Roads	Existing Road
— · — · —	Optional Road Construction
Logging Methods	Ground-Based Yarding
Symbols	
⊕	Landing
⊕	Wetland
*	Water Type Break
3	Water Type
◆	Concrete Monument
◆	Wood Post Monument
⊗	Rock Pit
⊗	Stream Crossing

Drawn By: Greg Anderson
 Date: February 5, 2007
 Scale: 1" = 1000'




TIMBER SALE MAP

SALE NAME: Ebey SWT (Small Wood Thin)
 AGREEMENT NO: 30-080737
 TRUST(S): Forest Board Transfer (01)

REGION: Northwest
 COUNTY(S): Snohomish
 ELEVATION: 1000 - 1600 Feet



Drawn By: Greg Anderson
 Date: January 24, 2007
 Scale: 1" = 1000'



TIMBER NOTICE OF SALE

SALE NAME: FORCEPS PC

AGREEMENT NO: 30-077837

AUCTION: November 26, 2007 starting at 10:00 a.m., **COUNTY:** Whatcom
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 5 miles , by road, northeast of Deming.

PRODUCTS SOLD AND SALE AREA: All timber designated for removal in Schedule B bounded by white timber sale boundary tags and the P-1200 Road. All timber bounded by orange right-of-way tags. The above described products on part(s) of Sections 6 and 7 all in Township 39 North, Range 5 East, W.M., containing 243 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade						UT		
						1P	2P	3P	SM	1S	2S		3S	4S
Hemlock	11	5	1,148	10,170	\$5.65							647	501	
Douglas fir	12	4	610	4,883	\$5.65							247	363	
Silver fir	10		218	1,573	\$5.65							97	121	
Cottonwood	12		50	316	\$25.00						2		48	
Red alder	11		36	395	\$25.00								36	
Sale Total			2,062	17,337										

MINIMUM BID: \$5.65/ton (est. value \$111,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$22,200.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: September 30, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Silver fir, Hemlock, Douglas fir

BID DEPOSIT: \$11,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable in cable areas as designated on the timber sale map and by cable or self-loading, bunk-equipped forwarder in ground based areas. Ground based equipment shall be capable of lifting and transporting (carrying, not skidding) logs free of the ground. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion. Cutting and yarding will not be permitted during the bark slippage season unless authorized in writing by the Contract Administrator. This season is estimated to run from April 1 to July 15 but will vary dependent on weather conditions. If permission is granted to operate during the bark slippage season the purchaser will be required to provide a plan outlining mitigation measures.

ROADS: 22.03 stations of optional construction. 22.03 stations of road to be abandoned if built.

Development of an existing hardrock source (Bummer Pit) at station 52.80 of the P-1300 Road will involve drilling, shooting, and processing rock to generate approximately 28 cubic yards of riprap and approximately 1,586 cubic yards of 3-inch-minus ballast rock. This rock is available at no cost on State.

Road construction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by Hand traverse. 247.2 acres gross. 4.7 acres deducted for existing road and wetland area. 242.5 acres net. Cruised using variable plot method. Expansion factor used is 40.00. Sighting height is 4.5 feet. Grid size plot spacing is 450 x 600 feet in the Units and 300 feet apart in the right of way. Plot ratio cruise count is 24:23 in Unit #1-A and cruised all for the remainder. 65 plots were taken in Units, and 4 plots taken in the right of way, for a total of 69 plots.

FEES: \$27,321.50 is due on day of sale. \$1.07 per ton is due upon removal. These are in addition to the bid price.

This sale is on lands certified
under the Sustainable Forestry
Initiative® program.
www.aboutsfi.org



WASHINGTON STATE DEPARTMENT OF
Natural Resources

TIMBER NOTICE OF SALE

SPECIAL REMARKS: Blue Special Management Tags demarcate an equipment exclusion zone.

Schedule B
Forceps Thinning Prescription

FOREST PRODUCTS SOLD (to be removed)

Remove all hardwood stems except where no conifers exist, hardwood species must be used to fulfill the spacing requirements.

Cut all trees 7" diameter breast height (DBH) and less.

Cut stems greater than 7" to meet the residual stand specifications while retaining the desired leave trees as defined below.

RESIDUAL STAND SPECIFICATIONS

Stand Prescription

1. The residual stand target is required to meet a minimum 160 square feet of basal area and a maximum of 180 square feet of basal area with an average of 130 to 140 trees per acre (TPA) across entire unit (including corridors and R/W area).
2. All Douglas fir greater than 14" DBH are to be left standing unless leaving them results in a residual stand closer than the indicated spacing or trees that are severely deformed as defined above.
3. Do not cut any western red cedar except where required for operational purposes along forwarding trails and cable yarding corridors.

LEAVE TREE DEFINITIONS

Leave trees in all units will be selected by comparing their characteristics with other trees in the stand. Leave trees will be the best trees from the largest diameter classes available.

Preferred leave tree species in order of preference are:

1. Western red cedar
2. Douglas fir
3. Silver fir
4. Sitka spruce
5. Western hemlock

Best tree definition is having the following characteristics:

1. Fullest and most vigorous crowns.
2. Free of disease, major defect and damage.
3. Best form: tallest tree, straightest boles, and smallest limb diameters.

Deformed tree:

Any tree that has forked tops, broken tops, and severe cat faces (bark removed on more than half the circumference of the tree).

Diseased Tree:

Any tree that is infested with Dwarf Mistletoe to the point that at least 2/3's of its crown contains witch brooms.

GENERAL REQUIREMENTS

Cable yarding corridors: Cable yarding corridors will be limited to 12-feet in width including rub trees. Corridors will be at least 100 feet apart when parallel as measured from the center of the

corridors unless approved by the contract administrator. Landings will be located to provide for parallel yarding corridors wherever possible. When radial yarding corridors are required from a central landing, the distance between yarding corridors must be no closer than 100 feet where the corridor leaves the unit as measured from the center of the corridors. Where possible, corridors should be located in a manner to minimize the damage to or removal of leave trees. When corridors are field located, only leave trees within 3 – 5 feet of the center of the corridor should be removed prior to yarding. Following completion of yarding of each corridor, damaged leave trees within 6 feet of the center of the corridor may be felled and yarded to the landing. It is not required to remove all leave trees from the 12-foot corridor.

Ground yarding corridors: Corridors are limited to 14 feet wide (including rub trees) and no less than 70 feet apart as measured from the center of the corridor. Where possible corridors should be located in a manner to minimize the damage to or removal of leave trees.

Openings created by felling trees shall not exceed 30 feet between leave trees. If openings in the stand approach this distance, sufficient trees shall be let on the perimeter of the opening to maintain the appropriate average trees per acre.

COMPLIANCE

On the main body of the sale, variable radius plots will be taken to determine basal area per acre for the unit. Plots will be evenly distributed at a density of at least 2 plots per five acres. Each plot will be measured with a 40 basal area factor (BAF) prism; the number of “in” trees multiplied by 40 will give the basal area for that plot. The average basal area of all plots in the unit will determine if the unit meets its target value. Borderline trees shall be measured at DBH to the face of the tree to the nearest 1/10th inch and multiplied by the plot radius factor of 1.903 to determine limiting distance.

A 1/20 acre fixed radius plot (26.3 feet) will also be measured to determine trees per acre. The number of trees in a plot will be multiplied by 20 to determine the trees per acre for that plot. The average of all plots in a unit will determine the trees per acre for that unit.

Only trees greater than or equal to 7” DBH will be counted towards leave tree targets.

Compartments for assessment of damage
Per contract clauses H-012 and D-040

Compartment A: Cable area west of the P-1000

Compartment B: Ground-based area west of the P-1000

Compartment C: Area located north of Spur A between P-1000 and the eastern wetland and type 4 and 5 streams

Compartment D: Area located south of Spur A between P-1000 and the eastern wetland and type 4 and 5 streams

Compartment E: Area east of eastern wetland and type 4 and 5 streams

CERTIFICATION OF FALLERS AND YARDER OPERATORS (ADDITIONAL REQUIREMENTS BEYOND THOSE OUTLINED IN H-011)

The Contract Administrator and faller/harvester operator will jointly review the take tree selection criteria as outlined in Schedule B of the sale contract.

In conjunction with the Contract Administrator, the faller/harvest operator will mark a designated area as a test plot within the sale area boundary. Satisfactory thinning of the test plot completes the certification process.


Certifications will be issued to individuals when they demonstrate to the Contract Administrator their ability to perform within the requirements set forth in the contract.

TIMBER SALE MAP

SALE NAME: Forceps PC
 AGREEMENT NO: 30-077837
 TRUST(S): Scientific School (10)

REGION: Northwest
 COUNTY(S): Whatcom
 ELEVATION: 2548 feet - 2900 feet

Township 39 North, Range 5 East, W.M.



Legend

Units

- ~~~~~ Sale Boundary Tags
- ~ ~ ~ ~ Management Unit Boundary Tags
- ~~~~~ R/W Boundary Tags

Logging Methods

- //// Cable
- \\ \\ Ground Based

Roads

- ==== Existing Road
- - - - Optional Construction
- Designated Forwarding Trail

Streams

- Type 1-5
- Wetland Boundary


RMZ / WMZ

Symbols

- A** Damage Assessment Compartment
- ◆ Monument
- * Water Type Break
- ⊕ Wetlands
- ⊕ Landing
- 3 Water Type
- Gate

Vicinity Map

- not to scale -



Drawn By: Mark Arneson
 Date: October 25, 2006
 Version: 1.1

